


FILE COPY

Republic of the Philippines
ENERGY REGULATORY COMMISSION
San Miguel Avenue, Pasig City

RECEIVED BY: _____

16 AUG 15 / P 4:52



IN THE MATTER OF THE
APPLICATION FOR APPROVAL
OF EMERGENCY AND/OR
URGENT MAJOR CAPITAL
EXPENDITURE (CAPEX)
PROJECTS,

ERC CASE NO. ~~2016~~ - 161 *Re*

MANILA ELECTRIC COMPANY
(MERALCO),

Applicant.

X-----X

APPLICATION

Applicant **MANILA ELECTRIC COMPANY (MERALCO)**, through the undersigned counsel, and to this Honorable Commission, most respectfully avers that:

1. Applicant MERALCO is a private corporation duly organized and existing under the laws of the Republic of the Philippines, with principal office located at Lopez Building, Ortigas Avenue, Barangay Ugong, Pasig City. It may be served with notices and other processes of this Honorable Commission through its undersigned counsel at the address indicated herein.

2. MERALCO has a legislative franchise to construct, operate and maintain an electric power distribution system for the conveyance of electric power to the end-users in the cities and municipalities of Metro Manila, Bulacan, Cavite and Rizal, and certain cities/municipalities/barangays in Batangas, Laguna, Quezon and Pampanga, pursuant to Republic Act No. 9209.

3. The Application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled: "*Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects*". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.

4. However, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

DISCUSSION OF MERALCO'S EMERGENCY CAPEX PROGRAM

5. MERALCO is part of the First Entry Group of distribution utilities that entered Performance Based Regulation ("PBR"). In its Final Determination dated 6 June 2011 in ERC Case No. 2010-069 RC, the Honorable Commission set out its final position on the price control arrangements that would apply to MERALCO for the Third Regulatory Period (3RP) covering the period from 1 July 2011 to 30 June 2015, including its approval of MERALCO's proposed Capital Expenditure (CAPEX) Program, for the said period.

6. The last year of MERALCO's Third Regulatory Period expired on 30 June 2015. The Fourth Regulatory Period (4RP) for the First Entry Group commenced on 1 July 2015 and will end on 30 June 2019. However, the Honorable Commission has not yet issued the relevant rules to govern the reset process and the filing by the DUs of their reset application.

7. As such, on 9 February 2015, MERALCO filed an application for the approval of its CAPEX program for Regulatory Year (RY) 2016. The said application was docketed as ERC Case No. 2015-016 RC.

8. On 10 April 2015, MERALCO filed an Urgent Motion for Issuance of a Provisional Authority ("Urgent Motion") dated 8 April 2015 requesting that it be allowed to immediately implement its priority projects, the list of which was attached to said Urgent Motion.

9. On 15 April 2015, MERALCO filed a Motion of even date attaching a detailed list showing a further breakdown of the projects into business segments especially those that are shared by different business segments.

10. On 11 June 2015, MERALCO filed a Very Urgent Motion for Authority to Commence Implementation of RY 2016 Priority Projects with an attached list of the RY 2016 priority projects ("Very Urgent Motion").

11. On 2 September 2015, MERALCO again filed a Very Urgent Motion to Resolve, emphasizing the urgency to implement its

CAPEX projects to ensure reliability and quality of service and avoid further delays.

12. On 4 February 2016, MERALCO filed a Manifestation, dated 2 February 2016, informing the Honorable Commission that in the interest of complying with its obligation to provide safe, adequate, reliable and efficient electric service to its customers, Applicant has implemented four (4) of its proposed major CAPEX projects for RY 2016.

13. On 1 April 2016, MERALCO filed another Manifestation of even date informing the Honorable Commission that in the pursuit of its obligation to provide safe, reliable and continuous electric service to its customers, MERALCO was constrained to implement additional priority CAPEX projects to address the need for capacity upgrades in order to avert multiple power interruptions to its customers and maintain a robust electric distribution infrastructure.

14. On 15 June 2016, MERALCO received a copy of the Decision dated 12 April 2016 which partially approved MERALCO's CAPEX program for RY 2016. However, the Honorable Commission also deferred the following projects, without prejudice to refiling:

Project Code	Project Title
MER-2	Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)
MER-4	Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer
MER-11	Rebuilding of Portion of Dasmariñas-FCIE 115kV Line
MER-13	Cut-in of Pinagbuhatan Switching Station
MER-14	Replacement of Power Transformer No.2 at Mandaluyong Substation
MER-15	Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation
MER-20	Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex

15. In the light of said decision, Applicant hereby refiles the following as major emergency capital projects, to wit:

Project Title	Cost (in PhP)
Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	162,580,219.00

Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer	68,161,085.00
Rebuilding of Portion of Dasmariñas-FCIE 115kV Line	75,913,229.00
Replacement of Power Transformer No.2 at Mandaluyong Substation	52,908,466.00

16. We note that these projects, while not emergency at the time of their original filing under ERC Case No. 2015-016 RC, have become critical and had to be immediately implemented as an emergency CAPEX in order to ensure continuous, safe and reliable electric service and compliance with safety and performance standards of the distribution system. More importantly, the immediate implementation of these projects averted emergency conditions or situations, and at the same time, provided the needed capacity intended for the forecasted growth of future electricity demand within MERALCO's franchise area.

17. In addition thereto, MERALCO is also refiling the following major capital projects:

Project Title	Cost (in PhP)
Cut-in of Pinagbuhatan Switching Station	58,635,873.00
Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation	46,443,027.00
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex	118,478,179.00

These projects are necessary to be acquired immediately in order to readily and quickly address contingencies requiring immediate response. The cut-in of Pinagbuhatan Switching Station project is intended to comply with the N-1 contingency and thus address system constraints and deficiencies. In the case of the spare power transformer, the same is urgently needed in order to have a ready replacement in the event of a failure of MERALCO's commissioned 83MVA power transformers. This will definitely prevent any prolonged and sustained power interruption in the event of a transformer failure. On the other hand, the acquisition of the 115kV line and switchyard at Navotas is urgently needed in order to have full control of such asset that are already part of MERALCO's distribution system.

18. In view of the foregoing, MERALCO is refiling the foregoing projects as Emergency/ Urgent Major CAPEX projects. It must be

emphasized that MERALCO's customers benefitted from the implementation of these projects as the integrity and reliability of the distribution system was maintained.

Copies of the different Project Information Summaries with supporting documents: (a) Technical and Economic Analysis; (b) Cost Estimates; (c) Expenditure Summary; (d) Cost Benefit Analysis Calculation; and (e) Gantt Chart of the projects are attached herewith as **Annexes "A" and series** and made integral parts hereof.

19. In further support of the Application, attached hereto as **Annex "B"** is the Judicial Affidavit of Mr. Froilan J. Savet, Senior Assistant Vice-President and Head of MERALCO's Network Planning and Project Management Office.

PRAYER

WHEREFORE, it is respectfully prayed to this Honorable Commission that the instant Application be **APPROVED** and that the building block components associated with the foregoing Major CAPEX projects from the time the same are put in service and considered use and useful be recognized as a deferred amount to be included in MERALCO's subsequent regulatory reset calculations.

Other relief just and equitable under the premises are likewise prayed for.


Pasig City, 12 August 2016.

MANILA ELECTRIC COMPANY

Applicant

MERALCO Compound
Ortigas Avenue, Pasig City

By:



FRANCIS DINO S. ANTONIO

Counsel for Applicant

Roll of Attorneys No. 48145

PTR No. 1473407; 01/21/16; Pasig City

IBP No. 1023724; 01/08/16; RSM

MCLE Compliance No. V-0004608; 6 November 2014



HAZEL ROSE B. SEE

Counsel for Applicant

Roll of Attorneys No. 48265

PTR No. 1473408; 01/21/16; Pasig City

IBP LRN No. 06460; 1/16/07; QC

MCLE Compliance No. V-0002589; 9 June 2014



MONICA M. MARTIN

Counsel for Applicant

Roll of Attorneys No. 55693

PTR No. 1473411; 01/21/16; Pasig City

IBP No. 1023726; 01/08/16; RSM

MCLE Compliance No. V-0002591; 9 June 2014



ADRIAN REX C. DIMALANTA

Counsel for Applicant

Roll of Attorneys No. 61149

PTR No. 1473413; 1/21/16; Pasig City

IBP No. 1023729; 01/08/16; PPLM

MCLE Compliance No. V-0002586; 9 June 2014

7th Floor, Lopez Building, Ortigas Avenue
Brgy. Ugong, Pasig City
Telephone Number 1622-2260; Fax No. 1622-3550

Republic of the Philippines)
Pasig City) S.S.

VERIFICATION AND CERTIFICATE OF NON-FORUM SHOPPING

I, **JOSE RONALD V. VALLES**, Filipino, of legal age and with office address at 7th Floor, Lopez Building, Ortigas Avenue, Pasig City, after being sworn to in accordance with law, hereby depose and say, that –

1. I am the Vice-President and Head of the Regulatory Affairs Office of Applicant Manila Electric Company;

2. I have been authorized by the Board of Directors of the Applicant to cause the preparation and filing of the instant Application. I have read and understood the allegations contained therein and the same are true and correct based on my personal knowledge and authentic records made available to me in the ordinary course of business of the Applicant;

3. I have been authorized by the Board of Directors to certify that Applicant has not heretofore commenced any other action or proceeding involving the same issues in the Supreme Court, the Court of Appeals, or any other tribunal or agency and to the best of my knowledge, no such action or proceeding is pending in the Supreme Court, the Court of Appeals, or any other tribunal or agency. A copy of the Secretary's Certificate authorizing the undersigned to sign this Verification and Certification is attached as **Annex "C"** of this Application and made integral part hereof;

4. Except for the application for the approval of Applicant's Capital Expenditure Program for Regulatory Year (RY) 2016 docketed as ERC Case No. 2016-015 RC, where a decision was already rendered by the Commission and a Motion for Reconsideration was filed by an Intervenor, there is no other similar action or proceedings involving the same subject matter before the Commission or any other tribunal or agency. If I should hereafter learn that a similar action or proceeding has been filed or is pending before the Supreme Court, the Court of Appeals, or any other tribunal or agency, I undertake to report such fact within five (5) days there from to this Honorable Commission.

IN WITNESS WHEREOF, I have hereunto affixed my signature this 12th day of August 2016 at Pasig City, Philippines.


JOSE RONALD V. VALLES

SUBSCRIBED AND SWORN to before me this 12th day of August 2016, by affiant having exhibited his Social Security System (SSS) ID bearing the number 33-10900088.

Doc. No. 244;
Page No. 50;
Book No. IV;
Series of 2016.


ATTY. CARMEN GRACE S. RAMOS
NOTARY PUBLIC
Pasig, Paleros, Taguig & San Juan
Issued on July 13, 2015 at Pasig City
until December 31, 2016
Roll No. 55945; IBP No. 1023723; 01/08/16; RSM Chapter
PTR No. 1473409; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City

**RY2016 CAPEX:
Capital Expenditure Projects**

ANNEX "A"

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 1	EXPANSION OF BAGBAGUIN 115 KV-34.5 KV SUBSTATION (2ND BANK)	April 2016	162,580,219

I. Project Background:

This project was filed as part of Meralco's RY2016 Capital Expenditure application last February 9, 2015. As early as CY2013, it has also been part of the regular annual submission of Meralco's 10-Year Distribution Plan (DDP) to the Department of Energy (DOE). As compared to other alternatives, this project always stood out to be the best solution to address the current problems determined in the area specifically capacity deficiency and critical loading of several distribution facilities in Bagbaguin power transformer bank no. 1, Malinta power transformer bank no. 1 and Balintawak power transformer bank no. 6. Because of the urgent need to address the aforementioned problems, we were constrained to implement the project immediately which is the best alternative among all other options to solve the problems identified in the area.

It was foreseen in RY2014 that the facilities in the area, namely Bagbaguin Power Transformer Bank No. 1 and Malinta Power Transformer Bank No. 1 would reach critical loading. Without this project in RY2016, forecasted loadings of affected power transformer banks will worsen and Balintawak Power Transformer Bank No. 6 will also experience critical loading condition due to load growth in the area served by these power transformer banks.

II. Technical Analysis:

Table I shows the 7-year historical loading of affected banks with impact of the said project in RY2016. The project was immediately started and partially completed last April 2016. The bank accommodated some loads of Bagbaguin power transformer bank no. 1 that resulted in normal operation with 63% loading. With the completion of the remaining project works for Bagbaguin power transformer bank no. 2, Malinta power transformer bank no. 1 and Balintawak power transformer bank no. 6 will also operate in normal loading condition. Residential, commercial and industrial customers benefited from this project are: Liberty Paper Inc., ASA Metal Products, Manly Plastic Inc., First Tandem Steel Resources, Atlas Metal Products Manufacturing Co., Gemsteel Inc., and Filspin Incorporated.

Table II shows the 10-year forecasted loading without the project. In 2016, without project, Bagbaguin power transformer bank no. 1, Malinta power transformer bank no. 1, and Balintawak power transformer bank no. 6 will continue to operate in critical loading condition with 83%, 72%, and 71% loading, respectively. Residential, commercial and industrial customers served by the aforementioned power transformer banks will be affected especially during maintenance or contingencies.

Table I: 7-year Historical Loading of Affected Banks with Impact of the Project for RY2016

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2010		RY 2011		RY 2012		RY 2013	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Bagbaguin Bank 1	83	68.81	83%	65.55	79%	64.54	78%	62.13	75%
Malinta Bank 1	83	70.38	85%	65.00	78%	65.80	79%	52.33	63%
Balintawak Bank 6	83	61.55	74%	57.53	69%	54.60	66%	54.05	65%

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2014		RY 2015		RY 2016	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Bagbaguin Bank 1	83	62.41	75%	68.31	82%	52.34	63%
Malinta Bank 1	83	65.23	79%	58.03	70%	60.04	72%
Balintawak Bank 6	83	55.22	67%	57.69	70%	59.89	71%
Bagbaguin Bank 2	83					18.42	22%

Table II: 10- year Forecasted Loading Without Project

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2016		RY 2017		RY 2018		RY 2019		RY 2020	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Bagbaguin Bank 1	83	68.91	83%	69.68	84%	71.07	86%	72.49	87%	74.67	90%
Malinta Bank 1	83	60.04	72%	62.44	75%	64.94	78%	67.54	81%	70.24	85%
Balintawak Bank 6	83	59.89	71%	64.08	77%	67.29	81%	72.67	88%	75.58	91%

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2021		RY 2022		RY 2023		RY 2024		RY 2025	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Bagbaguin Bank 1	83	77.65	94%	77.76	94%	80.87	97%	84.10	101%	87.47	105%
Malinta Bank 1	83	72.35	87%	75.24	91%	78.25	94%	81.38	98%	83.82	101%
Balintawak Bank 6	83	77.84	94%	80.18	97%	83.39	100%	86.72	104%	89.32	108%

With the completion of all four (4) feeders of this project, voltage regulation will improve in some areas of Valenzuela City, Caloocan City and Quezon City. Also, this project will reduce technical loss by as much as 1,440,042 kilowatt-hour per year (kWh/ yr).

III. Project Alternatives

MERALCO considered three (3) alternatives to address the aforementioned banks, Alternative 1 has least cost in terms of total project and nearest to the target load of Valenzuela City, Caloocan City and Quezon City. Alternative 2 will entail the highest total project cost due to the development of a newly substation, construction of new 115 kV lines and longer distribution lines. Also, Alternative 3 is far more distant from the aforementioned target load that will require longer distribution lines that resulted in more expensive project than Alternative 1. Table III shows the summary of three (3) projects that are evaluated.

Table III: Project Alternatives

Problem Description	The project alternatives intended to address the capacity deficiencies in some area of Valenzuela City, Caloocan City and Quezon City.	
Alternative	Project Name	Classification
1	Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	Stand-alone
2	Development of Bahay Pare 115 kV-34.5 kV Substation	Stand-alone
3	Installation of 1st 83 MVA Power Transformer at Sitio Gitna 115 kV Switching Station	Stand-alone

The descriptions of the project alternatives are summarized below:

Alternative 1:

This substation is located at G. Molina St. Bagbaguin, Valenzuela City. This project involved the installation of 1-83 MVA power transformer with associated protective equipment as well as appurtenant distribution lines. This project is within the target load center and upon completion of its feedering it will also unload the critical loading of Malinta bank no.1 and Balintawak bank no. 6. This project meets the load requirements of the customers within the area and ensures the flexibility and reliability during contingency problem.

Alternative 2:

This project involves the development of Bahay Pare 115 kV-34.5 kV substation in Bahay Pare, Meycauayan, Bulacan. It involves construction of two (2) 115 kV overhead subtransmission lines to cut-in the Meycauayan-Camarin 115 kV line approximately 350 meters. Also, it includes the installation of 1-83 MVA power transformer with associated protective equipment as well as appurtenant distribution lines. However, it will require longer distribution lines since this substation is far from the target load thus, will result in more expensive project.

Alternative 3:

This switching station is located at No. 8 MGM Industrial Compound, Sitio Gitna Kaybiga, Caloocan City. This project involves the installation of 1-83 MVA power transformer with associated protective equipment as well as appurtenant distribution lines.

Table IV summarizes the comparison of the advantages and disadvantages of the project alternatives, whereas Table V shows the summary of financial evaluations of the project alternatives.

Table IV: Comparison of Project Alternatives

Alternative	Advantages	Disadvantages
Alternative 1: Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	<ul style="list-style-type: none">- This project will unload the intended target load area of Valenzuela City, Caloocan City and Quezon City upon completion of its feedering.- It will unload the critical loading of above power transformers.- This project will provide a reliable service in the area with operational switching flexibility during contingencies.- This project will also improve voltage regulation and reduce system losses in some areas of Valenzuela, Caloocan and Quezon City.- The cost of this project is cheaper compared to the other two alternatives.	<ul style="list-style-type: none">- No significant disadvantages.
Alternative 2: Development of Bahay Pare 115 kV-34.5 kV Substation	<ul style="list-style-type: none">- This project will provide reliable service in the area, with operational switching flexibility during contingencies.	<ul style="list-style-type: none">- It is farther from the target loads resulting in more line losses and voltage drop. Thus, the reliability of new distribution feeders will suffer.-It will involve construction of 350 meters, 115 kV overhead subtransmission lines to cut in the Meycauayan- Camarin 115 kV lines and 34.5 kV distribution lines.- This project will require a higher investment by Meralco compared to alternatives 1 and 3.

		- Developing a new substation will take a longer time to be completed and will have a higher project cost compared to the expansion of an existing substation.
Alternative 3: Installation of 1st 83 MVA Power Transformer at Sitio Gitna 115 kV Switching Station	- This project will provide reliable service in the area, with operational switching flexibility during contingencies.	- It is farther from the target loads resulting in more line losses and voltage drop. - More expensive project compared to alternative 1.

Table V: Financial Evaluation of Project Alternatives

Problem Description	The project alternatives intended to address the capacity deficiencies in some area of Valenzuela City, Caloocan City and Quezon City.				
Alternative	Project Name	Project Cost (P in M)	NPV (P in M)	IRR	B/C
1	Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	162.58	1,172.43	30.12%	4.93
2	Development of Bahay Pare 115 kV-34.5 kV Substation	374.93	892.83	22.86%	2.74
3	Installation of 1st 83 MVA Power Transformer at Sitio Gitna 115 kV Switching Station	170.12	1,162.51	29.70%	4.80

IV. Recommendation

Based on the result of technical and financial evaluation, Alternative 1, the Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank), is the best option since it has least cost in terms of total project and nearest to the target load of Valenzuela City, Caloocan City and Quezon City compared to Alternatives 2 and 3. With Alternative 1 project, exposure of existing feeders will minimize thus, will improve the voltage regulation and reduce system loss. This will also provide additional capacity in the affected area to accommodate new load applications.

The expansion of Bagbaguin Substation involved installation of one (1) 83MVA, 110kVY-34.5kVY-13.8kVD three-phase power transformer with OLTC, one (1) 1.2 ohm, 630A, 36kV neutral reactor, four (4) unit three-phase 115kV outdoor-type circuit breaker and eight (8) unit 115kV disconnect switches, one (1) assembly of three-phase 34.5kV outdoor-type metalclad switchgear with six (6) vacuum circuit breakers and one (1) 7.2MVAR outdoor-type capacitor bank, construction of four (4) 34.5 kV new overhead feeders and installation of four (4) new 34.5 kV, 600 A Remote-Controlled Line Reclosers.

V. Urgent Reason for Implementing in CY2015:

To avert possible emergency conditions due to critical loadings of facilities, the project was implemented. In fact, while project construction was on going in CY2015, Bagbaguin power transformer bank no. 1, Malinta power transformer 1 and Balintawak power transformer bank no. 6 were already operating at critical level. If this condition was not addressed immediately, critical loading of these facilities would have continued to persist which could have resulted to widespread power interruption and loss of loads. Without the project, MERALCO would also have difficulty in accommodating new and additional customer load applications in the area because of the high growth rate in the area.

The expansion project was partially completed last April 2016. The project was immediately implemented to solve the capacity deficiencies and avert possible power interruptions in some areas of Valenzuela City, Caloocan City and Quezon City as well as to accommodate new customer applications.

Annex A: Expenditure Summary
Annex B: Cost-Benefit Analysis
Annex C: Project Gantt Chart

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
EXPANSION OF BAGBAGUIN 115 KV- 34.5 KV SUBSTATION (2ND BANK)		Forecast (US\$, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	0			
	Structures and Improvements (Distribution Purposes)	0			
	Station Equipment	0			
	Power transformers	1,367,822			
	Switchgear	286,263			
	Protective equipment	16,342			
	Metering & control equipment	39,122			
	Communications equipment	0			
	Other station equipment	77,255			
	Poles, Towers and Fixtures - Distribution	42,403			
	Overhead Conductors and Devices - Distribution	3,604			
	Underground Conduits - Distribution	0			
	Underground Conductors and Devices - Distribution	0			
	Distribution Transformers	0			
	Power Conditioning Equipment	0			
	Meters, Metering Instruments & Metering Transformers - Distribution	0			
	Information technology equipment (distribution)	0			
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		1,832,811	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		1,832,811	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
EXPANSION OF BAGBAGUIN 115 KV- 34.5 KV SUBSTATION (2ND BANK)		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	100,000			
	Structures and Improvements (Distribution Purposes)	1,142,006			
	Station Equipment	0			
	Power transformers	17,329,148			
	Switchgear	23,408,478			
	Protective equipment	4,385,101			
	Metering & control equipment	1,537,613			
	Communications equipment	0			
	Other station equipment	1,679,538			
	Poles, Towers and Fixtures - Distribution	14,437,595			
	Overhead Conductors and Devices - Distribution	16,655,681			
	Underground Conduits - Distribution	0			
	Underground Conductors and Devices - Distribution	0			
	Distribution Transformers	0			
	Power Conditioning Equipment	0			
	Meters, Metering Instruments & Metering Transformers - Distribution	0			
	Information technology equipment (distribution)	1,595,880			
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		82,271,040	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		82,271,040	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
EXPANSION OF BAGBAGUIN 115 KV- 34.5 KV SUBSTATION (2ND BANK)		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	100,000	0	0	0
	Structures and Improvements (Distribution Purposes)	1,142,006	0	0	0
	Station Equipment	0	0	0	0
	Power transformers	77,263,676	0	0	0
	Switchgear	35,951,804	0	0	0
	Protective equipment	5,101,156	0	0	0
	Metering & control equipment	3,251,836	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	5,064,644	0	0	0
	Poles, Towers and Fixtures - Distribution	16,295,607	0	0	0
	Overhead Conductors and Devices - Distribution	16,813,610	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	1,595,880	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
Subtrans	Transferred subtransmission assets	0	0	0	0
Sub-total Regulated Distribution Services		162,580,219	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
Non-network	Information Systems Equipment (Connection)	0	0	0	0
	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		162,580,219	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: EXPANSION OF BAGBAGUIN 115KV-34.5KV SUBSTATION (2nd Bank)
YEAR: 2016

REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	E	X	P	E	U	N	V	E	TOTAL REVENUE	ENERGY SALES (MWH)	SELLING RATE (P/KWH)	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX W/ DEPRECIATION ADDED BACK	FREE CASH FLOW
0	2016	162,580	-	162,580	694	780	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	(162,580)
1	2017	677	677	163,257	723	812	-	-	-	-	-	-	-	-	-	934	0	934	(13,548)	-	(13,548)	-	(8,806)
2	2018	-	-	163,257	752	845	-	-	-	-	-	-	-	-	-	972	0	972	(13,548)	-	(13,548)	-	(8,806)
3	2019	-	-	163,257	783	879	-	-	-	-	-	-	-	-	-	1011	0	1011	(13,548)	-	(13,548)	-	(8,806)
4	2020	-	-	163,257	814	915	-	-	-	-	-	-	-	-	-	1052	0	1052	(13,548)	-	(13,548)	-	(8,806)
5	2021	-	-	163,257	847	952	-	-	-	-	-	-	-	-	-	1095	0	1095	(13,548)	-	(13,548)	-	(8,806)
6	2022	-	-	163,257	882	991	-	-	-	-	-	-	-	-	-	1139	0	1139	(13,548)	-	(13,548)	-	(8,806)
7	2023	-	-	163,257	918	1031	-	-	-	-	-	-	-	-	-	1185	0	1185	(13,548)	-	(13,548)	-	(8,806)
8	2024	50,505	50,505	163,257	956	1073	-	-	-	-	-	-	-	-	-	1233	0	1233	(13,548)	-	(13,548)	-	(8,806)
9	2025	57,219	57,219	163,257	994	1116	-	-	-	-	-	-	-	-	-	1283	56,502	1283	(13,548)	-	(13,548)	-	(8,806)
10	2026	63,874	63,874	163,257	1034	1162	-	-	-	-	-	-	-	-	-	1335	115,813	1335	(13,548)	-	(13,548)	-	(8,806)
11	2027	71,541	71,541	163,257	1076	1209	-	-	-	-	-	-	-	-	-	1389	177,282	1389	(13,548)	-	(13,548)	-	(8,806)
12	2028	79,557	79,557	163,257	1120	1258	-	-	-	-	-	-	-	-	-	1445	241,255	1445	(13,548)	-	(13,548)	-	(8,806)
13	2029	88,468	88,468	163,257	1165	1309	-	-	-	-	-	-	-	-	-	1503	307,742	1503	(13,548)	-	(13,548)	-	(8,806)
14	2030	98,204	98,204	163,257	1213	1362	-	-	-	-	-	-	-	-	-	1564	376,842	1564	(13,548)	-	(13,548)	-	(8,806)
15	2031	91,844	91,844	163,257	1262	1417	-	-	-	-	-	-	-	-	-	1627	448,657	1627	(13,548)	-	(13,548)	-	(8,806)
16	2032	23,328	23,328	163,257	1313	1475	-	-	-	-	-	-	-	-	-	1683	483,508	1683	(13,548)	-	(13,548)	-	(8,806)
17	2033	24,135	24,135	163,257	1366	1535	-	-	-	-	-	-	-	-	-	1761	483,508	1761	(13,548)	-	(13,548)	-	(8,806)
18	2034	25,115	25,115	163,257	1422	1597	-	-	-	-	-	-	-	-	-	1833	483,508	1833	(13,548)	-	(13,548)	-	(8,806)
19	2035	26,135	26,135	163,257	1480	1662	-	-	-	-	-	-	-	-	-	1907	483,508	1907	(13,548)	-	(13,548)	-	(8,806)
20	2036	27,196	27,196	163,257	1540	1729	-	-	-	-	-	-	-	-	-	1984	483,508	1984	(13,548)	-	(13,548)	-	(8,806)
21	2037	28,436	28,436	163,257	1602	1800	-	-	-	-	-	-	-	-	-	2064	483,508	2064	(13,548)	-	(13,548)	-	(8,806)
22	2038	29,450	29,450	163,257	1667	1873	-	-	-	-	-	-	-	-	-	2148	483,508	2148	(13,548)	-	(13,548)	-	(8,806)
23	2039	30,646	30,646	163,257	1735	1949	-	-	-	-	-	-	-	-	-	2234	483,508	2234	(13,548)	-	(13,548)	-	(8,806)
24	2040	31,891	31,891	163,257	1807	2028	-	-	-	-	-	-	-	-	-	2325	483,508	2325	(13,548)	-	(13,548)	-	(8,806)
25	2041	33,185	33,185	163,257	1883	2110	-	-	-	-	-	-	-	-	-	2419	483,508	2419	(13,548)	-	(13,548)	-	(8,806)
26	2042	34,609	34,609	163,257	1965	2196	-	-	-	-	-	-	-	-	-	2517	483,508	2517	(13,548)	-	(13,548)	-	(8,806)
27	2043	35,986	35,986	163,257	2054	2285	-	-	-	-	-	-	-	-	-	2618	483,508	2618	(13,548)	-	(13,548)	-	(8,806)
28	2044	37,395	37,395	163,257	2147	2378	-	-	-	-	-	-	-	-	-	2724	483,508	2724	(13,548)	-	(13,548)	-	(8,806)
29	2045	38,914	38,914	163,257	2243	2475	-	-	-	-	-	-	-	-	-	2835	483,508	2835	(13,548)	-	(13,548)	-	(8,806)
30	2046	40,495	40,495	163,257	2292	2575	-	-	-	-	-	-	-	-	-	2948	483,508	2948	(13,548)	-	(13,548)	-	(8,806)

1127
129
37.12
4.53

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: DEVELOPMENT OF BAHAY PARE 115KV-33.5KV SUBSTATION
YEAR 2016

REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER COST	GEN COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MWH)	SELLING RATE (P/KWH)	TOTAL REVENUE	SALES BEFORE TAX	EARNINGS AFTER TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX	FREE CASH FLOW																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		

NPV

392,339.49

IRR

22.56

B/C

0.74

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS

(COST X 1,000)

PROJECT: INSTALLATION OF 1ST 230KV POWER TRANSFORMER AT SITIO GITNA
YEAR 2016

2016
2015
2014
2013
2012
2011
2010
2009
2008
2007
2006
2005
2004
2003
2002
2001
2000
1999
1998
1997
1996
1995
1994
1993
1992
1991
1990
1989
1988
1987
1986
1985
1984
1983
1982
1981
1980
1979
1978
1977
1976
1975
1974
1973
1972
1971
1970
1969
1968
1967
1966
1965
1964
1963
1962
1961
1960
1959
1958
1957
1956
1955
1954
1953
1952
1951
1950
1949
1948
1947
1946
1945
1944
1943
1942
1941
1940
1939
1938
1937
1936
1935
1934
1933
1932
1931
1930
1929
1928
1927
1926
1925
1924
1923
1922
1921
1920
1919
1918
1917
1916
1915
1914
1913
1912
1911
1910
1909
1908
1907
1906
1905
1904
1903
1902
1901
1900
1899
1898
1897
1896
1895
1894
1893
1892
1891
1890
1889
1888
1887
1886
1885
1884
1883
1882
1881
1880
1879
1878
1877
1876
1875
1874
1873
1872
1871
1870
1869
1868
1867
1866
1865
1864
1863
1862
1861
1860
1859
1858
1857
1856
1855
1854
1853
1852
1851
1850
1849
1848
1847
1846
1845
1844
1843
1842
1841
1840
1839
1838
1837
1836
1835
1834
1833
1832
1831
1830
1829
1828
1827
1826
1825
1824
1823
1822
1821
1820
1819
1818
1817
1816
1815
1814
1813
1812
1811
1810
1809
1808
1807
1806
1805
1804
1803
1802
1801
1800
1799
1798
1797
1796
1795
1794
1793
1792
1791
1790
1789
1788
1787
1786
1785
1784
1783
1782
1781
1780
1779
1778
1777
1776
1775
1774
1773
1772
1771
1770
1769
1768
1767
1766
1765
1764
1763
1762
1761
1760
1759
1758
1757
1756
1755
1754
1753
1752
1751
1750
1749
1748
1747
1746
1745
1744
1743
1742
1741
1740
1739
1738
1737
1736
1735
1734
1733
1732
1731
1730
1729
1728
1727
1726
1725
1724
1723
1722
1721
1720
1719
1718
1717
1716
1715
1714
1713
1712
1711
1710
1709
1708
1707
1706
1705
1704
1703
1702
1701
1700
1699
1698
1697
1696
1695
1694
1693
1692
1691
1690
1689
1688
1687
1686
1685
1684
1683
1682
1681
1680
1679
1678
1677
1676
1675
1674
1673
1672
1671
1670
1669
1668
1667
1666
1665
1664
1663
1662
1661
1660
1659
1658
1657
1656
1655
1654
1653
1652
1651
1650
1649
1648
1647
1646
1645
1644
1643
1642
1641
1640
1639
1638
1637
1636
1635
1634
1633
1632
1631
1630
1629
1628
1627
1626
1625
1624
1623
1622
1621
1620
1619
1618
1617
1616
1615
1614
1613
1612
1611
1610
1609
1608
1607
1606
1605
1604
1603
1602
1601
1600
1599
1598
1597
1596
1595
1594
1593
1592
1591
1590
1589
1588
1587
1586
1585
1584
1583
1582
1581
1580
1579
1578
1577
1576
1575
1574
1573
1572
1571
1570
1569
1568
1567
1566
1565
1564
1563
1562
1561
1560
1559
1558
1557
1556
1555
1554
1553
1552
1551
1550
1549
1548
1547
1546
1545
1544
1543
1542
1541
1540
1539
1538
1537
1536
1535
1534
1533
1532
1531
1530
1529
1528
1527
1526
1525
1524
1523
1522
1521
1520
1519
1518
1517
1516
1515
1514
1513
1512
1511
1510
1509
1508
1507
1506
1505
1504
1503
1502
1501
1500
1499
1498
1497
1496
1495
1494
1493
1492
1491
1490
1489
1488
1487
1486
1485
1484
1483
1482
1481
1480
1479
1478
1477
1476
1475
1474
1473
1472
1471
1470
1469
1468
1467
1466
1465
1464
1463
1462
1461
1460
1459
1458
1457
1456
1455
1454
1453
1452
1451
1450
1449
1448
1447
1446
1445
1444
1443
1442
1441
1440
1439
1438
1437
1436
1435
1434
1433
1432
1431
1430
1429
1428
1427
1426
1425
1424
1423
1422
1421
1420
1419
1418
1417
1416
1415
1414
1413
1412
1411
1410
1409
1408
1407
1406
1405
1404
1403
1402
1401
1400
1399
1398
1397
1396
1395
1394
1393
1392
1391
1390
1389
1388
1387
1386
1385
1384
1383
1382
1381
1380
1379
1378
1377
1376
1375
1374
1373
1372
1371
1370
1369
1368
1367
1366
1365
1364
1363
1362
1361
1360
1359
1358
1357
1356
1355
1354
1353
1352
1351
1350
1349
1348
1347
1346
1345
1344
1343
1342
1341
1340
1339
1338
1337
1336
1335
1334[illegible]

431

10
9
8
7
6
5
4
3
2
1

11
 12
 13

1

100

—
•
•
•

RY2016 CAPEX:
Emergency Capital Expenditure Projects

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 2	INSTALLATION OF 34.5 KV METALCLAD SWITCHGEAR AT DASMARIÑAS 83 MVA POWER TRANSFORMER BANK NO. 1	August 2016	68,161,085

I. Project Background:

This project involves the installation of 34.5 kV metalclad switchgear and 34.5 kV 7.2 MVAR capacitor bank in NGCP Dasmariñas Substation as well as construction of two (2) new distribution feeders, control house and telecommunications room. It is worthy to note that this is among the projects filed as part of MERALCO's RY2016 Capital Expenditure application last February 9, 2015 and has also been a part of MERALCO's regular annual submission of its 10- Year Distribution Development Plan (DDP) to the Department of Energy (DOE) since 2014 in order to address the capacity deficiency and critical loading of distribution facilities in the area. Because of the urgent need to address the aforementioned problems however, MERALCO was constrained to implement the project immediately in order to avert multiple power interruptions to its customers in the area and maintain a robust electric distribution infrastructure.

Part of the reason for the immediate implementation of the aforesaid project is the critical loading of the nearby Imus power transformer bank no. 2. Since RY2014, this Imus power transformer bank no. 2 has been operating at critical levels, and this condition worsened when the actual loading of the Imus power transformer bank no. 2 at the beginning of RY2016 registered a 79% loading attributable to the high growth rate in the area at 11.2%. It is submitted that the full capacity of the Dasmariñas 83 MVA power transformer bank no. 1 could have been utilized to help reduce the loading of the Imus power transformer bank no. 2 within the normal level if it had four (4) distribution feeders instead of two (2). The inability to shift a portion of the loads of the Imus power transformer bank no. 2 was aggravated when both of the existing distribution feeders of the Dasmariñas 83 MVA power transformer bank, 42DA and 43DA, lacked sufficient capacity to help unload the aforementioned critically loaded power transformer bank. In addition, the high growth rate of 20.7%, in the area served by the Dasmariñas 83 MVA transformer bank utilized the remaining capacity that could have been used to reduce loading of the Imus power transformer bank.

II. Technical Analysis

Due to the significant increase of the load growth in the areas of Imus and Dasmariñas during the past year, which are mainly due to several residential, commercial and industrial customer applications, the Imus power transformer bank no. 2 registered 79% loading, and is expected to increase by 82% loading in RY2017. If this load growth will continue, especially with the anticipated additional growth from new residential and commercial establishments like Ayala Land Inc.'s Vermosa Project in Dasmariñas City and Imus City as well as Lancaster New City in Gen. Trias, the actual loading of the affected banks would go beyond its forecasted loading. In fact, in RY 2016, the load growth rate at the area served by the Dasmariñas 83 MVA power transformer increased at 20.7%, resulting to the utilization of the most of the transformer bank's remaining available capacity. While the Dasmariñas 83 MVA power transformer still has available capacity to serve help unload the Imus power transformer bank no. 2 and cater to new and additional load applications, MERALCO still had difficulty in transferring the loads from the Imus transformer bank no. 2 to the Dasmariñas 83 MVA power transformer bank since the latter has only two (2) distribution feeders and these feeders both lack sufficient capacity. It should be noted that four (4) distribution feeders are necessary to utilize the full capacity of the Dasmariñas 83 MVA power transformer which could also provide sufficient tying facility with other adjacent banks.

Without sufficient capacity to reduce the loading of the Imus 83 MVA Power Transformer Bank No. 2 to within normal loading levels and lack of sufficient distribution feeders to utilize the remaining capacity of the

Dasmariñas 83 MVA power transformer bank no. 1, the Imus 83 MVA Power Transformer Bank No. 2 operates at above critical loading level.

Further to the above, the Imus power transformer bank no. 1 cannot be used to unload the Imus power transformer bank no. 2 since this has a different voltage level (13.8 kV) and will eventually be converted to the standard 34.5 kV voltage in keeping with MERALCO's plan to gradually convert to 34.5 kV circuits by the year 2019 these 13.8 kV circuits of Imus power transformer bank no. 1.

Table 1 shows the 7- year historical loading while Table 2 shows the 10- year forecasted loading of Imus 83 MVA Power Transformer Bank No. 2 and Dasmariñas 83 MVA power transformer bank no. 1.

Table 1: 7- Year Historical Loading of Affected Power Transformer Banks

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2010		RY 2011		RY 2012		RY 2013	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Imus Bank 2	83	59.61	72%	61.49	74%	66.14	80%	58.98	71%
Dasma Bank	83	26.05	31%	36.65	44%	39.64	48%	38.02	46%

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2014		RY 2015		RY 2016	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Imus Bank 2	83	59.02	71%	59.19	71%	65.81	79%
Dasma Bank	83	37.55	45%	40.66	49%	49.10	59%

Table 2: 10- Year Forecasted Loading of Affected Power Transformer Banks

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2017		RY 2018		RY 2019		RY 2020	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Imus Bank 2	83	67.81	82%	69.26	83%	70.74	85%	72.25	87%
Dasma Bank	83	50.15	60%	51.22	62%	52.32	63%	53.44	64%

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2021		RY 2022		RY 2023		RY 2024	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Imus Bank 2	83	73.80	89%	75.38	91%	76.99	93%	78.64	95%
Dasma Bank	83	54.58	66%	55.75	67%	56.94	69%	58.16	70%

POWER TRANSFORMER	MAX CAPACITY (MVA)	RY 2025		RY 2026	
		LOAD (MVA)	% Ldg.	LOAD (MVA)	% Ldg.
Imus Bank 2	83	80.32	97%	82.04	99%
Dasma Bank	83	59.41	72%	60.68	73%

III. Project Alternatives

In the process of determining the most cost-effective solution to address the identified system deficiencies, MERALCO generated technically feasible alternatives that could satisfy the distribution system requirements in a timely and efficient manner. Table 3 shows the summary of technically feasible projects that are evaluated.

Table 3: Project Alternatives

Problem Description	The project alternatives intended to address the capacity deficiencies in the areas of Imus City and Dasmariñas City in the province of Cavite.	
Alternative	Project Name	Classification
1	Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer Bank No. 1	Stand-alone
2	Development of Pala-pala 115 kV – 34.5 kV Substation	Stand-alone
3	Expansion of FCIE 115 kV- 34.5 kV Substation (3rd Bank)	Stand-alone

Alternative 1: Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer Bank No. 1

This project involved the: (a) installation of a 34.5 kV metalclad switchgear and 34.5 kV 7.2 MVAR capacitor bank in the NGCP Dasmariñas Substation, (b) construction of two (2) new distribution feeders, (c) installation of thirteen (13) new 34.5 kV, 600 A Remote-Controlled Line Reclosers, (d) transfer of control, metering, protection and communication facilities and equipment of three (3) existing MERALCO 115 kV lines namely FCIE, Imus and Silang 115 kV Lines from NGCP control room to the new MERALCO control house, (e) transfer of metering facilities and equipment from the secondary side of the 83 MVA power transformer to the primary side of the transformer; and (f) construction of a new control house, telecommunications room, guard house, substation gate and concrete road.

Alternative 2: Development of Pala-pala 115 kV- 34.5 kV Substation

This project involves the development of a conventional 115 kV- 34.5 kV substation in Pala-pala, Dasmariñas City, Cavite. It includes the installation of 1- 83 MVA power transformer with associated SCADA, communication and protective equipment as well as construction of approximately 5 km subtransmission lines and appurtenant distribution lines.

Alternative 3: Expansion of FCIE 115 kV- 34.5 kV Substation (3rd Bank)

This project involves the expansion of the existing FCIE 115 kV- 34.5 kV substation in First Cavite Industrial Estate (FCIE), Brgy. Langkaan, Dasmariñas City, Cavite. It includes the installation of 1-83 MVA power transformer with associated SCADA and protective equipment as well as appurtenant distribution lines.

Table 4: Comparison of Project Alternatives

Alternative	Advantages	Disadvantages
Alternative 1 Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer Bank No. 1	<ul style="list-style-type: none">- This project, among all options, is the cheapest.- With minimal project cost, this project can lower the loading level of Imus power transformer bank no. 2 to within normal loading level.- The remaining available capacity of Dasmariñas 83 MVA Power Transformer Bank No. 1 will be utilized thru construction of two (2) new distribution feeders.- All scope of the project have been approved already by the NGCP.	<ul style="list-style-type: none">- There were additional scope of works introduced to comply with NGCP requirements such as transfer of control, metering, protection and communication facilities and equipment of three (3) existing MERALCO 115 kV lines namely FCIE, Imus and Silang 115 kV Lines from NGCP control room to the new MERALCO control house, transfer of metering facilities and equipment from the secondary side of the 83 MVA power transformer to the primary side of the transformer and construction of new guard

	<ul style="list-style-type: none"> - Among all options, this project is nearest to the target loads. - Due to urgency of the need to address the critical loading situations mentioned earlier, this project has been started and is expected to be completed within CY2016. 	house, substation gate and concrete road.
<p>Alternative 2</p> <p>Development of Pala-pala 115 kV- 34.5 kV Substation</p>	<ul style="list-style-type: none"> - Although this project involves the development of a new substation, this will not require acquisition of substation lot since it will utilize a MERALCO- owned lot. - This project will provide larger additional capacity compared to Option 1. - This can provide capacity to other load centers in the area. 	<ul style="list-style-type: none"> - This is the most expensive because this option will require construction of approximately 5 km of 115 kV subtransmission lines. - Compared to Option 1, this project is far from the intended loads to be served.
<p>Alternative 3</p> <p>Expansion of FCIE 115 kV- 34.5 kV Substation (3rd Bank)</p>	<ul style="list-style-type: none"> - This project will provide larger additional capacity compared to Option 1. - This can provide capacity to other load centers in the area. 	<ul style="list-style-type: none"> - Compared to Option 1, this project is farther from the intended loads to be served.

Table 5: Financial Evaluation of Project Alternatives

Problem Description	The project alternatives are intended to reduce the loading of the Imus power transformer bank no. 2 to within normal loading levels and to utilize the remaining available capacity of the Dasmariñas 83 MVA power transformer bank no. 1 as well as to provide additional capacity for the new and additional load applications in the area of Imus City and Dasmariñas City in Cavite.				
Alternative	Project Name	Project Cost (P in M)	NPV (P in M)	IRR	B/C
1	Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer Bank No. 1	68.16	733.82	36.72%	6.34
2	Development of Pala-Pala 115 kV – 34.5 kV Substation	332.10	169.05	17.05%	1.43
3	Expansion of FCIE 115 kV- 34.5 kV Substation (3rd Bank)	160.17	395.43	22.02%	2.79

IV. Recommendation

Based on the technical and financial evaluation of the different alternatives it was deemed that the most economical solution to address the critical loading of the Imus power transformer bank no. 2 is the project 'Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer Bank No. 1'. Upon completion, it will also address the anticipated reliability problems in the areas being served by the Dasmariñas 83 MVA power transformer bank no. 1 due to limited distribution feeders and tying facilities. Furthermore, this project was chosen since it is near the target load center and load growth area to be served by the project. It will require construction of shorter distribution lines, minimize system loss, increase system reliability and improve power quality as the project will reduce technical loss by as much as 642,869 kilowatt-hour per year (kWh/ yr). Moreover, the additional capacity in the area will allow MERALCO to use the remaining available capacity of the 83 MVA power transformer thru its two (2) additional feeders..

The project involved: (a) the installation of one (1) assembly of three-phase 34.5 kV outdoor-type metalclad switchgear with seven (7) vacuum circuit breakers and one (1) 7.2 MVAR outdoor-type capacitor bank; (b) construction of two (2) 34.5 kV new overhead feeders; (c) installation of thirteen (13) new 34.5 kV, 600 A Remote-Controlled Line Reclosers; (d) transfer of control, metering, protection and communication facilities and equipment of three (3) existing MERALCO 115 kV lines namely FCIE, Imus and Silang 115 kV Lines from NGCP control room to the new MERALCO control house; (e) transfer of metering facilities and equipment from the secondary side of the 83 MVA power transformer to the primary side of the transformer; and (f) construction of a new control house, telecommunications room, guard house, substation gate and concrete road.

V. Urgent Reason for Implementing in CY2015

In order to avert possible emergency conditions due to critical loadings of facilities, the project was implemented. In fact, while project construction was on going in early CY2016 the Imus power transformer bank no. 2 was already operating at above critical levels. Meanwhile, two (2) existing distribution feeders of the Dasmariñas 83 MVA power transformer bank, 42DA and 43DA, cannot help unload the said critically loaded bank since these distribution feeders do not have sufficient capacity. If this condition would not be addressed immediately, critical loading of these facilities would continue to persist which could result to widespread power interruption and loss of loads. In addition, the increasing growth rate in the area puts MERALCO in a situation where it will have difficulty in accommodating new and additional customer load applications should the loading and capacity problems persist.

As for the additional requirements of this project, MERALCO already sought and secured clearance and approval from NGCP prior to the project's implementation since the project requires coordination and approval from the National Grid Corporation of the Philippines (NGCP) regarding construction, modification and installation of MERALCO substation equipment in an NGCP- owned substation. Our consultation with NGCP for the proposed project 'Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer' started in as early as November 25, 2013. In NGCP's response letters dated January 7 and 23, 2014, NGCP approved the proposed project citing that it is technically feasible and acceptable. On February 17, 2014, MERALCO also sought for the approval of our proposed general arrangement plan related to the project and during a meeting on January 20, 2015, NGCP approved the requested additional space to accommodate all the required equipment related to the project. The design stage of this project started in July 2015 and with several scope revisions, the design was completed in May 2016 while all equipment will be completely delivered in July 2016. The construction of this project started in January 2016 and is expected to be completed within August 2016.

Annex A: Expenditure Summary

Annex B: Cost-Benefit Analysis

Annex C: Project Gantt Chart

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
INSTALLATION OF 34.5 KV METALCLAD SWITCHGEAR AT DASMARIÑAS 83 MVA POWER TRANSFORMER BANK NO. 1		Forecast (US\$, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	0			
	Structures and Improvements (Distribution Purposes)	0			
	Station Equipment	0			
	Power transformers	10,197			
	Switchgear	277,650			
	Protective equipment	727			
	Metering & control equipment	39,122			
	Communications equipment	0			
	Other station equipment	39,879			
	Poles, Towers and Fixtures - Distribution	38,236			
	Overhead Conductors and Devices - Distribution	6,179			
	Underground Conduits - Distribution	0			
	Underground Conductors and Devices - Distribution	0			
	Distribution Transformers	0			
	Power Conditioning Equipment	0			
	Meters, Metering Instruments & Metering Transformers - Distribution	0			
	Information technology equipment (distribution)	0			
	Regulated Entity Property on Consumer's Premises	0			
	Street Lights and Signal Systems	0			
	Submarine Cables	0			
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		411,989	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		411,989	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
INSTALLATION OF 34.5 KV METALCLAD SWITCHGEAR AT DASMARIÑAS 83 MVA POWER TRANSFORMER BANK NO. 1		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	100,000			
	Structures and Improvements (Distribution Purposes)	2,992,592			
	Station Equipment	0			
	Power transformers	1,563,621			
	Switchgear	3,965,412			
	Protective equipment	3,492,495			
	Metering & control equipment	1,315,247			
	Communications equipment	0			
	Other station equipment	849,290			
	Poles, Towers and Fixtures - Distribution	10,151,708			
	Overhead Conductors and Devices - Distribution	23,284,574			
	Underground Conduits - Distribution	0			
	Underground Conductors and Devices - Distribution	0			
	Distribution Transformers	0			
	Power Conditioning Equipment	0			
	Meters, Metering Instruments & Metering Transformers - Distribution	0			
	Information technology equipment (distribution)	2,393,820			
	Regulated Entity Property on Consumer's Premises	0			
	Street Lights and Signal Systems	0			
	Submarine Cables	0			
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Transferred subtransmission assets				
Materials					
Subtrans					
Sub-total Regulated Distribution Services		50,108,759	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
Materials					
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		50,108,759	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
INSTALLATION OF 34.5 KV METALCLAD SWITCHGEAR AT DASMARIÑAS 83 MVA POWER TRANSFORMER BANK NO. 1					
		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	100,000	0	0	0
	Structures and Improvements (Distribution Purposes)	2,992,592	0	0	0
	Station Equipment	0	0	0	0
	Power transformers	2,010,434	0	0	0
	Switchgear	16,131,339	0	0	0
	Protective equipment	3,524,348	0	0	0
	Metering & control equipment	3,029,469	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	2,596,676	0	0	0
	Poles, Towers and Fixtures - Distribution	11,827,097	0	0	0
	Overhead Conductors and Devices - Distribution	23,555,309	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	2,393,820	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Transferred subtransmission assets	0	0	0	0
	Sub-total Regulated Distribution Services	68,161,085	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
Non-network	Information Systems Equipment (Connection)	0	0	0	0
	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Sub-total Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		68,161,085	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: INSTALLATION OF 11.5 KV METALCLAD SWITCHGEAR AT DASMARIÑAS 03 NYA POWER TRANSFORMER OWNED BY NEPLICO
YEAR: 2016

PER YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	E X P	OM COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MMH)	SELLING PRICE (P/KWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX (W/ DEPRECIATION ADDED BACK)	FREE CASH FLOW
0	2016		68,161														
1	2017	302		694	723	694	214	2,272	5,994	30	840		(5,633)		(5,633)	(3,361)	(68,161)
2	2018	1	302	752	761	722	230	2,272	5,910	31	918	281	(5,629)		(5,629)	(3,357)	(3,662)
3	2019	1		783		782	246	2,272	5,927	32	955	280	(5,626)		(5,626)	(3,354)	(3,358)
4	2020	2		814		813	263	2,272	5,945	33	993	323	(5,622)		(5,622)	(3,350)	(3,355)
5	2021	4,398		847	848		53,045	2,272	59,725	6,267	1033	64,762	6,037	1,511	4,226	6,498	2,100
6	2022	17,383		882	881		280,955	2,272	267,313	29,628	1075	318,541	51,223	15,387	35,856	38,128	20,746
7	2023	19,289		918	917		492,423	2,272	498,735	53,726	1119	537,26	102,192	35,683	71,534	73,806	54,517
8	2024	21,424		955	954		749,514	2,272	755,976	78,985	1164	914,578	158,702	47,650	111,091	113,363	91,939
9	2025	26,665		984	993		1,069,492	2,272	1,075,953	107,757	1211	1,304,787	228,933	97,033	160,253	162,626	135,861
10	2026	23,349		1034	1073		1,349,674	2,272	1,355,036	130,660	1250	1,646,314	290,278	104,713	203,195	205,467	182,118
11	2027	29,064		1076	1075		1,697,756	2,272	1,704,759	157,967	1311	2,000,525	365,726	134,154	314,670	316,942	229,217
12	2028	31,980		1120	1118		2,081,515	2,272	2,089,559	186,115	1364	2,538,087	449,529	157,154	379,152	381,424	346,218
13	2029	35,206		1165	1164		2,503,982	2,272	2,511,025	215,151	1419	3,052,671	541,645	182,154	397,586	429,858	403,309
14	2030	26,549		1213	1211		2,937,219	2,272	2,944,614	233,060	1476	3,440,451	610,837	197,154	427,586	446,975	437,421
15	2031	9,554		1262	1260		3,086,526	2,272	3,094,563	233,062	1536	3,578,553	635,291	197,154	444,703	464,293	454,294
16	2032	9,999		1311	1311		3,160,678	2,272	3,168,651	233,063	1598	3,724,281	660,030	197,154	462,021	482,793	472,447
17	2033	10,326		1366	1365		3,309,875	2,272	3,317,403	233,065	1663	3,874,861	686,458	203,939	480,521	499,752	491,258
18	2034	10,766		1422	1420		3,444,320	2,272	3,452,046	233,066	1730	4,031,532	713,932	215,713	499,752	502,024	510,813
19	2035	11,204		1480	1478		3,584,227	2,272	3,591,952	233,068	1800	4,264,538	742,483	227,713	519,745	522,017	531,142
20	2036	11,659		1540	1538		3,729,818	2,272	3,737,524	233,069	1872	4,484,137	772,185	239,634	540,529	542,801	551,742
21	2037	12,189		1602	1600		3,881,323	2,272	3,889,730	233,071	1949	4,724,189	802,370	250,711	561,659	563,931	573,768
22	2038	12,625		1667	1665		4,038,984	2,272	4,047,134	233,073	2027	4,965,208	834,459	260,234	584,121	586,393	596,008
23	2039	13,138		1733	1733		4,203,049	2,272	4,211,156	233,075	2109	5,111,954	867,818	270,316	607,473	609,745	620,348
24	2040	13,672		1805	1803		4,373,781	2,272	4,381,937	233,077	2194	5,300,737	902,488	279,756	631,718	634,020	645,029
25	2041	14,228		1879	1877		4,551,448	2,272	4,559,614	233,078	2283	5,500,737	938,560	289,237	656,985	659,237	670,153
26	2042	14,862		1955	1953		4,736,335	2,272	4,744,614	233,080	2375	5,700,737	973,348	298,713	682,744	685,016	696,883
27	2043	15,407		2034	2032		4,928,732	2,272	4,936,935	233,082	2471	5,900,737	1,014,311	307,234	710,018	712,290	724,611
28	2044	16,033		2117	2115		5,128,947	2,272	5,137,220	233,085	2571	6,100,737	1,054,817	316,142	738,372	740,644	753,436
29	2045	16,685		2203	2200		5,337,296	2,272	5,345,555	233,087	2675	6,300,737	1,096,926	325,375	767,848	770,120	783,401
30	2046	17,362		2292	2290			2,272		233,089	2783	6,487,087	1,140,702	334,211	798,492	800,764	

NPV 733,433.31
IRR 34.72
B/C 5.34

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: DEVELOPMENT OF PALA-PALA 115 KV- 34.5 KV SUBSTATION
YEAR 2016

REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	OSM COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MWH)	SELLING RATE (P/KWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX	FREE CASH FLOW
W/ DEPRECIATION ADDED BACK																	
0	2016	332,086	-	332,086	6.84	6.93	-	11,070	27,888	30	8.47	-	(27,627)	-	-	(27,627)	(332,086)
1	2017		1,402	1,402	7.23	7.21	214	16,605	27,904	31	8.81	261	(27,624)	(16,557)	(16,557)	(17,855)	
2	2018		1	1	7.52	7.51	229	16,605	27,904	31	9.17	280	(27,624)	(16,554)	(16,554)	(16,555)	
3	2019		1	1	7.63	7.61	246	16,605	27,921	32	9.54	301	(27,620)	(16,550)	(16,550)	(16,552)	
4	2020		2	2	8.14	8.13	264	16,605	27,939	33	9.93	323	(27,616)	(16,546)	(16,546)	(16,548)	
5	2021		2	2	8.47	8.46	284	16,605	27,958	34	10.33	347	(27,612)	(16,542)	(16,542)	(16,544)	
6	2022		278	278	8.82	8.80	305	19,936	31,303	35	10.74	372	(30,928)	(19,858)	(19,858)	(20,137)	
7	2023		2	2	9.16	9.16	327	19,936	31,322	36	11.18	359	(30,923)	(19,854)	(19,854)	(19,855)	
8	2024		12,056	12,056	9.55	9.53	145,001	11,070	275,997	15,214	11.63	176,538	63,667	19,136	44,567	31,891	
9	2025		23,746	23,746	9.92	9.94	429,957	11,070	480,952	43,352	12.10	524,619	76,119	22,416	53,283	39,800	
10	2026		4,754	4,754	10.34	10.32	486,999	11,070	517,995	47,188	12.59	594,113	116,557	24,942	81,580	78,746	
11	2027		16,913	16,913	10.76	10.74	686,637	11,070	730,954	63,935	13.10	837,511	164,907	45,412	119,435	108,092	
12	2028		18,413	18,413	11.20	11.18	907,594	11,070	941,911	81,211	13.63	1,068,818	216,239	45,412	152,767	143,494	
13	2029		20,343	20,343	11.65	11.63	1,151,706	11,070	1,136,023	99,032	14.18	1,283,241	276,970	45,412	193,879	182,511	
14	2030		22,437	22,437	12.13	12.10	1,420,955	11,070	1,485,272	117,415	14.75	1,623,241	341,552	45,412	236,086	225,446	
15	2031		24,710	24,710	12.62	12.59	1,717,480	11,070	1,791,736	136,379	15.35	2,003,349	409,152	45,412	286,406	270,024	
16	2032		27,452	27,452	13.13	13.10	2,043,588	11,070	2,091,224	155,941	15.97	2,300,378	486,935	45,412	340,855	322,076	
17	2033		29,849	29,849	13.66	13.64	2,401,771	11,070	2,439,403	175,120	16.62	2,626,344	572,147	45,412	400,503	378,827	
18	2034		32,745	32,745	14.22	14.19	2,794,713	11,070	2,832,350	195,936	17.29	3,064,497	688,778	45,412	482,145	448,392	
19	2035		36,245	36,245	14.80	14.77	3,332,686	11,070	3,370,224	225,673	17.99	3,604,497	787,336	45,412	537,135	517,863	
20	2036		40,342	40,342	15.40	15.37	3,696,687	11,070	3,734,325	245,560	18.71	4,000,002	875,354	45,412	612,748	601,581	
21	2037		45,237	45,237	16.02	15.99	4,212,209	11,070	4,253,163	263,409	19.47	4,501,660	986,852	45,412	697,796	681,925	
22	2038		46,941	46,941	16.67	16.64	4,775,507	11,070	4,816,465	285,909	20.25	5,103,371	1,129,326	45,412	790,529	750,350	
23	2039		51,249	51,249	17.35	17.32	5,390,490	11,070	5,431,443	311,284	21.03	5,813,317	1,273,659	45,412	901,561	846,724	
24	2040		60,944	60,944	18.05	18.02	6,091,376	11,070	6,102,134	336,376	21.81	6,600,775	1,430,798	45,412	1,001,558	951,684	
25	2041		66,566	66,566	18.75	18.75	6,792,705	11,070	6,803,134	362,260	22.81	7,232,993	1,596,441	45,412	1,116,909	1,063,313	
26	2042		72,273	72,273	19.55	19.51	7,489,371	11,070	7,500,824	388,939	23.74	8,044,481	1,784,330	45,412	1,245,031	1,187,828	
27	2043		78,630	78,630	20.31	20.34	8,456,644	11,070	8,468,434	416,472	24.70	9,085,253	1,986,323	45,412	1,390,426	1,322,866	
28	2044		85,969	85,969	21.17	21.13	9,400,203	11,070	9,412,619	448,872	25.69	10,026,805	2,206,915	45,412	1,544,840	1,469,941	
29	2045		94,319	94,319	22.03	21.99	10,431,929	11,070	10,444,109	474,427	26.73	11,049,005	2,341,149	45,412	1,638,804	1,597,115	
30	2046		103,759	103,759	22.92	22.88	11,064,938	11,070	11,109,217	483,581	27.81	12,683,023	2,341,149	45,412	1,638,804	1,597,115	

NET
IPF
3.12
17.22
1.43

ANNEX B: COST-BENEFIT ANALYSIS

SYSTEM FINANCIAL ANALYSIS

(COST : 1,000)

PROJECT: EXPANSION OF ECIE 115 KV- 34.5 KV SUBSTATION (2PD BANK)

YEAR 2016

REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (\$/KWH)	PURCH. POWER (\$/KWH)	PURCH. POWER (\$/KWH)	PURCH. POWER (\$/KWH)	OWN COST	DEPRECIATION	TOTAL EXPENSES	ENERGY (\$/KWH)	SELLING (\$/KWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS TAX	FREE CASH FLOW
N/ LOSS																			
0	2016	160,168	-	160,168	694	694	-	-	8,008	5,339	13,561	30	8.47	-	-	-	-	-	(160,168)
1	2017	685	685	685	721	721	214	214	8,008	5,339	13,561	30	8.81	261	(13,300)	9	(7,951)	(7,951)	(8,646)
2	2018	1	1	1	732	732	229	229	8,008	5,339	13,577	31	9.17	280	(13,296)	0	(7,958)	(7,958)	(8,646)
3	2019	1	1	1	762	762	245	245	8,008	5,339	13,594	32	9.54	301	(13,293)	0	(7,954)	(7,954)	(8,646)
4	2020	2	2	2	814	814	264	264	8,008	5,339	13,611	33	9.93	323	(13,289)	0	(7,950)	(7,950)	(8,646)
5	2021	2	2	2	846	846	284	284	8,008	5,339	13,631	34	10.33	347	(13,285)	0	(7,946)	(7,946)	(8,646)
6	2022	135	135	135	882	882	305	305	9,610	5,339	15,254	35	10.74	372	(14,882)	0	(9,543)	(9,543)	(9,540)
7	2023	2	2	2	916	916	327	327	9,610	5,339	15,276	36	11.13	399	(14,877)	0	(9,538)	(9,538)	(9,540)
8	2024	12,056	12,056	12,056	955	955	145,001	145,001	9,610	5,339	159,959	15,214	11.63	795	17,008	5,102	11,905	17,244	37,392
9	2025	23,746	23,746	23,746	994	994	429,557	429,557	9,610	5,339	444,906	43,382	12.10	524,619	79,714	23,611	58,000	67,139	65,101
10	2026	47,564	47,564	47,564	1034	1034	868,989	868,989	9,610	5,339	879,638	47,168	12.59	594,113	142,165	27,450	64,516	69,855	65,101
11	2027	16,770	16,770	16,770	1076	1076	486,937	486,937	11,212	5,339	701,193	63,935	13.10	837,511	134,323	31,397	94,026	99,365	82,595
12	2028	18,413	18,413	18,413	1118	1118	907,594	907,594	11,212	5,339	924,148	81,211	13.63	1,106,818	182,873	34,392	127,871	133,210	114,797
13	2029	20,343	20,343	20,343	1120	1120	1,151,706	1,151,706	11,212	5,339	1,168,257	117,415	14.18	1,404,262	236,005	37,301	170,542	179,842	150,200
14	2030	22,437	22,437	22,437	1165	1165	1,420,955	1,420,955	11,212	5,339	1,437,506	119,415	15.35	1,732,241	294,736	43,421	206,315	211,654	189,215
15	2031	24,710	24,710	24,710	1202	1202	1,717,480	1,717,480	11,212	5,339	1,734,030	135,941	15.97	2,093,349	359,318	47,385	251,523	256,862	232,151
16	2032	27,309	27,309	27,309	1313	1313	2,043,588	2,043,588	12,813	5,339	2,061,741	155,941	16.82	2,460,378	426,637	52,451	300,046	303,385	278,076
17	2033	29,849	29,849	29,849	1366	1366	2,401,771	2,401,771	12,813	5,339	2,415,923	175,120	17.99	2,863,344	498,632	57,459	334,494	339,985	329,065
18	2034	32,745	32,745	32,745	1422	1422	2,794,713	2,794,713	12,813	5,339	2,812,365	195,936	17.29	3,263,344	566,420	62,459	386,736	391,985	379,076
19	2035	44,823	44,823	44,823	1477	1477	3,332,585	3,332,585	12,813	5,339	3,350,739	223,673	17.99	4,059,002	789,264	177,439	419,481	419,481	399,833
20	2036	30,342	30,342	30,342	1540	1540	4,339,490	4,339,490	12,813	5,339	4,374,849	240,500	18.71	5,128,522	896,558	236,043	550,775	550,775	525,772
21	2037	43,094	43,094	43,094	1599	1599	4,775,507	4,775,507	14,415	5,339	4,785,261	283,409	19.47	5,650,775	1,018,056	268,763	627,591	627,591	589,836
22	2038	46,841	46,841	46,841	1667	1667	5,390,490	5,390,490	14,415	5,339	5,410,234	311,294	21.08	6,560,775	1,150,531	305,417	712,639	712,639	671,037
23	2039	51,249	51,249	51,249	1735	1735	6,051,376	6,051,376	14,415	5,339	6,061,134	336,376	21.93	7,375,933	1,294,864	345,159	805,372	805,372	759,462
24	2040	55,907	55,907	55,907	1805	1805	6,792,705	6,792,705	14,415	5,339	6,811,459	362,250	22.81	8,264,461	1,452,002	393,453	908,404	908,404	855,836
25	2041	60,944	60,944	60,944	1879	1879	7,589,371	7,589,371	16,017	5,339	7,610,727	388,939	23.74	9,322,091	1,621,365	435,401	1,016,401	1,016,401	960,798
26	2042	66,522	66,522	66,522	1955	1955	8,456,644	8,456,644	16,017	5,339	8,478,066	416,472	24.70	10,395,253	1,807,253	462,112	1,134,955	1,134,955	1,073,772
27	2043	72,773	72,773	72,773	2031	2031	9,400,823	9,400,823	16,017	5,339	9,421,533	444,872	25.69	11,406,905	2,009,247	502,114	1,270,416	1,270,416	1,198,143
28	2044	78,630	78,630	78,630	2117	2117	10,431,829	10,431,829	16,017	5,339	10,453,135	474,427	26.73	12,893,023	2,229,839	563,114	1,406,473	1,406,473	1,333,182
29	2045	85,969	85,969	85,969	2199	2199	11,061,938	11,061,938	16,017	5,339	11,079,233	483,581	27.81	14,560,887	2,364,072	603,222	1,566,226	1,566,226	1,480,257
30	2046	52,759	52,759	52,759	2292	2292	-	-	16,017	5,339	11,039,233	483,581	27.81	13,450,366	2,364,072	-33,222	1,654,851	1,654,851	1,607,431

Q4

31.
62.
9-4

۱۸

**RY2016 CAPEX:
Capital Expenditure Projects**

ANNEX "A-2"

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 3	REBUILDING PORTION OF DASMARIÑAS-FCIE 115 KV LINE	December 2015	75,913,229

I. Project Background:

The Dasmariñas-FCIE 115 kV line is one of the main outlets of the Dasmariñas 230kV-115kV delivery point substation in Cavite Sector that supplies bulk power to FCIE, TMC2, Gateway, and Rosario 115kV-34.5kV substations including the customer-owned, SMC 115kV substation. The FCIE, Gateway, and TMC 2 substations are serving the residential, commercial and large industrial customers in the portions of Dasmariñas, Trece Martires City and Gen Trias including locators in First Cavite Industrial Estate and Gateway Business Park, respectively. On the other hand, the Rosario substation is serving the residential, commercial and large industrial customers in Rosario, portions of General Trias, Kawit and Cavite City including the locators in Cavite Economic Zone.

This project involved the rebuilding of the 115 kV line from FCIE substation up to the tapping point along Governor's Drive to uprate the 3.1-kilometer portion of the Dasmariñas-FCIE Line from 1-795 MCM ACSR conductor per phase to 2-795 MCM ACSR conductor per phase. This project was filed as part of MERALCO's RY2016 Capital Expenditure application last February 9, 2015 and has also been a part of MERALCO's regular annual submission of its 10-Year Distribution Development Plan (DDP) to the Department of Energy (DOE) since 2012 in order to address line overloading in the area during N-1 contingency. Because of the urgent need to address the aforementioned problem however, MERALCO was constrained to implement the project immediately in order to avert multiple power interruptions to its customers in the area and maintain a robust electric distribution infrastructure.

The ERC's deferral of this project was based on the pending resolution of the case elevated by MERALCO to the Court of Appeals (CA) regarding the Dasmariñas-Rosario 115 kV line. MERALCO's implementation of this project was based on the urgent need of the system. Regardless of the pending CA ruling on the classification of the facilities involved, this project was implemented since the N-1 problem at Dasmariñas-FCIE 115 kV line is a technical issue and is unrelated or irrelevant to the said case. Likewise, even with the CA ruling disapproving the sale of the Dasmariñas-Abubot-Rosario 115 kV line to MERALCO, MERALCO still has the responsibility to maintain the Dasmariñas-FCIE 115 kV line since it is part of the Cavite 115 kV Sector linking all other substations serving the MERALCO loads. More importantly, the instant project will not be affected by the case concerning the reclassification of the Dasmariñas-Rosario 115 kV line as the scope only involves the uprating of line facilities the location of which is approximately two (2) kilometres away from the Dasmariñas substation.

II. Technical Analysis

During N-1 contingencies in the Cavite Sector, specifically the outage of either the Dasmariñas-Abubot-Rosario 115 kV line, the Amadeo-Gateway-FCIE 115 kV line or the Amadeo 300 MVA power transformer, the Dasmariñas-FCIE 115 kV line will be overloaded at a maximum of 106%. The overloading, if not corrected, would have led to widespread power interruptions in the Cavite area affecting major customers in First Cavite Industrial Estate (FCIE), Gateway Business Park, Cavite Export Zone (CEZ), and San Miguel Corporation with a total load at risk of 220 MVA. Due to rapid development in the area, the number of loads that will be affected will continue to increase. (Please refer to Tables 1 & 2 below for the performance measures with and without project)

By rebuilding a portion of the Dasmariñas-FCIE 115 kV Line, it addressed the N-1 requirement of the distribution line and strengthened the sub-transmission backbone in the area. The project also provided adequate capacity to meet the increasing power demand and accommodate new customer applications as well as future prospective large customers. Likewise, this project improved the reliability of the sub-transmission system in the Cavite Sector as well as contributed to the reduction of the system loss by an estimated 1,936,302 kWh annually.

Without this project, the Cavite Sector will not meet the N-1 redundancy requirement.

This project addressed the technical issues and provided urgent solution to the precarious condition in the area and complied with the N-1 redundancy for sub-transmission system to avoid breaching the sub-transmission planning criteria that states "*sub-transmission lines shall not be loaded beyond 90% of its rated capacity during N-*

1 contingency". The single outage contingency or N-1 redundancy for sub-transmission system is approved by the Energy Regulatory Commission (ERC) in the Second Regulatory Period and is prescribed in the Investor-owned Electric Distribution Utility Planning Manual. Thus, it is emphasized that it is imperative for MERALCO to implement the project because it will impact the reliability of system and cause widespread interruptions in the area.

Moreover, the circuit breakers associated on the termination of this line at Dasmariñas 115 kV switchyard is owned and operated by MERALCO (see Figure 1). Thus, it is MERALCO's responsibility to correct critical and overloading problems of this line since MERALCO customers will be affected. Furthermore, outage of any of the NGCP-owned circuit breakers at Dasmariñas 115kV switchyard will not affect the project. And lastly, the rebuilt portion of the project is 1.2 km. away from Dasmariñas substation, and the project has no substation or line equipment works involved inside the substation, which is the subject of the said CA case.




Figure 1 – Dasmariñas 115 kV Switchyard

Table 1: Performance Measures Without the Project during N-1 Contingency

PARAMETERS UNDER CONSIDERATION			PERCENT LOADING OF DASMARINAS-FCIE LINE DURING N-1 CONTINGENCY				
OUTAGE OF BANK/LINE DURING N-1 CONTINGENCY	AFFECTED SUB-TRANSMISSION FACILITY DURING N-1 CONTINGENCY		RY2015	RY2016	RY2017	RY2018	RY2019
	LINE	CAPACITY (MVA)					
Dasmariñas-Abubot-Rosario Line	Dasmariñas-FCIE Line	171.5	93%	98%	102%	107%	111%
Amadeo-Gateway-FCIE Line			87%	92%	96%	100%	104%

Amadeo 300 MVA Bank			99%	106%	110%	115%	120%
---------------------	--	--	-----	------	------	------	------

Table 2: Performance Measures With Project during N-1 Contingency

PARAMETERS UNDER CONSIDERATION			PERCENT LOADING OF DASMARIÑAS-FCIE LINE DURING N-1 CONTINGENCY				
OUTAGE OF BANK/LINE DURING N-1 CONTINGENCY	AFFECTED SUB-TRANSMISSION FACILITY DURING N-1 CONTINGENCY		RY2015	RY2016	RY2017	RY2018	RY2019
	LINE	CAPACITY (MVA)					
Dasmarinas-Abubot-Rosario Line	Dasmarinas-FCIE Line	342.9	93%	53%	55%	57%	59%
Amadeo-Gateway-FCIE Line			87%	47%	49%	51%	53%
Amadeo 300 MVA Bank			99%	60%	63%	65%	68%

III. Project Alternatives

In the process of determining the most cost-effective solution to address the identified system deficiencies, MERALCO generated technically feasible alternatives that could satisfy the distribution system requirements in a timely and efficient manner. Table 3 shows the summary of technically feasible projects that were evaluated.

Table 3: Problem and project alternatives

Problem Description	N-1 contingency problem involving the Dasmarinas-FCIE 115 kV line	
Alternative	Project Name	Classification
1	Rebuilding Portion of Dasmarinas-FCIE 115 kV Line	Stand-alone
2	Construction of New Dasmarinas-FCIE 115 kV Line	Stand-alone
3	Construction of New Amadeo-FCIE 115 kV Line	Stand-alone

Alternative 1: Rebuilding Portion of Dasmariñas-FCIE 115 kV Line

This project involves rebuilding the 115 kV line from FCIE substation up to the tapping point along Governor's Drive to uprate the 3.1-kilometer portion of Dasmariñas-FCIE Line from 1-795 MCM ACSR conductor per phase to 2-795 MCM ACSR conductor per phase (refer to Figure 2).




Figure 2 – Proposed Rebuilding Portion of Dasmariñas-FCIE 115 kV Line (Alternative 1)

Alternative 2: Construction of New Dasmariñas-FCIE 115 kV Line

This project involves the construction of around 4.9-kilometers of 115 kV line using 2-795 MCM ACSR conductor per phase. The new line will be built along the Aguinaldo Highway and Governor's Drive from Dasmariñas substation up to FCIE substation. This project also includes the installation of 115 kV power circuit breakers and associated equipment and structures including protection/control equipment at Dasmariñas and FCIE substations for the termination of the proposed line (refer to Figure 3).




Figure 3 – Proposed Construction of New Dasmariñas-FCIE 115 kV Line (Alternative 2)

Alternative 3: Construction of New Amadeo-FCIE 115 kV Line

This project involves the construction of around 15.1-kilometer of 115 kV line using 2-795 MCM ACSR conductor per phase. The new line will be built along the road from Amadeo substation up to FCIE substation. This project also includes the installation of 115 kV power circuit breakers and associated equipment and structures including protection/control equipment at Amadeo and FCIE substations for the termination of the proposed line (refer to Figure 4).




Figure 4 – Proposed Construction of New Amadeo-FCIE 115 kV Line (Alternative 3)

Table 4: Comparison of Project Alternatives

Alternative	Advantages	Disadvantages
Alternative 1 Rebuilding Portion of Dasmariñas-FCIE 115 kV Line	- Aside from addressing the N-1 contingency problem, this project can be completed faster and is the most economical among the alternatives because it will reuse existing Right-of-Way (ROW) and requires minimal reinforcement to carry the bundled conductors.	- This project will require interruptions of Dasmariñas-FCIE Line during construction period.
Alternative 2 Construction of New Dasmariñas-FCIE 115 kV Line	- This project will provide an additional corridor to Dasmariñas Delivery Point substation to supply bulk power to Cavite Sector, thus enabling the	- This project involves the construction of a new and longer sub-transmission line than Alternative 1 and requires the installation of protection and control equipment at Dasmariñas and FCIE

	system to accommodate higher load growth in the area.	substations, hence, requires a longer time to complete. It also requires acquisition of permits and ROW for the 4.9-kilometer line, making it more expensive than Alternative 1.
Alternative 3 Construction of New Amadeo-FCIE 115 kV Line	- This project will provide an additional corridor to Amadeo Delivery Point substation to supply bulk power to Cavite Sector, thus enabling the system to accommodate higher load growth in the area.	- This project involves the construction of a new and longer sub-transmission line than Alternatives 1 and 2 and installation of protection and control equipment at Amadeo and FCIE substations, and also, requires acquisition of permits and ROW for the 15.1-kilometer line. Hence, it will: (1) take a longer time to complete; and (2) increase the cost of implementing the.

Table 5: Financial Evaluation of Project Alternatives

Problem Description	N-1 contingency problem involving the Dasmariñas-FCIE 115 kV line				
Alternative	Project Name	Project Cost (P in M)	NPV (P in M)	IRR	B/C
1	Rebuilding Portion of Dasmariñas-FCIE 115 kV Line	75.91	440.40	64.67%	4.46
2	Construction of New Dasmariñas-FCIE 115 kV Line	138.20	366.20	40.32%	2.93
3	Construction of New Amadeo-FCIE 115 kV Line	351.42	129.06	20.10%	1.32

IV. Recommendation

Based on the technical and financial evaluation of the different alternatives it was deemed that the most economical solution to address the line overloading in the area during N-1 contingency is to implement the project 'Rebuilding Portion of Dasmariñas-FCIE 115 kV Line'. Upon completion, it also: (1) strengthened the sub-transmission backbone in the area; (2) provided adequate capacity to meet the increasing power demand; (3) and enabled MERLCO to accommodate new customer applications as well as future prospective large customers. In the same manner, this project improved the reliability of the sub-transmission system in the Cavite Sector as well as contributed on the system loss reduction program of MERALCO by an estimated 1,936,302 kWh annually.

V. Urgent Reason for Implementing in CY2015

In order to avert any loss of load in the Cavite Sector during N-1 contingency and improve the reliability of the sub-transmission system, the project was implemented immediately. In 2016, the worst case scenario would be the outage of Amadeo 1-300 MVA power transformer which would lead to 106% overloading of the Dasmariñas – FCIE 115 kV line. Said overloading would lead to cascaded trippings of adjacent 115 kV facilities and possible system blackout in the area. This would affect numerous customers including the 115 kV direct connect customer, San Miguel Corporation (SMC), and other large industrial customers connected to FCIE, TMC2, Gateway, and Rosario substations with a total load at risk of 220 MVA. Said load at risk would continue to increase due to the rapid load growth in the area if this condition would not be addressed immediately.

Annex A: Expenditure Summary
Annex B: Cost-Benefit Analysis
Annex C: Project Gantt Chart

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
Rebuilding Portion of Dasmariñas-FCIE 115 kV Line		Forecast (US\$, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers				
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution	941,720			
	Overhead Conductors and Devices - Distribution	4,175			
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Transferred subtransmission assets				
Materials					
Subtrans					
Sub-total Regulated Distribution Services		945,894	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
Materials					
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		945,894	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY							
Capital Expenditure - Major Projects							
US\$ Expenditure (including all international expenditure)							
PROJECT NAME:				CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
Rebuilding Portion of Dasmariñas-FCIE 115 kV Line				Forecast (US\$, real) (Regulatory Year)			
Category				2016	2017	2018	2019
Regulated Distribution Services Assets							
Network	Land and Land Rights (Distribution Purposes)						
	Structures and Improvements (Distribution Purposes)						
	Station Equipment						
	Power transformers						
	Switchgear						
	Protective equipment						
	Metering & control equipment						
	Communications equipment						
	Other station equipment						
	Poles, Towers and Fixtures - Distribution	941,720					
	Overhead Conductors and Devices - Distribution	4,175					
	Underground Conduits - Distribution						
	Underground Conductors and Devices - Distribution						
	Distribution Transformers						
	Power Conditioning Equipment						
	Meters, Metering Instruments & Metering Transformers - Distribution						
	Information technology equipment (distribution)						
	Regulated Entity Property on Consumer's Premises						
	Street Lights and Signal Systems						
	Submarine Cables						
Non-network	Land and Land Rights (non-network)						
	Structures and Improvements (non-network)						
	Office Furniture and Equipment						
	Transportation Equipment						
	Stores Equipment						
	Tools, Shop and Garage Equipment						
	Laboratory Equipment						
	Information Systems Equipment (non-network)						
	Power-operated Equipment						
	Communication Plant and Equipment						
	Miscellaneous Equipment						
Materials	Materials and supplies (including spares)						
Subtrans	Transferred subtransmission assets						
Sub-total Regulated Distribution Services				945,894	0	0	0
Distribution Connection Services Assets							
Network	Poles, Towers and Fixtures (Customer)						
	Overhead Conductors and Devices (Customer)						
	Underground Conduits (Customer)						
	Underground Conductors and Devices (Customer)						
	Line Transformers (Customer)						
	Information Systems Equipment (Connection)						
Non-network	Land and Land Rights (non-network)						
	Structures and Improvements (non-network)						
	Office Furniture and Equipment						
	Transportation Equipment						
	Stores Equipment						
	Tools, Shop and Garage Equipment						
	Laboratory Equipment						
	Information Systems Equipment (non-network)						
	Power-operated Equipment						
	Communication Plant and Equipment						
	Miscellaneous Equipment						
Materials	Materials and supplies (including spares)						
Sub-total Distribution Connection Assets				0	0	0	0
Regulated Retail Services Assets							
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)						
	Land and land rights						
	Structures and improvements						
	Office Furniture and Equipment						
	Transportation Equipment						
	Stores Equipment						
	Tools, Shop and Garage Equipment						
	Laboratory Equipment						
	Information Systems Equipment						
	Communication Plant and Equipment						
	Miscellaneous Equipment						
Sub-total Regulated Retail Services Assets				0	0	0	0
TOTAL CAPEX				945,894	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
Rebuilding Portion of Dasmarinas-FCIE 115 kV Line					
		Forecast (Php, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers				
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution	21,816,794			
	Overhead Conductors and Devices - Distribution	12,649,703			
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		34,466,497	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
	Information Systems Equipment (Connection)				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		34,466,497	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
Rebuilding Portion of Dasmariñas-FCIE 115 kV Line					
		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	0	0	0	0
	Structures and Improvements (Distribution Purposes)	0	0	0	0
	Station Equipment	0	0	0	0
	Power transformers	0	0	0	0
	Switchgear	0	0	0	0
	Protective equipment	0	0	0	0
	Metering & control equipment	0	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	0	0	0	0
	Poles, Towers and Fixtures - Distribution	63,080,596	0	0	0
	Overhead Conductors and Devices - Distribution	12,832,633	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Transferred subtransmission assets	0	0	0	0
	Sub-total Regulated Distribution Services	75,913,229	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
Non-network	Information Systems Equipment (Connection)	0	0	0	0
	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Sub-total Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		75,913,229	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS

(COST X 1,000)

PROJECT: Rebuilding Portion of Gasarinas-Fore 115 kv line (Alternative 1)

2016	2015
------	------

REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (\$/KWH)	PURCH. POWER (\$/KWH)	W/ LOSS	S	X	P	E	H	S	S	S	TOTAL EXPENSES	ENERGY SALES (MWH)	SELLING RATE (\$/KWH)	NET REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX (W/ DEPRECIATION ADDED BACK)	FREE CASH FLOW
0	2016	75,913	-	75,913	6.94	7.69										433,282	53,354	9.23	512,375	79,083	23,735	55,369	-	75,913
1	2017	35,897	35,897	35,897	7.23	8.00					426,966					432,789		9.60					57,888	
2	2018	2,458	2,458	456,483	7.52	8.33					456,483					452,789		9.99	54,814	547,681	25,433	54,814	57,888	
3	2019	2,628	2,628	487,988	7.83	8.67					487,988					484,354		10.40	58,420	585,420	27,339	58,420	63,767	
4	2020	2,809	2,809	521,711	8.14	9.02					521,711					529,037		10.82	62,576	625,760	29,339	62,576	68,406	
5	2021	3,004	3,004	557,754	8.47	9.38					557,754					564,080		11.25	66,837	668,379	31,440	66,837	70,936	
6	2022	3,274	3,274	596,287	8.82	9.76					596,287					603,372		11.71	71,490	714,970	33,479	71,490	75,890	
7	2023	3,433	3,433	637,482	9.18	10.16					637,482					645,411		12.18	76,423	764,237	35,501	76,423	80,649	
8	2024	3,670	3,670	681,523	9.55	10.57					681,523					689,608		12.67	81,900	819,900	37,530	81,900	86,300	
9	2025	3,924	3,924	728,606	9.95	11.00					728,606					736,691		13.19	87,919	879,919	39,483	87,919	92,335	
10	2026	4,186	4,186	778,942	10.34	11.45					778,942					786,027		13.72	93,361	933,361	41,430	93,361	98,250	
11	2027	4,548	4,548	832,756	10.76	11.92					832,756					840,600		14.26	99,888	999,888	43,500	99,888	104,684	
12	2028	4,984	4,984	890,287	11.20	12.40					890,287					899,133		14.85	1,065,672	1,065,672	45,633	1,065,672	110,954	
13	2029	5,458	5,458	951,793	11.65	12.90					951,793					959,639		15.45	1,135,912	1,135,912	47,813	1,135,912	117,808	
14	2030	5,968	5,968	1,017,549	12.12	13.43					1,017,549					1,025,393		16.08	1,208,462	1,208,462	49,999	1,208,462	125,932	
15	2031	6,508	6,508	1,087,847	12.62	13.97					1,087,847					1,095,651		16.73	1,283,425	1,283,425	52,200	1,283,425	134,748	
16	2032	6,326	6,326	1,163,348	13.14	14.54					1,163,348					1,171,605		17.40	1,362,174	1,362,174	54,451	1,362,174	144,744	
17	2033	6,656	6,656	1,243,348	13.68	15.12					1,243,348					1,251,951		18.11	1,445,108	1,445,108	56,700	1,445,108	154,399	
18	2034	7,159	7,159	1,328,606	14.22	15.88					1,328,606					1,337,843		18.84	1,530,654	1,530,654	59,013	1,530,654	167,940	
19	2035	7,653	7,653	1,410,259	14.80	16.38					1,410,259					1,420,680		19.50	1,620,264	1,620,264	61,275	1,620,264	175,300	
20	2036	8,181	8,181	1,498,810	15.40	17.05					1,498,810					1,508,184		20.20	1,700,264	1,700,264	63,700	1,700,264	183,609	
21	2037	8,810	8,810	1,590,259	16.02	17.74					1,590,259					1,600,574		21.22	1,817,459	1,817,459	66,872	1,817,459	194,285	
22	2038	9,351	9,351	1,687,937	16.67	18.46					1,687,937					1,697,856		21.88	1,942,668	1,942,668	70,701	1,942,668	201,339	
23	2039	9,997	9,997	1,789,383	17.35	19.21					1,789,383					1,799,574		22.08	2,076,537	2,076,537	74,733	2,076,537	216,368	
24	2040	10,687	10,687	1,896,332	18.05	19.99					1,896,332					1,906,745		22.97	2,219,632	2,219,632	79,754	2,219,632	231,528	
25	2041	11,428	11,428	2,012,741	18.79	20.80					2,012,741					2,023,595		23.90	2,372,583	2,372,583	85,887	2,372,583	247,721	
26	2042	12,278	12,278	2,142,000	19.55	21.85					2,142,000					2,153,104		24.87	2,536,084	2,536,084	97,913	2,536,084	265,015	
27	2043	13,059	13,059	2,285,323	20.34	22.93					2,285,323					2,296,145		25.87	2,710,847	2,710,847	108,074	2,710,847	283,486	
28	2044	13,961	13,961	2,435,032	21.17	24.44					2,435,032					2,445,165		26.92	2,897,654	2,897,654	118,281	2,897,654	302,682	
29	2045	14,826	14,826	2,592,567	22.03	25.40					2,592,567					2,603,288		28.01	3,097,334	3,097,334	129,531	3,097,334	326,381	
30	2046	15,557	15,557	2,771,676	22.92	26.39					2,771,676					2,781,797		30.32	3,310,775	3,310,775	140,812	3,310,775	346,783	
											2,963,159					2,973,280			3,538,523	3,538,523			370,284	
																							395,951	
																								352,552

Ad:1

१३२

10. **Q.** What is the difference between a "contract" and a "contractual agreement"?

25

10

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: Construction of New Data-trans-File 115 Ky Line (Alternative 2)
YEAR 2016

[illegible]

NPV	IPP	B+C
12	12	12
11	11	11
10	10	10
9	9	9
8	8	8
7	7	7
6	6	6
5	5	5
4	4	4
3	3	3

ANNEX B: COST-BENEFIT ANALYSIS

FINANCIAL ANALYSIS
(Cost x 1,000)
Project: Construction of New Andeco-FIE 115 kV Line (Alternative 3)
Year: 2016

REF YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	I N V E S T M E N T S										E X P E N D I T U R E										R E V E N U E										E A R N I N G S		FREE CASH FLOW
			TOTAL INVESTMENTS	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	PURCH. POWER (P/KWH)	W/ LOSS	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MWH)	SELLING PRICE (P/KWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX (% DEPRECIATION ADDED BACK)													
0 2016	351,420	-	351,420	6.94	7.69	8.00	8.33	8.67	9.02	9.38	9.75	10.16	10.57	703,158	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	7.51	52,869	(351,420)				
1 2017	38,174	2,536	40,710	7.23	8.00	8.33	8.67	9.02	9.38	9.75	10.16	10.57	10.98	538,274	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	8.17	57,094	58,564				
2 2018	2,536	2,711	5,247	7.83	8.67	9.02	9.38	9.75	10.16	10.57	10.98	11.39	11.80	613,224	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	8.47	61,575	58,564				
3 2019	2,711	2,899	5,610	8.14	9.02	9.38	9.75	10.16	10.57	10.98	11.39	11.80	12.21	651,217	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	8.77	66,361	68,373				
4 2020	3,089	3,666	6,755	8.82	9.75	10.16	10.57	10.98	11.39	11.80	12.21	12.62	13.03	689,016	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	9.10	71,472	74,470				
5 2021	3,666	3,542	7,208	9.16	10.16	10.57	10.98	11.39	11.80	12.21	12.62	13.03	13.44	726,815	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	9.43	74,740	76,758				
6 2022	3,542	3,787	7,329	9.48	10.48	10.89	11.29	11.69	12.09	12.49	12.89	13.29	13.69	764,614	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	9.76	76,855	78,863				
7 2023	3,787	4,048	7,835	9.94	11.00	11.45	11.80	12.21	12.62	13.03	13.44	13.85	14.26	802,413	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	10.09	80,300	82,318				
8 2024	4,048	4,328	8,376	10.34	11.45	11.80	12.21	12.62	13.03	13.44	13.85	14.26	14.67	840,212	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	10.48	82,740	84,758				
9 2025	4,328	4,920	9,248	10.76	11.92	12.40	12.80	13.20	13.60	14.00	14.40	14.80	15.20	878,011	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	10.87	86,527	88,545				
10 2026	4,920	5,288	10,208	11.20	12.40	12.90	13.40	13.90	14.40	14.90	15.40	15.90	16.40	915,810	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	11.29	88,912	90,930				
11 2027	5,288	5,654	10,942	11.65	12.90	13.40	13.90	14.40	14.90	15.40	15.90	16.40	16.90	953,609	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	11.65	91,291	93,309				
12 2028	5,654	6,044	11,698	12.13	13.40	13.90	14.40	14.90	15.40	15.90	16.40	16.90	17.40	991,408	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	12.13	93,671	95,689				
13 2029	6,044	6,755	12,799	12.62	13.90	14.40	14.90	15.40	15.90	16.40	16.90	17.40	17.90	1,029,207	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	12.62	98,042	100,060				
14 2030	6,755	7,385	14,140	13.13	14.54	15.00	15.40	15.80	16.20	16.60	17.00	17.40	17.80	1,067,006	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	13.13	100,413	102,431				
15 2031	7,385	8,008	15,393	13.66	15.13	15.60	16.00	16.40	16.80	17.20	17.60	18.00	18.40	1,104,805	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	13.66	102,764	104,782				
16 2032	8,008	8,917	16,925	14.22	15.74	16.20	16.60	17.00	17.40	17.80	18.20	18.60	19.00	1,142,604	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	14.22	105,109	107,127				
17 2033	8,917	9,916	18,833	14.80	16.38	16.80	17.20	17.60	18.00	18.40	18.80	19.20	19.60	1,180,403	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	14.80	107,454	109,472				
18 2034	9,916	10,964	20,880	15.40	17.05	17.40	17.80	18.20	18.60	19.00	19.40	19.80	20.20	1,218,202	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	15.40	109,799	111,817				
19 2035	10,964	12,072	23,036	16.02	17.74	18.00	18.40	18.80	19.20	19.60	20.00	20.40	20.80	1,256,001	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	16.02	112,144	114,162				
20 2036	12,072	13,474	25,546	16.67	18.46	18.70	19.10	19.50	19.90	20.30	20.70	21.10	21.50	1,293,800	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	16.67	114,489	116,507				
21 2037	13,474	14,404	27,878	17.33	19.17	19.40	19.80	20.20	20.60	21.00	21.40	21.80	22.20	1,331,600	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	17.33	116,816	118,834				
22 2038	14,404	15,400	30,804	18.00	20.00	20.20	20.60	21.00	21.40	21.80	22.20	22.60	23.00	1,369,400	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	119,141	121,159				
23 2039	15,400	16,463	33,863	18.75	20.85	21.00	21.40	21.80	22.20	22.60	23.00	23.40	23.80	1,407,200	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	18.75	121,466	123,484				
24 2040	16,463	17,835	36,298	19.55	21.75	21.90	22.30	22.70	23.10	23.50	23.90	24.30	24.70	1,445,000	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	19.55	123,791	125,809				
25 2041	17,835	19,222	39,057	20.34	22.65	22.80	23.20	23.60	24.00	24.40	24.80	25.20	25.60	1,482,800	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	20.34	126,106	128,124				
26 2042	19,222	20,638	42,860	21.17	23.58	23.70	24.10	24.50	24.90	25.30	25.70	26.10	26.50	1,520,600	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	21.17	128,421	130,439				
27 2043	20,638	22,072	46,710	22.03	24.54	24.60	25.00	25.40	25.80	26.20	26.60	27.00	27.40	1,558,400	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	22.03	130,736	132,754				
28 2044	22,072	23,528	50,600	22.92	25.39	25.40	25.80	26.20	26.60	27.00	27.40	27.80	28.20	1,596,200	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	22.92	133,051	135,069				
29 2045	23,528	25,318	54,846	23.85	26.36	26.40	26.80	27.20	27.60	28.00	28.40	28.80	29.20	1,634,000	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	23.85	135,366	137,384				
30 2046	25,318	27,400	59,718	24.80	27.39	27.40	27.80	28.20	28.60	29.00	29.40	29.80	30.20	1,671,800	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	24.80	137,681	139,699				

NPV
IPV
B/C

129,061.91
20.11
1.32

RY2016 CAPEX:
Capital Expenditure Projects

ANNEX "A-3" 

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 4	REPLACEMENT OF POWER TRANSFORMER NO. 2 AT MANDALUYONG SUBSTATION	December 18, 2015	52,908,466

I. Project Background:

Due to its old age, the 22-year old power transformer # 2 (NLTC – No Load Tap Changer) at the Mandaluyong substation has not been delivering the regulated voltage quality to the customers it serves. Furthermore, it is likewise not being utilized to meet its optimal capacity to accommodate the additional load applications in the Mandaluyong and Pasig commercial area. At present, the voltage regulation of transformer # 2 cannot be automatically controlled and therefore needs human intervention. This entails frequent manual switching of the secondary and bus tie breakers during off-peak when needed in order to shift the loads normally carried by transformer # 2 to transformer # 1. This operation is only a stop gap measure to remedy the high voltage problem and cater to customer needs. However, even with this stop gap measure, there are still customer complaints of voltage quality problems.

The loads in the Pasig and Mandaluyong areas are served by feeders from SM-Shangri-la, Rockwell and Mandaluyong substations. All the power transformers in SM-Shangri-la substation, Rockwell substation and bank # 1 in the Mandaluyong substation are with On-Load Tap Changers (OLTCs) and as such, the voltage quality of the feeders carried by these transformers are regulated automatically. Since the Mandaluyong transformer # 2 has no OLTC, its flexibility of tying and carrying the feeder loads, which are normally served by the Mandaluyong power transformer # 1, Shangri-la and Rockwell power transformers, are diminished and will result in voltage regulation problems if load shifting is undertaken at any given time. In addition, the N -1 contingency function of transformer # 2 to carry the loads of transformer # 1 is not utilized. Moreover, there is also the constraint of load distribution balancing in the Mandaluyong and Pasig areas, which are served by SM-Shangri-la, Rockwell, and Mandaluyong substations.

From the foregoing, the replacement of the Mandaluyong power transformer # 2 with a new 83 MVA power transformer with OLTC resulted in the delivery of quality voltage regulation to customers. Further, the project provided the flexibility in tying the configuration of its feeders and load balancing in the Mandaluyong and Pasig areas sourcing its energy from the power transformers in SM-Shangri-la, Rockwell, and Mandaluyong (transformer # 1) substations.

II. Technical Analysis

Table I shows the voltage quality complaints by major customers normally served by Mandaluyong power transformer # 2. During off peak periods, the loads of transformer # 2 are shifted to transformer # 1 – the system operator regularly monitors the voltage and manually operates transformer # 2 secondary breaker and closes the bus tie breaker. These manual operations are corrective measures for voltage regulation since transformer # 1 has OLTC and automatically regulates the voltage. Transformer # 1 carries all the loads of the Mandaluyong substation (one bank operation) during off peak periods.

Table I: List of Voltage Quality Complaints of Major Customers

No.	Complainant	SIN	TLN	Circuit	Nature of Complaint
1	Primex Printers Inc.	310032080101	128343	54VD	High Voltage
2	HTCG Premium Food Concepts Inc.	310073170101	378034	53VD	High Voltage
3	JELP Real Estate Development Corp.	100158320101	992271	53VD	Low Voltage

4	Paragon Plaza	100043500101	093974	52VD	Fluctuating Voltage
5	Linkem Trading Corp.	160483401	022169	53VD	Low Voltage

Additionally, Table II shows the major customers in Mandaluyong and Pasig City, served by feeders from SM-Shangri-la, Rockwell and Mandaluyong substations, applying for additional loads. At present, the initial load of 8 MVA is served by the Mandaluyong transformer #1, Rockwell transformer #4 and SM-Shangri-la transformer #1. Normally, Mandaluyong transformer #2 is at 34% loading but it will be 0% during peak load since its loads will be carried by transformer #1.

Furthermore, because of the expected additional loads and realization of all customer applications in the area (total of 32.16 MVA), there will be a capacity deficiency of 24.16 MVA and the transformers (Mandaluyong #1, Rockwell #4, and SM-Shangri-la #2) will be critically loaded as high as 82%. The constraint of realizing the additional loads and load balancing among the said substation transformers is the absence of automatic voltage regulation of Mandaluyong transformer #2.

Table II: Large customer Applications in Mandaluyong and Pasig Area

Customers	Ultimate Load (MVA)	Present Load (MVA)	Remarks	Energization Date
St. Francis BSA Twin Towers	4.00	1.00	Currently served by SM-Shangri-la 44VR to be shifted to Mandaluyong 43VD	Energized 2011 but not in full capacity
Harmony Homes Inc.	2.10	1.00	Currently served by Mandaluyong 53VD	Energized 2011 but not in full capacity
SMDC Light Residences	10.56	2.00	Currently served by New Rockwell 445VV to be unloaded by Mandaluyong 54VD	Energized 2011 but not in full capacity
Robinsons Land Corporation (Cyberscape Alpha)	6.5	1.00	Currently served by Mandaluyong 44VD	Energized 2014 but not in full capacity
Podium and BDO Ortigas Tower	9.00	3.00	Currently served by SM-Shangri-la 44VR to be shifted to Mandaluyong 44VD	Existing Podium and additional load in 2015-2016
Total	32.16	8.00		
Additional Capacity Needed	24.16			

III. Project Alternatives

In the process of determining the most cost-effective solution to address the identified deficiencies, MERALCO generated technically feasible alternatives that could satisfy the distribution system requirements in a timely and efficient manner. Table III shows the summary of technically feasible projects that were evaluated.

Table III: Project Alternatives

Problem Description	Voltage quality complaints of major customers, as well as, the expected capacity deficiency due to the realization of additional load applications in the area.	
Alternative	Project Name	Classification
1	Replacement of Power Transformer No. 2 at Mandaluyong Substation	Stand-alone
2	Development of Wack-Wack 115kV-34.5kV GIS Substation	Stand-alone
3	Operate and Maintain the Power Transformer	Stand-alone

The descriptions of the project alternatives are summarized below:

Alternative 1:

This project alternative is the replacement of the 83MVA power transformer no.2 (NLTC) with a new 83 MVA power transformer with OLTC. This will address the voltage quality problem experienced by customers since the OLTC will automatically regulate voltage at the desired level. The project will also optimize the transformers load capacity in Mandaluyong since there will be flexibility of load shifting and balancing of feeder loads carried by the Mandaluyong transformers, SM-Shangri-la and Rockwell substation transformers.

Alternative 2:

The project is the development of a new 115kV-34.5kV GIS substation at Wack-Wack area located within a kilometer radius from the existing Mandaluyong substation. The project will resolve the voltage quality problem and can cater additional load applications at Pasig and Mandaluyong areas.

Alternative 3:

The use and continuous operation of the existing power transformer no. 2 (NLTC) will result to continuous voltage quality problem experienced by customers. The manual intervention of Meralco system operator to correct the voltage problem of customer through monitoring and shifting loads of Mandaluyong bank 2 (with OLTC) is a stop gap solution. The transformer #2 secondary breaker and bus tie breaker will be frequently operated, however, this is not the normal practice in the electric industry. Also, there are still customer voltage complaints even with the shifting of loads correction.

Also with this alternative, the transformer load capacity is not optimized and the voltage quality output to customers will remain a problem.

MERALCO also considered other alternatives, such as the installation of automatic voltage regulators (AVRs) at the 3 feeders of Mandaluyong power transformer # 2. However, installation of AVRs cannot technically resolve the capacity problems and flexibility of load shifting with other power transformers with OLTC. Besides the main reason mentioned, installation of AVRs inside the substation and along the Pasig and Mandaluyong commercial areas are not also feasible due to unavailability of space and safety clearances and the perennial right of way permit problems along the commercial area.

Table IV summarizes the comparison of the advantages and disadvantages of the project alternatives with respect to Operate and Maintain (no project), whereas Table V shows the summary of financial evaluations of the project alternatives.

Table IV: Comparison of Project Alternatives

Alternative	Advantages	Disadvantages
Alternative 1: Replacement of Power Transformer No. 2 at Mandaluyong Substation	<ul style="list-style-type: none"> - Since voltage regulation is automatically controlled, customers voltage quality will be resolved - Flexible load shifting contingencies - Flexible load balancing of feeders sourced from Mandaluyong, SM-Shangri-la and Rockwell 	-no significant disadvantages

	- Optimize Mandaluyong transformer #2 load capacity.	
Alternative 2: Development of Wack-Wack 115kV-34.5kV GIS Substation	<ul style="list-style-type: none"> - Since voltage regulation is automatically controlled, customers voltage quality will be resolved - All additional loads can be accommodated - Flexible load shifting contingencies 	-high initial capital expenditure or investment compared to alternative 1
Alternative 3: Operate and Maintain the Power Transformer	- No significant advantages	<ul style="list-style-type: none"> - customer voltage problem - impractical and frequent manual switching operations of bus tie breaker which can cause premature mechanical breakdown of the breakers - will require frequent maintenance of the breakers due to frequent operations

Table V: Financial Evaluation of Project Alternatives

Alternative	Project Name	Project Cost (PhP)	NPV (PhP)	FIRR	B/C Ratio
1	Replacement of Power Transformer No. 2 at Mandaluyong Substation	52,908,466	4,016,096	16.73%	1.08
2	Development of Wack-Wack 115kV-34.5kV GIS Substation	448,130,899	3,547,294	15%	1.01
3	Operate and Maintain the Power Transformer	3,610,449.56	136,393	11.31%	0.13

IV. Recommendation

Based on the technical and financial evaluation of the different alternatives it was deemed that the most economical solution to address the capacity deficiency and voltage problem in the area is to implement Alternative # 1, the Replacement of Power Transformer No. 2 at Mandaluyong Substation with a new 83 MVA power transformer with OLTC, considering the needed higher cost of investment of Alternative # 2. By implementing the project, the new power transformer will deliver quality voltage regulation to customers due to its OLTC automatic control. The project will likewise provide flexible tying configuration of its feeders and load balancing in the the Mandaluyong and Pasig areas which are sourced from power transformers in SM-Shangri-la, Rockwell, and Mandaluyong (transformer #1) substations. In addition, this project will optimize the load capacity of the Mandaluyong substation transformers and improve the reliability and quality of service to customers in the Pasig and Mandaluyong areas. The replaced power transformer can be used for other projects.

V. Urgent Reason for Implementing in CY2015:

The project was implemented as a solution to resolve the capacity deficiency and voltage quality complaints by major customers normally served by Mandaluyong power transformer # 2 (NLTC).

Even before the filing of the project with the ERC on February 2015, MERALCO received voltage quality complaints from major customers served by the Mandaluyong power transformer # 2. Meralco tried to address the same by filing the project to ERC with a target implementation of December 2016. However, by August 2015, apart from the voltage complaints, MERALCO was experiencing capacity deficiency in high density urban areas of Mandaluyong and nearby Pasig commercial areas being served by Mandaluyong substation, Rockwell Bank No. 4 and SM-Shangri-la Bank No. 1 due to the large customer applications in the area. Considering the realization of ultimate loads of large developments in the area ahead of schedule, the affected power transformer banks would have been critically loaded to as high as 87% due to the constraint in the load

balancing among the said substation transformers with the absence of an OLTC of the Mandaluyong power transformer # 2, if the project was not implemented.

The replacement project was implemented in CY 2015 and the new Mandaluyong power transformer # 2 with OLTC was energized in December 18 of the same year. The project was immediately implemented so as not to jeopardize the quality and reliability of service in the affected areas.

Annex A: Expenditure Summary

Annex B: Cost-Benefit Analysis

Annex C: Project Gantt Chart.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
REPLACEMENT OF POWER TRANSFORMER NO. 2 AT MANDALUYONG SUBSTATION					
		Forecast (Php, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers	2,722,996			
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution				
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
	Sub-total Regulated Distribution Services	2,722,996	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
	Information Systems Equipment (Connection)				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
	Sub-total Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		2,722,996	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
REPLACEMENT OF POWER TRANSFORMER NO. 2 AT MANDALUYONG SUBSTATION					
		Forecast (US\$, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers	1,145,329			
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution				
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Transferred subtransmission assets				
	Sub-total Regulated Distribution Services	1,145,329	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		1,145,329	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (Php, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
REPLACEMENT OF POWER TRANSFORMER NO. 2 AT MANDALUYONG SUBSTATION					
		Forecast (Php, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets.					
Network	Land and Land Rights (Distribution Purposes)	0	0	0	0
	Structures and Improvements (Distribution Purposes)	0	0	0	0
	Station Equipment				
	Power transformers	52,908,466	0	0	0
	Switchgear	0	0	0	0
	Protective equipment	0	0	0	0
	Metering & control equipment	0	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	0	0	0	0
	Poles, Towers and Fixtures - Distribution	0	0	0	0
	Overhead Conductors and Devices - Distribution	0	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
Subtrans	Transferred subtransmission assets	0	0	0	0
Sub-total Regulated Distribution Services		52,908,466	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
Non-network	Information Systems Equipment (Connection)	0	0	0	0
	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		52,908,466	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST-BENEFIT ANALYSIS

Project Name: Replacement of Power Transformer No. 2 at Mandaluyong Substation

Year	Investment	Savings in Purch. Power Cost (Including System Loss)	Savings In O&M	Savings In Unserved Energy	Total Revenue	Net Cash Flow
0	(52,908,466.33)				2,645,423.32	(52,908,466)
1		2,863,610	2,911,397	3,613,162	9,388,169	9,388,169
2		2,978,155	2,940,511	3,757,689	9,676,354	9,676,354
3		3,097,281	2,969,916	3,907,996	9,975,193	9,975,193
4		3,221,172	2,999,615	4,064,316	10,285,103	10,285,103
5		3,350,019	3,029,611	4,226,889	10,606,519	10,606,519
6		3,484,020	3,059,907	4,395,964	10,939,891	10,939,891
7		3,623,381	3,090,506	4,571,803	11,285,690	11,285,690
8		3,768,316	3,121,411	4,754,675	11,644,402	11,644,402
9		3,919,048	3,152,625	4,944,862	12,016,536	12,016,536
10		4,075,810	3,184,152	5,142,657	12,402,619	12,402,619
11		4,111,697	3,215,993	5,187,937	12,515,628	12,515,628
12		4,111,697	3,248,153	5,187,937	12,547,787	12,547,787
13		4,111,697	3,280,635	5,187,937	12,580,269	12,580,269
14		(1,027,924)	(383,341)	(1,296,984)	(2,708,250)	(2,708,250)
15		(1,027,924)	(387,174)	(1,296,984)	(2,712,083)	(2,712,083)
16		(1,027,924)	(391,046)	(1,296,984)	(2,715,955)	(2,715,955)
17		(1,027,924)	(394,957)	(1,296,984)	(2,719,865)	(2,719,865)
18		(1,027,924)	(398,906)	(1,296,984)	(2,723,815)	(2,723,815)
19		(1,027,924)	(402,895)	(1,296,984)	(2,727,804)	(2,727,804)
20		(1,027,924)	(406,924)	(1,296,984)	(2,731,833)	(2,731,833)
21		(1,027,924)	(410,993)	(1,296,984)	(2,735,902)	(2,735,902)
22		(1,027,924)	(415,103)	(1,296,984)	(2,740,012)	(2,740,012)
23		(1,027,924)	(419,254)	(1,296,984)	(2,744,163)	(2,744,163)
24		(1,027,924)	(423,447)	(1,296,984)	(2,748,356)	(2,748,356)
25		(1,027,924)	(427,681)	(1,296,984)	(2,752,590)	(2,752,590)
26		(1,027,924)	(431,958)	(1,296,984)	(2,756,867)	(2,756,867)
27		(1,027,924)	(436,278)	(1,296,984)	(2,761,186)	(2,761,186)
28		(1,027,924)	(440,641)	(1,296,984)	(2,765,549)	(2,765,549)
29		(1,027,924)	(445,047)	(1,296,984)	(2,769,956)	(2,769,956)
30		(1,027,924)	(449,498)	(1,296,984)	(2,774,406)	(2,774,406)

WACC	14.97%
------	--------

NPV	4,016,096
FIRR	16.73%
B/C Ratio	1.08

ANNEX B: COST-BENEFIT ANALYSIS

Project Description: Operate and Maintain the Power Transformer

Year	Investment	Savings in Purch. Power Cost (Including System Loss)	Savings In O&M	Savings In Unserved Energy	Total Revenue	Net Cash Flow
0						
1	-	1,073,854	(2,420,899)	1,354,936	7,891	0
2	(2,042,089.91)	1,116,808	(2,445,108)	1,409,133	80,833	7,891
3	-	1,161,480	(2,469,559)	1,465,499	157,420	(1,961,257)
4	-	1,207,940	(2,494,255)	1,524,119	237,803	157,420
5	(784,179.82)	1,256,257	(2,519,197)	1,585,083	322,143	237,803
6	-	1,306,507	(2,544,389)	1,648,487	410,605	(462,037)
7	-	1,358,768	(2,569,833)	1,714,426	503,361	410,605
8	(784,179.82)	1,413,118	(2,595,532)	1,783,003	600,590	503,361
9	-	1,469,643	(2,621,487)	1,854,323	702,480	(183,590)
10	-	1,528,429	(2,647,702)	1,928,496	809,223	702,480
11	-	1,541,887	(2,674,179)	1,945,476	813,184	809,223
12	-	1,541,887	(2,700,921)	1,945,476	786,442	813,184
13	-	1,541,887	(2,727,930)	1,945,476	759,433	786,442
14		-	-	-	154,703	759,433
						154,703

WACC	14.97%
------	--------

NPV	136,393
FIRR	11.31%
B/C Ratio	0.13

ANNEX C: GANTT CHART

Name of Project:

Target Completion:

REPLACEMENT OF POWER TRANSFORMER NO. 2 AT MANDALUYONG SUBSTATION

[illegible]

**RY2016 CAPEX:
Capital Expenditure Projects**

ANNEX "A-4"

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 5	CUT-IN OF PINAGBUHATAN SWITCHING STATION	November 2016	58,635,873

I. Project Background:

This project involves the construction of overhead 115 kV line with an approximate length of 0.7 kilometer using 2-795 MCM ACSR conductor per phase to cut-in SM Shangri-La-Dolores 115 kV line to the proposed Pinagbuhatan 115 kV Switching Station. This project also includes the construction of 115 kV bus and the installation of 115 kV breaker and associated disconnect switches, installation of control and protection equipment and construction of control house.

This project was originally filed as part of MERALCO's RY2016 Capital Expenditure application last February 9, 2015 and was included in the ten-year (10-year) Distribution Development Plan (DDP) of MERALCO that was previously submitted to the Department of Energy (DOE).

While the project at the time of the original filing was intended to address the load growth in the area, it came to a point that MERALCO was constrained to immediately implement the same as an emergency CAPEX to avert system deficiencies that will result in widespread power interruptions affecting customers in Taytay, Cainta, Pasig and portions of Marikina, Mandaluyong and Quezon City.

As a background, the main outlets of Dolores 230 kV-115 kV delivery point substation in MERALCO Sector 2 are the SM Shangri-La-Dolores 115 kV line, Dolores-Marikina Line, Dolores-Masinag Line, Marikina-Cubao Line, and Dolores-Cainta Line. The SM Shangri-La-Dolores 115 kV line carries bulk power from the Dolores delivery point substation and transport it to SM Shangri-La 115 kV-34.5 kV substation to cater to the residential, commercial and large industrial customers in portions of Pasig, Quezon City, and Mandaluyong such as Medical City, SM Megamall, EDSA Shangri-La Hotel, Energy Regulatory Commission and Pag-asa Steel Works, Inc. (PSWI).¹

MERALCO has to ensure at all times the reliability and security of the main outlets of Sector 2, including all lines/facilities connected thereto. Thus, MERALCO finds means to address all system constraints and deficiencies for the main corridors of Sector 2 such as the tapping configuration of the PSWI at SM Shangri La Dolores 115 kV line. With such set-up, SM Shangri La-Dolores line will be out of service when maintenance works are conducted at PSWI substation or when there has been fault/trouble thereat. The said customer substation will be isolated from the 115 kV grid by de-energizing the SM Shangri-La-Dolores line. During such condition, an outage of any of the Dolores-Cainta, Dolores-Masinag, Dolores-Marikina, Marikina-Cubao and Cubao-Hillcrest 115 kV lines will cause critical loading/overloading of the other 115 kV lines in Sector 2. This will result in widespread power interruption affecting customers in Taytay, Cainta, Pasig and portions of Marikina, Mandaluyong and Quezon City.

Thus, there is a need to develop the 115 kV Pinagbuhatan switching station in order to address such system constraints and deficiencies. The cut-in connection will protect MERALCO's 115 kV system from cascaded tripping of its 115 kV lines. As above-mentioned, such tripping of 115 kV lines will emanate from outage of SM Shangri-La-Dolores line caused by the trouble at customer's substation and one of Dolores delivery point substation's 115 kV outlets.

This project will also provide N-1 contingency for SM Shangri-La-Dolores line and will therefore enhance/strengthen the reliability of the 115 kV system in Sector 2. The implementation of the project will not expose the SM Shangri-La-Dolores line to risks of interruptions.

¹ PSWI will be connected by MERALCO's distribution system in the last quarter of 2016.

With the switching station in place, in case there is a fault on either line leg, PSWI will be isolated from and would not affect MERALCO's distribution system. Restoration works of the faulted leg may be conducted independently and without affecting the normal operations of the 115 kV system.

MERALCO will also have a freehand to operate, maintain, and rehabilitate the SM Shangri-La-Dolores line without constraints on the continuity of distribution service to PSWI.

II. Technical Analysis

In planning the expansion of its distribution system, MERALCO adheres to the following policies and criteria:

2.1 Subtransmission Planning Policies

- a. Subtransmission lines and delivery point substation power transformers shall comply with the N-1 provision
- b. Adequate subtransmission feeds shall be provided to all substations to ensure reliability of power supply;
- c. Subtransmission development plans should be aligned with relevant NGCP, NPC, IPP and Government Projects
- d. Delivery Point substation and subtransmission line projects should be financially viable.

2.2 Subtransmission Planning Criteria

- a. Subtransmission lines shall not be loaded beyond 90% of its rated capacity during N-1 contingency.
- b. Delivery point power transformers shall not be loaded beyond 100% of its FA2 rating during N-1 contingency.
- c. Bus voltage regulation shall be within $\pm 5\%$ of nominal voltage during normal condition and within $\pm 10\%$ during N-1 condition.
- d. Bus fault duty should not exceed 90% of the equipment interrupting rating.
- e. There should be no loss of load during N-1 contingency.

MERALCO exerts its best effort to address all possible concerns/problems with its sub-transmission lines. This includes ensuring that all connections are properly maintained and secured. It is for these reasons that MERALCO deems it necessary to develop a new switching station to facilitate disconnection of a customer from the grid during fault condition or trouble in said customer's substation to protect its 115 kV system from cascaded tripping of its 115 kV lines due to outage of SM Shangri-La-Dolores line emanating from trouble at customer's substation and outage of one of Dolores delivery point substation's 115 kV outlets. MERALCO's ownership of the switching station will also ensure that it will have freedom to operate, maintain, and rehabilitate the SM Shangri-La-Dolores line without constraints with regard to the continuity of service to PSWI.

In 2016, in case SM Shangri-La-Dolores line is out-of-service due to fault of PSWI substation, and at the same time there is an outage of any of Dolores-Cainta, Dolores-Masinag, Dolores-Marikina, Marikina-Cubao and Cubao-Hillcrest 115 kV lines, such system conditions will definitely cause critical loading/overloading of several 115 kV lines in Sector 2 at a maximum of 111%. This incident will consequently result in power interruption affecting major customers in Taytay, Cainta, Pasig and portions of Marikina, Mandaluyong and Quezon City. **The maximum load at risk is around 398 MVA and will continue to increase if this project is not implemented.**

Without the project, the specific planning criteria that will be breached during outage of SM Shangri-La -Dolores 115 kV line and one of Dolores delivery point substation's 115 kV outlets are :

- a. Subtransmission lines shall not be loaded beyond 90% of its rated capacity during N-1 contingency;
- b. There should be no loss of load during N-1 contingency.

The forecasted load in case SM Shangri-La-Dolores 115 kV Line out-of-service due to trouble at PSWI customer substation with and without the project are provided in the tables below.

Table 1: 5- Year Forecasted Load Without Project (SM Shangri-La-Dolores 115 kV Line out-of-service due to trouble at PSWI customer substation)

PARAMETERS UNDER CONSIDERATION			PERCENT LOADING OF AFFECTED LINE DURING N-1 CONTINGENCY				
OUTAGE OF LINE DURING N-1 CONTINGENCY	AFFECTED SUBTRANSMISSION LINE DURING N-1 CONTINGENCY		RY2016	RY2017	RY2018	RY2019	RY2020
	LINE	CAPACITY (MVA)					
Dolores-Cainta Line	Dolores-Marikina Line	342.9	98%	101%	104%	107%	109%
	Dolores-Masinag Line		87%	90%	93%	96%	98%
	Marikina-Cubao Line		98%	101%	104%	107%	109%
Dolores-Masinag Line	Dolores-Cainta Line		98%	101%	104%	107%	109%
	Dolores-Marikina Line		111%	114%	117%	120%	122%
Dolores-Marikina Line	Dolores-Cainta Line		96%	99%	102%	105%	107%
	Dolores-Masinag Line		97%	100%	103%	106%	108%
Marikina-Cubao Line	Dolores-Cainta Line		105%	108%	111%	114%	116%
Cubao-Hillcrest Line	Dolores-Cainta Line		86%	89%	92%	95%	97%

Table 2: 5- Year Forecasted Load With Project (SM Shangri-La-Dolores 115 kV Line out-of-service due to trouble at PSWI customer substation)

PARAMETERS UNDER CONSIDERATION			PERCENT LOADING OF AFFECTED LINE DURING N-1 CONTINGENCY				
OUTAGE OF LINE DURING N-1 CONTINGENCY	AFFECTED SUBTRANSMISSION LINE DURING N-1 CONTINGENCY		RY2016	RY2017	RY2018	RY2019	RY2020
	LINE	CAPACITY (MVA)					
Dolores-Cainta Line	Dolores-Marikina Line		77%	80%	83%	86%	88%

	Dolores-Masinag Line	342.9	71%	74%	77%	80%	82%
	Marikina-Cubao Line		64%	67%	70%	73%	75%
Dolores-Masinag Line	Dolores-Cainta Line		76%	79%	82%	85%	87%
	Dolores-Marikina Line		79%	82%	85%	88%	90%
Dolores-Marikina Line	Dolores-Cainta Line		78%	81%	84%	87%	89%
	Dolores-Masinag Line		79%	82%	85%	88%	90%
Marikina-Cubao Line	Dolores-Cainta Line		78%	81%	84%	87%	89%
Cubao-Hillcrest Line	Dolores-Cainta Line		75%	78%	81%	84%	86%

III. Project Alternatives

In the process of determining the most cost-effective solution to address the identified system deficiencies, MERALCO generated technically feasible alternatives that could satisfy the distribution system requirements in a timely and efficient manner. In its evaluation and due to the immediate need to pursue the appropriate solution to address the system deficiencies, MERALCO was constrained to immediately pursue the first alternative. Table 3 shows the summary of technically feasible projects that are evaluated.

Table 3: Project Alternatives

Problem Description	The project alternatives intended to address the N-1 contingency problem involving several 115 kV lines in Sector 2 during planned maintenance or fault condition at PSWI customer substation.	
Alternative	Project Name	Classification
1	Cut-in of Pinagbuhatan Switching Station	Stand-alone
2	Construction of SM Shangri-La-Dolores 115 kV Line 2	Stand-alone
3	Construction of SM Shangri-La-Pinagbuhatan and Pinagbuhatan-Dolores 115 kV Lines	Stand-alone

Note: Applicant considered as an option maintaining the current set up where there is no switching station. However, the same will not address the above-mentioned N-1 contingency problem.

Alternative 1: Cut-in of Pinagbuhatan Switching Station

The proposed Pinagbuhatan 115 kV Switching Station is comprised of three (3) 115 kV power circuit breakers, six (6) 115 kV disconnect switches, two (2) 115 kV busses, protection and control equipment, construction of control house, and construction of 115 kV line with an approximate length of 700 meters using 2-795 MCM ACSR per phase conductor to cut-in SM Shangri-La-Dolores 115 kV line to Pinagbuhatan Switching Station (refer to Figure 1).

Project Cost (Php): 58,635,872.82




Figure 1 – Proposed Cut-in of Pinagbuhatan Switching Station (Alternative 1)

Alternative 2: Construction of SM Shangri-La-Dolores 115 kV Line 2

This project involves the installation of two (2) 115 kV power circuit breakers, four (4) 115 kV disconnect switches, and protection and control equipment at Dolores delivery point substation; installation of one (1) 115 kV GIS power circuit breaker and associated disconnect switches at SM Shangri-La substation; and construction of around 18.1 kilometers of overhead 115 kV line using 2-795 MCM ACSR conductor phase (refer to Figure 2).

Project Cost (Php): 405,338,149.64




Figure 2 – Proposed Construction of SM Shangri-La-Dolores 115 kV Line 2 (Alternative 2)

Alternative 3: Construction of SM Shangri-La-Pinagbuhatan and Pinagbuhatan-Dolores 115 kV Lines

This project involves the development of a 115 kV switching station comprised of: three (3) 115 kV power circuit breakers, six (6) 115 kV disconnect switches, two (2) 115 kV busses, protection and control equipment, construction of control house. This project also involves the installation of two (2) 115 kV power circuit breakers, four (4) 115 kV disconnect switches, and protection and control equipment at Dolores delivery point substation; installation of one (1) 115 kV GIS power circuit breaker and associated disconnect switches at SM Shangri-La substation; and construction of around 16.5 kilometers of overhead 115 kV line using 2-795 MCM ACSR conductor per phase (refer to Figure 3).

Project Cost (Php): 426,090,959.37




Figure 3 – Proposed Construction of SM Shangri-La-Pinagbuhatan and Pinagbuhatan-Dolores 115 kV Lines (Alternative 3)

Table 3: Comparison of Project Alternatives

Alternative	Advantages	Disadvantages
Alternative 1 Cut-in of Pinagbuhatan Switching Station	<p>This project will solve all of the above-mentioned system constraints and deficiencies.</p> <ul style="list-style-type: none"> The cut-in connection will protect MERALCO's 115 kV system from cascaded tripping of its 115 kV lines. As above-mentioned, such tripping of 115 kV lines will emanate from outage of SM Shangri-La-Dolores line caused by the trouble at customer's substation and one of Dolores delivery point substation's 115 kV outlets. The tap connection of PSWI will be converted to cut-in connection. Hence, any trouble/fault within PSWI substation will not impact/affect the Dolores-SM Shangri-La 115 kV line. Thus, this project will ensure a reliable 115 kV system in Sector 2; 	<ul style="list-style-type: none"> There is no significant disadvantage.

	<ul style="list-style-type: none"> • This project will also provide N-1 contingency for SM Shangri-La-Dolores line; • Likewise, this alternative will give MERALCO the full control of Dolores-SM-Shangri-La 115 kV corridor since MERALCO can perform maintenance, upgrading, or rehabilitation works on said line without having to secure permission from the customer. Thus, MERALCO can immediately address any constraints/problems that will be brought by the PSWI to the distribution system; • This project involves the shortest line route at around 700 meters, thus it will have the least exposure to risks of interrupting the existing SM Shangri-La Dolores line; • This project, among all options, is the most economical since it entails the least cost among project alternatives; • Minimal permit and ROW acquisition will be required for this alternative. Accordingly, the project will be completed earlier as compared to other project alternatives. 	
<p>Alternative 2</p> <p>Construction of SM Shangri-La-Dolores 115 kV Line 2</p>	<ul style="list-style-type: none"> • This will also provide an alternate feed/line in case of outage of the existing Shangri -La Dolores line due to fault/trouble in the PSWI substation. 	<ul style="list-style-type: none"> • This alternative will require construction of a longer line than Alternatives 1 ; • Alternative 2 is more expensive than Alternative 1 and likewise takes longer time to complete because unlike Alternative 1, Alternative 2 will require installation of protection and control equipment at Dolores delivery point substation and SM Shangri-La substation; • Likewise, the length that SM Shangri-La-Dolores

		<ul style="list-style-type: none"> 115 kV Line 2 will traverse substantially increases the risk of interrupting said line; the outage of existing Dolores-SM Shangri-La 115 kV line will still result in the outage of PSWI.
<p>Alternative 3</p> <p>Construction of SM Shangri-La-Pinagbuhatan and Pinagbuhatan-Dolores 115 kV Lines</p>	<ul style="list-style-type: none"> This alternative will give MERALCO the full control of Dolores-SM Shangri-La 115 kV corridor. Thus, MERALCO can independently conduct maintenance works on said assets; This will also provide two 115 kV feeds to Pinagbuhatan switching station. 	<ul style="list-style-type: none"> Alternative 3 would not only require construction of a longer subtransmission line than Alternative 1 but also installation of protection and control equipment at Dolores delivery point substation and Pinagbuhatan switching station. Hence, the implementation of this alternative will take longer than alternatives 1 and 2; The same is more expensive than the other alternatives; The length that SM Shangri-La-Pinagbuhatan and Pinagbuhatan-Dolores 115 kV Lines will traverse substantially increases the risk of interrupting said line. This project also requires construction of a switching station which requires acquisition of lot that involves legal process and may take some time to complete.

Table 5: Financial Evaluation of Project Alternatives

Problem Description	The project alternatives are intended to improve the reliability of the 115 kV system in Sector 2.				
Alternative	Project Name	Project Cost (P in M)	NPV (P in M)	FIRR	B/C Ratio
1	Cut-in of Pinagbuhatan Switching Station	58.64	1,632.11	222.89%	9.07
2	Construction of SM Shangri-La-Dolores 115 kV Line 2	405.34	235.91	19.89%	1.50
3	Construction of SM Shangri-La-Pinagbuhatan and Pinagbuhatan-Dolores 115 kV Lines	426.09	210.79	19.20%	1.43

	and Pinagbuhatan-Dolores 115 kV Lines				
--	--	--	--	--	--

IV. Recommendation

Based on the result of technical and financial evaluation, Alternative 1 or the 'Cut-in of Pinagbuhatan Switching Station' was implemented by MERALCO as the same addresses the above-mentioned system constraints and deficiencies without exposing the SM Sharing-la Dolores Line to risks of interrupting said line. The cutting-in of said switching station likewise will improve the reliability of the 115 kV system in Sector 2 and even the 115 kV service of PSI substation, since the project provided an alternate feed to PSWI substation. This project will also provide MERALCO full control of the SM Shangri-La-Dolores Line. If this project was not immediately initiated, the SM Shangrila-La-Dolores 115 kV line will remain at risk of outages caused by Pag-asa Steel. Consequently, the security of outlets of Dolores 230 kV-115 kV delivery point substation will be overloaded during N-1 condition which could result in cascaded trippings and widespread outages in Sector 2 of MERALCO 115 kV system.

Annex A: Expenditure Summary

Annex B: Cost-Benefit Analysis

Annex C: Project Gantt Chart

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
Cut-in of Pinagbuhatan Switching Station		Forecast (US\$, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers				
	Switchgear	21,289			
	Protective equipment	41,956			
	Metering & control equipment				
	Communications equipment				
	Other station equipment	17,488			
	Poles, Towers and Fixtures - Distribution	38,810			
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
Non-network	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		119,543	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and Improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		119,543	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
Cut-in of Pinagbuhatan Switching Station					
		Forecast (Php, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	600,000			
	Structures and Improvements (Distribution Purposes)	13,008,872			
	Station Equipment				
	Power transformers				
	Switchgear	15,677,276			
	Protective equipment	9,612,492			
	Metering & control equipment	5,632,329			
	Communications equipment				
	Other station equipment	5,998,177			
	Poles, Towers and Fixtures - Distribution	734,999			
	Overhead Conductors and Devices - Distribution	2,133,652			
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Transferred subtransmission assets				
	Sub-total Regulated Distribution Services	53,397,797	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and Improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		53,397,797	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
Cut-in of Pinagbuhatan Switching Station					
		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	600,000	0	0	0
	Structures and Improvements (Distribution Purposes)	13,008,872	0	0	0
	Station Equipment	0	0	0	0
	Power transformers	0	0	0	0
	Switchgear	16,610,121	0	0	0
	Protective equipment	11,450,904	0	0	0
	Metering & control equipment	5,632,329	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	6,764,456	0	0	0
	Poles, Towers and Fixtures - Distribution	2,435,539	0	0	0
	Overhead Conductors and Devices - Distribution	2,133,652	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
Subtrans	Transferred subtransmission assets	0	0	0	0
Sub-total Regulated Distribution Services		58,635,873	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
	Information Systems Equipment (Connection)	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
Materials	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		58,635,873	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST BENEFIT ANALYSIS FINANCIAL ANALYSIS

(COST X 1,000)
PROJECT: Cut-in of Pinagbuhatan Switching Station
YEAR : 2016

I N V E S T M E N T S				E X P E N S E S				R E V E N U E				C O R P O R A T E I N C O M E T A X		E A R N I N G S A F T E R T A X (W/ D E P R E C I A T I O N A D D E D B A C K)		F R E E C A S H F L O W		
REF	Y E A R	C A P I T A L E X P E N D I T U R E	C H A N G E I N W O R K I N G C A P I T A L	T O T A L I N V E S T M E N T S	P U R C H. P O W E R (P/KW/H)	P U R C H. P O W E R (P/KW/H)	P U R C H. P O W E R C O S T	O & M C O S T	D E P R E C I A T I O N	T O T A L E X P E N S E S	E N E R G Y S A L E S (M W/H)	S E L L I N G R A T E (P/KW/H)	T O T A L R E V E N U E	E A R N I N G S B E F O R E T A X	C O R P O R A T E I N C O M E T A X	E A R N I N G S A F T E R T A X	E A R N I N G S A F T E R T A X (W/ D E P R E C I A T I O N A D D E D B A C K)	F R E E C A S H F L O W
0	2016	58,636		58,337	6.94	7.39	1,467,587	2,917	1,945	1,472,449	190,778	8.93	1,772,984	300,535	90,160	210,374	212,319	(58,337)
1	2017		122,542	122,542	7.23	7.69	1,527,180	2,917	1,945	1,532,051	190,778	9.29	1,844,671	312,620	93,786	218,834	220,778	89,777
2	2018	4,967	4,967	8,01	7.52	7.97	1,589,212	2,917	1,945	1,594,074	190,778	9.57	1,919,255	325,182	97,655	227,628	229,572	215,811
3	2019	5,169	5,169	13,178	7.83	8.33	1,653,754	2,917	1,945	1,658,615	190,778	10.06	2,077,597	338,242	101,473	236,770	238,714	224,404
4	2020	5,378	5,378	18,556	8.14	8.67	1,720,907	2,917	1,945	1,725,778	190,778	10.47	2,161,601	351,819	105,546	246,273	248,218	233,336
5	2021	5,597	5,597	24,153	8.47	9.02	1,790,807	3,500	1,945	1,796,252	190,778	10.89	2,249,002	365,349	109,605	255,745	257,699	242,621
6	2022	5,873	5,873	30,026	8.82	9.39	1,863,536	3,500	1,945	1,868,980	190,778	11.33	2,249,002	380,022	114,007	266,015	267,960	251,816
7	2023	6,061	6,061	36,087	9.18	9.77	1,933,218	3,500	1,945	1,938,653	190,778	11.79	2,339,938	395,275	118,582	276,692	278,630	261,899
8	2024	6,307	6,307	42,394	9.55	10.16	2,017,974	3,500	1,945	2,023,419	190,778	12.27	2,434,550	411,131	123,339	287,792	289,736	272,330
9	2025	6,563	6,563	48,957	9.94	10.58	2,099,929	3,500	1,945	2,105,374	190,778	12.76	2,532,989	427,615	128,285	298,331	301,275	283,173
10	2026	6,830	6,830	55,787	10.34	11.01	2,185,212	3,500	1,945	2,191,240	190,778	13.28	2,635,403	441,131	133,250	301,275	302,219	288,046
11	2027	7,156	7,156	62,943	10.76	11.45	2,273,958	4,084	1,945	2,279,985	190,778	13.81	2,741,969	461,983	138,595	312,862	313,806	294,446
12	2028	7,396	7,396	70,339	11.20	11.92	2,366,309	4,084	1,945	2,372,337	190,778	14.37	2,852,839	480,502	144,151	326,351	327,332	305,707
13	2029	7,696	7,696	78,035	11.65	12.40	2,462,410	4,084	1,945	2,468,438	190,778	14.98	2,968,192	500,000	149,926	336,325	337,337	317,937
14	2030	8,008	8,008	86,043	12.13	12.91	2,562,414	4,084	1,945	2,568,442	190,778	15.56	3,088,210	519,768	155,930	349,837	350,800	330,600
15	2031	8,334	8,334	94,377	12.62	13.43	2,666,480	4,667	1,945	2,672,091	190,778	16.84	3,213,081	539,990	161,997	363,837	364,764	343,764
16	2032	8,721	8,721	103,108	13.13	13.98	2,774,772	4,667	1,945	2,780,439	190,778	17.52	3,343,002	561,619	168,485	371,217	372,177	351,448
17	2033	9,024	9,024	111,912	13.66	14.54	2,887,461	4,667	1,945	2,893,073	190,778	18.23	3,478,177	584,104	175,231	381,334	382,332	361,054
18	2034	9,391	9,391	121,303	14.22	15.14	3,000,728	4,667	1,945	3,006,395	190,778	18.97	3,618,818	607,479	182,244	395,078	396,078	371,217
19	2035	9,772	9,772	131,075	14.80	15.75	3,125,757	4,667	1,945	3,131,339	190,778	19.74	3,765,147	631,779	189,534	408,873	409,873	381,054
20	2036	10,169	10,169	141,244	15.40	16.39	3,253,741	5,250	1,945	3,259,991	190,778	20.53	3,917,393	658,457	196,937	425,235	426,235	391,054
21	2037	10,631	10,631	151,875	16.02	17.06	3,385,883	5,250	1,945	3,391,133	190,778	21.36	4,075,768	682,717	204,815	442,240	443,240	401,054
22	2038	11,012	11,012	162,887	16.67	17.75	3,523,392	5,250	1,945	3,529,644	190,778	22.23	4,240,604	710,017	213,005	457,902	458,902	411,054
23	2039	11,459	11,459	174,346	17.35	18.47	3,668,485	5,250	1,945	3,674,740	190,778	23.13	4,412,077	738,397	221,519	477,012	478,012	421,054
24	2040	11,924	11,924	186,270	18.05	19.22	3,815,389	5,250	1,945	3,821,609	190,778	24.06	4,590,485	767,801	229,370	496,632	497,632	431,054
25	2041	12,409	12,409	198,679	18.79	20.00	3,970,341	5,834	1,945	3,976,175	190,778	25.03	4,776,107	797,988	239,396	516,878	517,878	441,054
26	2042	12,961	12,961	211,640	19.55	20.81	4,131,586	5,834	1,945	4,137,420	190,778	26.05	4,969,236	829,872	249,962	539,475	540,475	451,054
27	2043	13,437	13,437	225,077	20.34	21.65	4,299,379	5,834	1,945	4,305,213	190,778	27.10	5,170,175	863,018	258,905	560,911	561,911	461,054
28	2044	13,983	13,983	239,060	21.17	22.54	4,473,986	5,834	1,945	4,479,970	190,778	28.20	5,379,240	897,476	269,243	580,113	581,113	471,054
29	2045	14,551	14,551	253,611	22.03	23.45	4,655,685	5,834	1,945	4,661,519	190,778	29.34	5,595,760	933,297	279,989	600,178	601,178	481,054
30	2046	15,142	15,142	268,753	22.92	24.40		5,834	1,945	4,667,463	190,778	29.34				655,252	656,252	491,054
														NPV	1,632,112			
														IRR	22.89%			
														B/C	9.07			

ANNEX B: COST-BENEFIT ANALYSIS

(COST X 1,000)

PROJECT: CONSTRUCTION OF SM SHANGRI-LA-DOLORES 115 KV LINE 2
YEAR : 2016

I N V E S T M E N T S				E X P E N S E S				R E V E N U E				(W/ DEPRECIATION ADDED BACK)						
REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (PIKW/H)	PURCH. POWER (PIKW/H)	PURCH. POWER COST	O&M COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MW/H)	SELLING RATE (PIKW/H)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX	FREE CASH FLOW
0	2017	405,338	-	405,338	7.23	7.57	-	20,267	13,511	452,479	53,172	9.17	507,188	54,708	16,413	-	-	(405,338)
1	2018	36,581	36,581	36,581	7.52	7.87	418,701	20,267	13,511	488,588	55,504	9.54	550,832	62,243	18,673	38,296	51,807	15,226
2	2019	3,009	3,009	3,009	7.83	8.19	454,810	20,267	13,511	488,588	55,504	9.92	550,832	62,243	18,673	43,570	57,062	54,072
3	2020	3,269	3,269	3,269	8.14	8.53	494,033	20,267	13,511	527,812	57,938	10.33	598,231	70,420	21,126	49,294	59,537	59,537
4	2021	3,550	3,550	3,550	8.47	8.87	536,639	20,267	13,511	570,418	60,478	10.74	649,710	79,293	23,788	55,505	69,016	69,016
5	2022	3,857	3,857	3,857	8.82	9.23	582,920	20,267	13,511	616,698	63,130	11.18	705,619	88,921	26,676	62,245	75,756	75,756
6	2023	4,527	4,527	4,527	9.18	9.61	633,191	20,267	13,511	671,023	65,858	11.63	768,338	95,316	28,595	66,721	80,232	80,232
7	2024	4,551	4,551	4,551	9.55	10.00	687,798	24,320	13,511	725,630	68,788	12.10	832,283	106,654	31,996	74,658	88,169	88,169
8	2025	4,943	4,943	4,943	9.84	10.40	747,114	24,320	13,511	784,946	71,804	12.59	903,903	118,957	35,687	83,270	96,781	96,781
9	2026	5,369	5,369	5,369	10.34	10.83	811,546	24,320	13,511	849,378	74,952	13.10	981,686	132,308	39,692	92,516	106,127	106,127
10	2027	5,832	5,832	5,832	10.76	11.27	881,535	24,320	13,511	919,366	78,239	13.63	1,066,162	146,796	44,039	102,757	116,268	116,268
11	2028	6,673	6,673	6,673	11.20	11.72	957,559	28,374	13,511	998,444	81,689	14.18	1,157,908	158,464	47,539	110,925	124,436	124,436
12	2029	6,882	6,882	6,882	11.65	12.20	1,040,140	28,374	13,511	1,082,025	85,250	14.75	1,257,550	175,524	52,657	125,867	136,378	136,378
13	2030	7,475	7,475	7,475	12.13	12.70	1,129,843	28,374	13,511	1,171,728	88,988	15.35	1,365,765	194,038	58,211	135,826	149,338	149,338
14	2031	8,120	8,120	8,120	12.62	13.21	1,227,281	28,374	13,511	1,269,166	92,890	15.97	1,483,294	214,127	64,238	149,889	163,400	163,400
15	2032	8,820	8,820	8,820	13.13	13.75	1,333,123	28,374	13,511	1,375,008	96,963	16.61	1,610,936	235,927	70,778	165,149	178,650	178,650
16	2033	9,919	9,919	9,919	13.65	14.31	1,448,053	32,427	13,511	1,494,031	101,215	17.29	1,749,562	255,531	76,659	178,871	189,840	189,840
17	2034	10,407	10,407	10,407	14.22	14.89	1,572,978	32,427	13,511	1,618,916	105,653	17.98	1,900,118	281,202	84,360	196,841	210,352	210,352
18	2035	11,305	11,305	11,305	14.80	15.49	1,708,633	32,427	13,511	1,754,572	110,286	18.71	2,063,630	309,059	92,718	218,341	229,852	229,852
19	2036	12,280	12,280	12,280	15.40	16.12	1,855,987	32,427	13,511	1,901,926	115,122	19.47	2,241,213	339,286	101,786	237,501	251,013	251,013
20	2037	13,339	13,339	13,339	16.02	16.78	2,016,049	32,427	13,511	2,061,988	120,169	20.26	2,434,079	372,091	111,627	260,464	273,975	273,975
21	2038	14,827	14,827	14,827	16.67	17.46	2,189,916	36,480	13,511	2,239,907	125,439	21.07	2,643,541	403,634	121,050	282,544	296,055	296,055
22	2039	15,738	15,738	15,738	17.35	18.17	2,378,776	36,480	13,511	2,428,767	130,939	21.93	2,871,029	442,262	132,678	303,583	323,094	323,094
23	2040	17,096	17,096	17,096	18.05	18.90	2,583,924	36,480	13,511	2,633,915	136,680	22.81	3,118,084	484,179	145,254	338,925	354,336	354,336
24	2041	18,570	18,570	18,570	18.79	19.67	2,806,764	36,480	13,511	2,868,813	142,673	23.70	3,367,838	529,685	158,989	370,765	384,277	384,277
25	2042	20,171	20,171	20,171	19.55	20.47	3,048,822	36,480	13,511	3,098,813	148,929	24.70	3,677,838	579,024	173,707	405,317	418,828	418,828
26	2043	22,249	22,249	22,249	20.34	21.30	3,317,755	40,534	13,511	3,365,800	155,459	25.69	3,994,334	628,534	188,560	439,974	453,485	453,485
27	2044	23,801	23,801	23,801	21.17	22.17	3,597,364	40,534	13,511	3,651,409	162,276	26.73	4,338,066	686,687	205,997	480,660	494,171	494,171
28	2045	25,853	25,853	25,853	22.03	23.07	3,907,604	40,534	13,511	3,961,649	169,392	27.81	4,711,379	749,730	224,919	524,811	538,323	538,323
29	2046	28,083	28,083	28,083	22.92	24.01	4,244,559	40,534	13,511	4,296,644	176,819	28.94	5,116,819	818,174	245,452	572,722	586,233	586,233
30	2047	30,505	30,505	30,505	23.86	24.96	4,610,857	40,534	13,511	4,664,702	184,572	30.11	5,557,149	892,447	297,734	624,713	638,224	638,224
														NPV	235,905			
														IRR	19.89%			
														P/C	1.50			

ANNEX B: COST-BENEFIT ANALYSIS FINANCIAL ANALYSIS

{COST X 1.000}

PROJECT: CONSTRUCTION OF SM SHANGRI-LA-PINAGBUHATAN AND PINAGBUHATAN-DOLORES 115 KV LINES
YEAR : 2016

I N V E S T M E N T S				E X P E N S E S				R E V E N U E				(W/ DEPRECIATION - ADDED BACK)						
REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (PIKWH)	PURCH. POWER (PIKWH)	PURCH. POWER COST	O&M COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MMWH)	SELLING RATE (PIKWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX	FREE CASH FLOW
0	2017	426,091	-	426,091	7.23	7.57	-	21,305	14,203	454,209	53,172	9.17	507,188	-	-	-	-	(426,091)
1	2018	36,667	36,667	36,667	7.52	7.87	418,701	21,305	14,203	481,209	53,172	9.54	507,188	52,979	15,894	37,085	51,288	
2	2019	3,009	3,009	3,009	7.83	8.19	454,810	21,305	14,203	490,318	55,504	9.92	550,832	60,514	18,154	42,360	56,563	53,554
3	2020	3,269	3,269	3,269	8.14	8.53	494,033	21,305	14,203	529,541	57,938	10.33	598,231	68,690	20,607	48,083	52,286	59,018
4	2021	3,550	3,550	3,550	8.47	8.87	536,639	21,305	14,203	572,147	60,478	10.74	649,719	77,563	23,697	64,947	68,497	71,300
5	2022	3,857	3,857	3,857	8.82	9.23	582,920	21,305	14,203	618,427	63,130	11.18	705,619	87,191	26,157	81,044	85,237	88,534
6	2023	4,544	4,544	4,544	9.18	9.61	633,191	25,565	14,203	672,960	65,898	11.63	786,338	93,379	28,014	93,365	97,568	101,862
7	2024	4,551	4,551	4,551	9.55	10.00	687,798	25,565	14,203	727,567	68,788	12.10	832,283	104,717	31,415	104,702	108,917	113,214
8	2025	4,943	4,943	4,943	9.94	10.40	747,114	25,565	14,203	786,893	71,804	12.59	903,903	117,020	35,106	117,005	121,312	125,619
9	2026	5,369	5,369	5,369	10.34	10.83	811,546	25,565	14,203	851,315	74,932	13.10	981,686	130,371	39,111	130,356	134,667	138,974
10	2027	5,832	5,832	5,832	10.76	11.27	881,535	25,565	14,203	921,303	78,239	13.63	1,066,162	144,859	43,458	144,844	149,153	153,462
11	2028	6,690	6,690	6,690	11.20	11.72	957,559	29,826	14,203	1,001,589	81,669	14.18	1,157,908	156,320	46,896	156,305	160,611	164,918
12	2029	6,882	6,882	6,882	11.65	12.20	1,040,140	29,826	14,203	1,071,311	85,250	14.75	1,257,550	173,380	52,014	173,365	177,670	181,977
13	2030	7,475	7,475	7,475	12.13	12.70	1,129,843	29,826	14,203	1,159,669	88,958	15.35	1,365,765	191,893	57,568	191,878	196,186	200,493
14	2031	8,120	8,120	8,120	12.62	13.21	1,227,281	29,826	14,203	1,246,483	92,880	15.97	1,483,294	211,983	63,995	211,968	216,273	220,580
15	2032	8,820	8,820	8,820	13.13	13.75	1,333,123	29,826	14,203	1,352,949	96,963	16.61	1,610,936	233,783	70,135	233,768	238,075	242,382
16	2033	9,935	9,935	9,935	13.66	14.31	1,448,093	34,087	14,203	1,482,180	105,653	17.98	1,800,118	253,179	75,954	253,164	257,469	261,776
17	2034	10,407	10,407	10,407	14.22	14.89	1,572,522	34,087	14,203	1,606,609	110,286	18.71	2,003,630	276,860	83,655	276,845	281,150	285,457
18	2035	11,305	11,305	11,305	14.80	15.49	1,708,533	34,087	14,203	1,742,620	115,122	19.47	2,241,213	306,707	92,012	306,692	310,904	315,209
19	2036	12,280	12,280	12,280	15.40	16.12	1,855,987	34,087	14,203	1,904,278	120,169	20.25	2,434,079	336,936	101,081	336,855	341,166	345,471
20	2037	13,339	13,339	13,339	16.02	16.78	2,016,049	34,087	14,203	2,064,340	125,439	21.07	2,643,541	369,739	110,922	369,617	373,912	378,207
21	2038	14,844	14,844	14,844	16.67	17.46	2,189,915	38,348	14,203	2,242,467	130,939	21.93	2,871,029	401,074	120,322	400,752	404,947	409,142
22	2039	15,738	15,738	15,738	17.35	18.17	2,378,776	38,348	14,203	2,431,327	130,939	21.93	3,118,094	439,702	131,911	439,591	443,882	448,073
23	2040	17,096	17,096	17,096	18.05	18.90	2,593,924	38,348	14,203	2,636,475	136,680	22.81	3,386,420	481,619	144,486	481,433	485,624	490,815
24	2041	18,570	18,570	18,570	18.79	19.67	2,806,764	38,348	14,203	2,859,315	142,673	23.74	3,386,420	527,105	158,132	526,973	531,164	535,355
25	2042	20,171	20,171	20,171	19.55	20.47	3,048,822	38,348	14,203	3,101,373	148,929	24.70	3,677,838	576,465	172,939	576,326	580,517	584,708
26	2043	22,266	22,266	22,266	20.34	21.30	3,311,755	42,609	14,203	3,368,567	155,459	25.69	3,994,334	625,767	187,730	625,617	629,808	633,999
27	2044	23,801	23,801	23,801	21.17	22.17	3,597,364	42,609	14,203	3,654,176	162,276	26.73	4,338,066	693,890	205,167	693,723	697,914	702,105
28	2045	25,853	25,853	25,853	22.03	23.07	3,907,604	42,609	14,203	3,964,416	169,392	27.81	4,711,379	746,963	224,089	746,874	751,065	755,256
29	2046	28,083	28,083	28,083	22.92	24.01	4,244,599	42,609	14,203	4,301,411	176,819	28.94	5,116,819	815,407	244,622	815,265	819,456	823,647
30	2047	30,505	30,505	30,505	23.86	24.98	4,610,657	42,609	14,203	4,667,470	184,572	30.11	5,557,149	889,680	266,904	889,511	893,702	897,893
NPV																		210,791
IRR																		19.20%
B/C																		1.43

**RY2016 CAPEX:
Capital Expenditure Projects**

ANNEX "A-5"

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 6	SPARE 83MVA 110kV-34.5kV-13.8kV POWER TRANSFORMER WITH OLTC for GIS Substation	May 2017 (Arrival Date)	46,443,027

I. Project Description:

As of May 2016, MERALCO has one hundred twenty three (123) units of 83 MVA 110kV-34.5kV-13.8kV power transformers installed in various substations. Fifty two (52) power transformers are designed for use in GIS substations and seventy one (71) power transformers are designed for use in conventional substations. Each transformer serves 46.68 MVA of demand on the average. Twenty three (23%) percent, or about twenty eight (28) units, have been in continuous service for fifteen (15) years or more.

Unfortunately, MERALCO does not have a spare 83 MVA 110kV-34.5kV-13.8kV power transformer for GIS substations. As such, any failure of any of the installed 83 MVA GIS transformers cannot be sufficiently and speedily addressed. While load-shifting will temporarily address the problem during transformer breakdowns, such solution will not address any further contingencies. Thus, transformer breakdown would result in sustained power interruption to the detriment of MERALCO's customers, commerce and vital public service.

In this regard, it is imperative that MERALCO purchase a spare 83 MVA 110kV-34.5kV-13.8kV GIS power transformer with OLTC to readily resolve cases of breakdown and failure of transformers.

II. Reason for Implementing in CY2015:

The need to have an available spare of at least one (1) unit of 83 MVA 110kV-34.5kV-13.8kV power transformer for a GIS substation at any given time is imperative in order to facilitate the quick replacement of any commissioned 83MVA power transformer that breaks down. It should be noted that the acquisition of a power transformer may usually take 15 months from the initiation of purchase until arrival of the equipment. Considering this lead time, there is an urgent need for the approval of the acquisition of a spare GIS power transformer. Additionally, the availability of a spare unit will not expose the adjacent transformers which carry the shifted loads to critical loading.

If the project was not implemented, any breakdown of a commissioned 83 MVA power transformer cannot be addressed readily thereby exhausting the critical loading of adjacent transformers which can temporarily carry the load. At this condition, any further breakdown of the adjacent transformers would result to prolonged and widespread power interruptions. The increased exposure of the affected 34.5kV distribution lines due to emergency load shifting would result in higher line losses and possibly more power interruptions.

III. Risk Analysis

Alternative 1: Provide a Spare 83 MVA 110kV-34.5kV-13.8kV GIS power transformer with OLTC
In order to readily resolve GIS power transformer breakdown / failure at any given time.

Alternative 2: Continue operation by shifting the loads to adjacent power transformers

Continue to shift the loads of adjacent transformers that breaks down to the other adjacent transformer banks, which can temporarily carry the load. The said transformers will run the risk of operating above the critical level. Also, there will be higher system loss as a result.

At this condition, an outage of any of these transformers and those in adjacent substations would result in prolonged and widespread power interruptions. Furthermore, MERALCO would have difficulty accommodating the load applications of large customers due to inadequate capacity. Likewise, there will be increased exposure of the affected 34.5kV distribution lines due to emergency load shifting thus resulting to higher line losses and possibly more frequent interruptions which would burden the consumers.

The conventional spare power transformer to be used to replace the power transformer of GIS was also considered. However, due to the design of GIS substations, it will not be feasible to use conventional spare power transformers due to the limited space inside GIS substations. In cases where there are space availability, the construction to modify the configuration of the substation may pose safety clearance problems and thus necessitate more time to construct the modifications and purchase the necessary materials. Accordingly, possible power interruptions may occur due to lack of power supply.

Comparison of Alternatives

Alternative	Advantages	Disadvantages
Alternative 1: Provide a Spare in case of GIS Power Transformer Breakdown/Failure	- minimal interruption - loading of adjacent existing transformers is within the normal loading condition - lower system loss	-no significant disadvantages
Alternative 2: Continue operation by shifting the loads to adjacent power transformers until a GIS transformer will be purchased	- no significant advantages	- widespread and frequent interruption - loading of adjacent existing transformers is above the critical loading condition - higher system loss

IV. Analysis of Options

The financial analysis includes and assumes the system losses and the maintenance costs of the project.

IV.A. Cost Estimate

ASSET CATEGORY	LABOR COST	MATERIAL COST	OTHER COST	TOTAL
Power transformers		46,443,027		46,443,027
TOTAL		46,443,027		46,443,027

The cost estimate includes the purchase of a new 83MVA 110kV-34.5kV-13.8kV GIS power transformer only. The cost includes delivery cost, taxes and duties.

IV.B. Financial Analysis

The table below shows the summary of financial evaluations of the project alternatives.

Financial Evaluation of Project Alternatives

Alternative	Project Name	Project Cost (PhP)	NPV (PhP)	FIRR	B/C Ratio
1	Provide a Spare in case of GIS Power Transformer Breakdown/Failure	46,443,027	11,891,418	19.44%	1.24
2	Continue operation by shifting the loads to adjacent power transformers until a GIS transformer will be purchased	47,371,888	1,109,819	15.33%	1.07

Conclusion

From the foregoing, it is imperative that MERALCO must have an available spare unit of an 83 MVA 110kV-34.5kV-13.8kV power transformer for a GIS substation at any given time. With the spare 83MVA GIS power transformer on hand, MERALCO will be able to quickly replace any commissioned 83MVA power transformer that breaks down at GIS substations. Furthermore, it is worthy to note that with this project, adjacent transformers will not be exposed to critical loading because of the temporary load shifting that has to be undertaken in cases when there are breakdown/failures of GIS transformers.

Annex A: Expenditure Summary

Annex B: Cost-Benefit Analysis

Annex C: Project Gantt Chart

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
SPARE 83MVA 110kV-34.5kV-13.8kV POWER TRANSFORMER WITH OLTC for GIS Substation					
		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers				
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution				
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		0	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
	Information Systems Equipment (Connection)				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		0	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY										
Capital Expenditure - Major Projects										
US\$ Expenditure (including all international expenditure)										
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)								
SPARE 83MVA 110kV-34.5kV-13.8kV POWER TRANSFORMER WITH OLTC for GIS Substation		Forecast (US\$, real) (Regulatory Year)								
Category		2016	2017	2018	2019					
Regulated Distribution Services Assets										
Network	Land and Land Rights (Distribution Purposes)	1,059,920								
	Structures and Improvements (Distribution Purposes)									
	Station Equipment									
	Power transformers									
	Switchgear									
	Protective equipment									
	Metering & control equipment									
	Communications equipment									
	Other station equipment									
	Poles, Towers and Fixtures - Distribution									
	Overhead Conductors and Devices - Distribution									
	Underground Conduits - Distribution									
	Underground Conductors and Devices - Distribution									
	Distribution Transformers									
	Power Conditioning Equipment									
	Meters, Metering Instruments & Metering Transformers - Distribution									
	Information technology equipment (distribution)									
	Regulated Entity Property on Consumer's Premises									
	Street Lights and Signal Systems									
	Submarine Cables									
Non-network	Land and Land Rights (non-network)									
	Structures and Improvements (non-network)									
	Office Furniture and Equipment									
	Transportation Equipment									
	Stores Equipment									
	Tools, Shop and Garage Equipment									
	Laboratory Equipment									
	Information Systems Equipment (non-network)									
	Power-operated Equipment									
	Communication Plant and Equipment									
	Miscellaneous Equipment									
	Materials	Materials and supplies (including spares)								
	Subtrans	Transferred subtransmission assets								
Sub-total Regulated Distribution Services		1,059,920	0	0	0					
Distribution Connection Services Assets										
Network	Poles, Towers and Fixtures (Customer)									
	Overhead Conductors and Devices (Customer)									
	Underground Conduits (Customer)									
	Underground Conductors and Devices (Customer)									
	Line Transformers (Customer)									
	Information Systems Equipment (Connection)									
Non-network	Land and Land Rights (non-network)									
	Structures and Improvements (non-network)									
	Office Furniture and Equipment									
	Transportation Equipment									
	Stores Equipment									
	Tools, Shop and Garage Equipment									
	Laboratory Equipment									
	Information Systems Equipment (non-network)									
	Power-operated Equipment									
	Communication Plant and Equipment									
	Miscellaneous Equipment									
	Materials					Materials and supplies (including spares)				
	Sub-total Distribution Connection Assets					0	0	0	0	
Regulated Retail Services Assets										
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)									
	Land and land rights									
	Structures and improvements									
	Office Furniture and Equipment									
	Transportation Equipment									
	Stores Equipment									
	Tools, Shop and Garage Equipment									
	Laboratory Equipment									
	Information Systems Equipment									
	Communication Plant and Equipment									
Miscellaneous Equipment										
Sub-total Regulated Retail Services Assets		0	0	0	0					
TOTAL CAPEX		1,059,920	0	0	0					

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
SPARE 83MVA 110kV-34.5kV-13.8kV POWER TRANSFORMER WITH OLTC for GIS Substation					
		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	0	0	0	0
	Structures and Improvements (Distribution Purposes)	0	0	0	0
	Station Equipment				
	Power transformers	46,443,027	0	0	0
	Switchgear	0	0	0	0
	Protective equipment	0	0	0	0
	Metering & control equipment	0	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	0	0	0	0
	Poles, Towers and Fixtures - Distribution	0	0	0	0
	Overhead Conductors and Devices - Distribution	0	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
Subtrans	Transferred subtransmission assets	0	0	0	0
	Sub-total Regulated Distribution Services	46,443,027	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
	Information Systems Equipment (Connection)	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
Materials	Materials and supplies (including spares)	0	0	0	0
	Sub-total Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		46,443,027	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST-BENEFIT ANALYSIS

Project Name: Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation

Year	Investment	Savings in Purch. Power Cost (Including System Loss)	Savings In O&M	Savings In Unserved Energy	Total Revenue	Net Cash Flow
0	(46,443,027.00)				2,322,151.35	(46,443,027)
1		2,863,610	2,135,214	3,613,162	8,611,986	8,611,986
2		2,978,155	2,156,566	3,757,689	8,892,410	8,892,410
3		3,097,281	2,178,132	3,907,996	9,183,409	9,183,409
4		3,221,172	2,199,913	4,064,316	9,485,401	9,485,401
5		3,289,358	2,221,912	4,150,350	9,661,620	9,661,620
6		3,289,358	2,244,131	4,150,350	9,683,839	9,683,839
7		3,289,358	2,266,573	4,150,350	9,706,280	9,706,280
8		3,289,358	2,289,238	4,150,350	9,728,946	9,728,946
9		3,289,358	2,312,131	4,150,350	9,751,838	9,751,838
10		3,289,358	2,335,252	4,150,350	9,774,959	9,774,959
11		3,289,358	2,358,604	4,150,350	9,798,312	9,798,312
12		3,289,358	2,382,190	4,150,350	9,821,898	9,821,898
13		3,289,358	2,406,012	4,150,350	9,845,720	9,845,720
14		3,289,358	2,430,073	4,150,350	9,869,780	9,869,780
15		3,289,358	2,454,373	4,150,350	9,894,081	9,894,081
16		3,289,358	2,478,917	4,150,350	9,918,625	9,918,625
17		3,289,358	2,503,706	4,150,350	9,943,414	9,943,414
18		3,289,358	2,528,743	4,150,350	9,968,451	9,968,451
19		3,289,358	2,554,031	4,150,350	9,993,738	9,993,738
20		3,289,358	2,579,571	4,150,350	10,019,279	10,019,279
21		(822,339)	(410,993)	(1,037,587)	(2,270,920)	(2,270,920)
22		(822,339)	(415,103)	(1,037,587)	(2,275,030)	(2,275,030)
23		(822,339)	(419,254)	(1,037,587)	(2,279,181)	(2,279,181)
24		(822,339)	(423,447)	(1,037,587)	(2,283,374)	(2,283,374)
25		(822,339)	(427,681)	(1,037,587)	(2,287,608)	(2,287,608)
26		(822,339)	(431,958)	(1,037,587)	(2,291,885)	(2,291,885)
27		(822,339)	(436,278)	(1,037,587)	(2,296,205)	(2,296,205)
28		(822,339)	(440,641)	(1,037,587)	(2,300,568)	(2,300,568)
29		(822,339)	(445,047)	(1,037,587)	(2,304,974)	(2,304,974)
30		(822,339)	(449,498)	(1,037,587)	(2,309,424)	(2,309,424)

WACC	14.97%
------	--------

NPV	11,891,418
FIRR	19.44%
B/C Ratio	1.24

ANNEX B: COST-BENEFIT ANALYSIS

Project Name: Continue operation by shifting the loads to adjacent power transformers until a GIS transformer will be purchased

Year	Investment	Savings in Purch. Power Cost (Including System Loss)	Savings In O&M	Savings in Unserved Energy	Total Revenue	Others (Losses)	Net Cash Flow
0							
1							
2	(47,371,887.54)	-	-	-	-	10,568,007.08	(10,568,007)
3		3,097,281	2,178,132	3,907,996	947,438		(50,101,029.07)
4		3,221,172	2,199,913	4,064,316	9,183,409		9,183,409
5		3,289,358	2,221,912	4,150,350	9,485,401		9,485,401
6		3,289,358	2,244,131	4,150,350	9,661,620		9,661,620
7		3,289,358	2,266,573	4,150,350	9,683,839		9,683,839
8		3,289,358	2,289,238	4,150,350	9,706,280		9,706,280
9		3,289,358	2,312,131	4,150,350	9,728,946		9,728,946
10		3,289,358	2,335,252	4,150,350	9,751,838		9,751,838
11		3,289,358	2,358,604	4,150,350	9,774,959		9,774,959
12		3,289,358	2,382,190	4,150,350	9,798,312		9,798,312
13		3,289,358	2,406,012	4,150,350	9,821,898		9,821,898
14		3,289,358	2,430,073	4,150,350	9,845,720		9,845,720
15		3,289,358	2,454,373	4,150,350	9,869,780		9,869,780
16		3,289,358	2,478,917	4,150,350	9,894,081		9,894,081
17		3,289,358	2,503,706	4,150,350	9,918,625		9,918,625
18		3,289,358	2,528,743	4,150,350	9,943,414		9,943,414
19		3,289,358	2,554,031	4,150,350	9,968,451		9,968,451
20		3,289,358	2,579,571	4,150,350	9,993,738		9,993,738
21		3,289,358	2,605,367	4,150,350	10,019,279		10,019,279
22		3,289,358	2,631,420	4,150,350	10,045,074		10,045,074
23		3,289,358	2,657,735	4,150,350	10,071,128		10,071,128
24		3,289,358	2,684,312	4,150,350	10,097,442		10,097,442
25		3,289,358	2,711,155	4,150,350	10,124,019		10,124,019
26		3,289,358	2,738,267	4,150,350	10,150,863		10,150,863
27		3,289,358	2,765,649	4,150,350	10,177,974		10,177,974
28		3,289,358	2,793,306	4,150,350	10,205,357		10,205,357
29		3,289,358	2,821,239	4,150,350	10,233,013		10,233,013
30		3,289,358	2,849,451	4,150,350	10,260,946		10,260,946
31		3,289,358	2,877,946	4,150,350	10,289,159		10,289,159
32		3,289,358	2,906,725	4,150,350	10,317,653		10,317,653
					10,346,433		10,346,433

WACC	14.97%
------	--------

NPV	1,109,819
FIRR	15.33%
B/C Ratio	1.07

RY2016 CAPEX:
Capital Expenditure Projects

Project Code	Project Title	Commissioning Date	Project Cost
REFILING 7	ACQUISITION OF 115 KV LINE AND 115 KV SWITCHYARD AT THE NAVOTAS FISHPORT COMPLEX	October 2016	118,478,179

I. Project Background

The project involves acquisition of four 115 kV, 2000 A power circuit breakers, eight 115 kV, 2000 A disconnect switches, two 115 kV busses, teleprotection and radio links equipment, synchronism check relay, import-export billing meter and 115 kV line with 2-795 MCM ACSR conductor per phase with a length of 428 meters.

This Project was filed as part of Meralco's RY2016 Capital Expenditure application last February 09, 2015 and included in MERALCO's 2014-2023 Distribution Development Plan (DDP).

This project is treated as an emergency/urgent CAPEX considering the dire need for MERALCO to have full operational and maintenance control at the Navotas Fishport Switching Station so as to address the system constraints and deficiencies that currently affect the reliability of MERALCO's 115 kV System in Sector 1.

As a background, the Thermal Mobile Inc. (TMO) is the owner of a 242 MW diesel fired power plant with four (4) power barges located at Navotas, Metro Manila. On March 04, 2013, TMO executed a power supply agreement with MERALCO. TMO's power plant is the source of power supply of the customers in the whole of Manila, Caloocan, Valenzuela, Malabon, Navotas, as well as some parts of Quezon City and San Jose Del Monte, Bulacan (MERALCO Sector 1).

The 115 kV switchyard at the Navotas Fishport Complex (TMO Switching Station) is currently owned by TMO. However, the switching station was only tapped to MERALCO's Grace Park- Malabon 115 kV line via 428 meters 115 kV line also constructed and owned by TMO.

In 2013, upon consultation of TMO and MERALCO with ERC, TMO was allowed to build a point-to-point facility so that it will be able to meet the target commissioning schedule for the plant. In 2014, considering the need to improve reliability of the Grace Park- Malabon 115 kV line, MERALCO took the initiative to have a cut-in connection of the switching station to the said 115 kV line. This will improve the reliability of the said line since when TMO's plant, an embedded generation (EG), is connected via cut-in, and there has been a fault on either line leg, the said plant will not be isolated from the MERALCO system. Thus, it cannot have an impact to the distribution system. Restoration works of the faulted leg may be conducted independently and without affecting the normal operations of the 115 kV system. Unlike where the EG is tapped only to a line, the fault shall be cleared first before the operation at 115 kV system can be resumed by MERALCO.

As above-mentioned, the TMO's plant supplies a portion of MERALCO's peak power requirements for the benefit of its customers in the said areas. EGs, like TMO's plant, play an important role especially when NGCP power plants are on emergency shutdown, experiencing an outage or running on limited capacity. Like any other EGs, TMO's plant could also contribute to system loss reduction and should therefore maintain being connected to the grid at all times. Specifically for this case, the connection of TMO (EG) results in 6,491,467 kWH loss reduction annually. Hence, MERALCO deems it relevant to assure that the connection of said plant to the 115 kV system is well-maintained and secured.

However, MERALCO still has no full control of the said switching station which is the connection point to MERALCO. Maintenance works or repairs require a series of coordination before it can be executed. Full control which is crucial to the operation especially during emergency can be achieved if MERALCO owns the said switching station. At present, MERALCO cannot ensure proper maintenance of the TMO switching station and equipment thereat. This exposes the 115 kV system to risks that may be caused by fault or trouble in the switching station.

In particular, the reliability of the MERALCO 115 kV system in Sector 1 will be compromised. A fault or trouble in TMO's switching station may cause the disconnection of the TMO plant and result to overloading of the remaining power transformer banks at Balintawak 230kV Delivery Point substation during N-1. It should also

be considered that when there is an outage of the Grace Park-TMO-Malabon 115 kV due to fault / any problems caused by the TMO's switching station, there will be no available 2nd 115 kV feed to Malabon and Grace Park Substations. Consequently, there will be power interruptions to customers being served by these substations.

For these reasons, the CAPEX project for acquisition of the 115 kV line and 115 kV switchyard in the Navotas Fishport Complex should be immediately approved. This will ensure that the switching station is properly maintained and consequently ensure that TMO's power plant is always connected and can deliver the peaking power that is required by MERALCO.

II. Technical Analysis:

In planning the expansion of its distribution system, MERALCO adheres to the following policies and criteria:

2.1 Subtransmission Planning Policies

- a. Subtransmission lines and delivery point substation power transformers shall comply with the N-1 provision
- b. Adequate subtransmission feeds shall be provided to all substations to ensure reliability of power supply;
- c. Subtransmission development plans should be aligned with relevant NGCP, NPC, IPP and Government Projects
- d. Delivery Point substation and subtransmission line projects should be financially viable.

2.2 Subtransmission Planning Criteria

- a. Subtransmission lines shall not be loaded beyond 90% of its rated capacity during N-1 contingency.
- b. Delivery point power transformers shall not be loaded beyond 100% of its FA2 rating during N-1 contingency.
- c. Bus voltage regulation shall be within $\pm 5\%$ of nominal voltage during normal condition and within $\pm 10\%$ during N-1 condition.
- d. Bus fault duty should not exceed 90% of the equipment interrupting rating.
- e. There should be no loss of load during N-1 contingency.

Thus, MERALCO exerts its best effort to address all possible concerns/problems with its sub-transmission lines. This includes ensuring that all connections are properly maintained and secured. It is for these reasons that MERALCO deems it proper to acquire the TMO's switching station. MERALCO's ownership of the switching station will also lessen the probability of power interruptions caused by/due to improper maintenance of the switching station. If MERALCO will acquire the same, it would have a free hand to operate, maintain, repair and rehabilitate these assets.

TMO's connection to the 115 kV line needs to be secured considering that the Balintawak 230kV Delivery Point substation will be overloaded during N-1 contingencies without the EG (TMO). This delivery point substation, together with Duhat and Paco 230kV Delivery Point substations, supplies power to several 115 kV-34.5 kV substations in Sector 1 of MERALCO 115 kV system serving the customers in the north-western portion of Metro Manila and southern portion of Bulacan.

If MERALCO owns the said asset, problems arising from any of the equipment can be immediately addressed. This will avoid the occurrence of similar incidences in the past where MERALCO cannot provide the needed works for maintenance of equipment in said switching station because of lack of right to access and control thereto. Particularly, in February 2016, deteriorating battery condition had been discovered by MERALCO during maintenance inspection at TMO switching station. MERALCO could not replace the batteries due to the limitations provided in the Interconnection Agreement signed on March 4, 2013 by MERALCO and TMO. Per Section 3.2.1 of said Agreement, particularly, in the Fixed Asset Boundary Document (FABD), TMO's DC System is part of TMO's assets and MERALCO is only responsible to operate, maintain and control the interconnection facilities and switching station. Thus, replacement of the battery units is TMO's responsibility.

Also, MERALCO noticed that TMO was using two battery banks operating in parallel (10 cells for each bank with each cells having 12V) for the switching station. This can cause a large voltage drop when a single battery cell breaks down. Thus, MERALCO recommended to TMO to relocate the battery charger outside the battery room to avoid damage to its electronic components since substation batteries emit chemical fumes. TMO initially refused to heed to MERALCO's recommendation. However, after an exchange of series of correspondence between TMO and MERALCO and meetings, TMO finally replaced the battery bank 1 on May 5, 2016. But bank 2 will only be replaced upon the arrival of TMO's new charger.

The unreliable condition of TMO's DC system puts TMO's protection and control system at risk and may cause disruption of service to MERALCO's 115 kV Sub-transmission line. Said problems and other similar issues that may arise in the future regarding the conduct of maintenance will all be averted through the acquisition of the pertained Navotas Fishport Complex switching station, including the said DC system, by MERALCO. Moreover, additional improvement or expansion can be executed without delays due to the required approval or tedious coordination with TMO.

Without the project, the planning criteria *"Delivery point power transformers shall not be loaded beyond 100% of its FA2 rating during N-1 contingency"* will be breached.

Table 1: Actual and Forecasted Loading without EG due to switching station trouble

PARAMETERS UNDER CONSIDERATION			PERCENT LOADING OF AFFECTED BANKS/LINE DURING N-1 CONTINGENCY				
OUTAGE OF BANK/LINE DURING N-1 CONTINGENCY	AFFECTED SUBTRANSMISSION FACILITY DURING N-1 CONTINGENCY		RY2016	RY2017	RY2018	RY2019	RY2020
	BANK/LINE	CAPACITY (MVA)					
Balintawak 300 MVA Bank	Remaining Balintawak 3X300 MVA Banks	900	112%	117%	122%	126%	131%

Table2: Actual and Forecasted Loading with EG

PARAMETERS UNDER CONSIDERATION			PERCENT LOADING OF AFFECTED BANKS/LINE DURING N-1 CONTINGENCY				
OUTAGE OF BANK/LINE DURING N-1 CONTINGENCY	AFFECTED SUBTRANSMISSION FACILITY DURING N-1 CONTINGENCY		RY2016	RY2017	RY2018	RY2019	RY2020
	BANK/LINE	CAPACITY (MVA)					
Balintawak 300 MVA Bank	Remaining Balintawak 3X300 MVA Banks	900	95%	79%	82%	85%	88%

Note: Loadings are with the complimentary effect of other CAPEX projects.

III. Project Alternatives

In the process of determining the most cost-effective solution to address the identified system deficiencies, MERALCO generated technically feasible alternatives that could satisfy the distribution system requirements in a timely and efficient manner. Table 3 shows the summary of technically feasible projects that are evaluated.

Table 3: Project Alternatives

Problem Description	Lack of full operational and maintenance control at the Navotas Fishport Switching Station which affects the reliability of MERALCO's 115 kV System in Sector 1	
Alternative	Project Name	Classification
1	Acquisition of 115 kV Line and 115 kV Switchyard at Navotas Fishport Complex	Stand-alone
2	Construction of Grace-Park Malabon 115 kV Line	Stand-alone


Note: Applicant considered as an option maintaining the current set-up. However, the same will not address the above-mentioned operational and maintenance of the Navotas Switching Station affecting the N-1 contingency problem.


Alternative 1: Acquisition of 115 kV Line and 115 kV Switchyard at Navotas Fishport Complex

The proposed project for acquisition of TMO switching station comprises of four (4) 115 kV, 2000 A power circuit breakers, eight (8) 115 kV, 2000 A disconnect switches, two (2) 115 kV busses, teleprotection and radio links equipment, synchronism check relay, import-export billing meter and 115 kV line using 2-795 MCM ACSR conductor per phase with a total length of 428 meters.

It is a must that the ownership of the switching station be transferred to MERALCO so that it would have a free hand to operate, maintain, repair and rehabilitate the TMO switching station. This is to be able to prevent if not deter the above-discussed system problems/ constraints.

Project Cost (PhP): 118.48 M





Alternative 2: Construction of Grace-Park Malabon 115 kV Line

This project involves the installation of one (1) 115 kV power circuit breaker at Malabon substation, one (1) bay extension of the existing 115 kV GIS equipment at Grace Park substation, protection and control equipment and the construction of overhead (OH) 115 kV line using 2-795 MCM ACSR per phase on steel poles with an approximate length of 5 km.

There is a need to secure the reliability of 115 kV system in case MERALCO will not be allowed to acquire ownership of the switching station. As an alternative, the Grace Park Malabon 115 kV line may be constructed so that if there is trouble/fault in the Navotas Fishport Switching Station and the same causes outage to Malabon-TMO-Grace Park 115 kV line there will be an N-1 provision for the Malabon and Grace Park substations. However, this will not resolve all possible system constraints such as overloading of power transformers of Balintawak Delivery Point Substation during N-1 in case of fault/roubles in Navotas Fishport Switching Station.

Project Cost (PhP): 133.44 M




Table 4: Comparison of Project Alternatives:

Alternative	Advantages	Disadvantages
Alternative 1 Acquisition of 115 kV Line and 115 kV Switchyard at Navotas Fishport Complex	MERALCO can ensure proper maintenance of the TMO switching station and equipment thereat. Thus, risks and faults of said switching	There is no significant disadvantage

	<p>station will be minimized if not totally prevented;</p> <p>Higher probability of uninterrupted EG connection thru properly maintained switching station results to the following:</p> <ul style="list-style-type: none">•Improvement of reliability of the Malabon-TMO-Grace Park 115 kV line so as to avoid any N-1 problem with Malabon and Grace Park substations; and•System loss reduction <p>The implementation of this alternative will also address the N-1 deficiency at Balintawak DP substation and strengthen the 115 kV subtransmission system.</p> <p>There is no need to acquire property (lot) and secure ROW for 115 kV line works.</p> <p>This will save time of both MERALCO and TMO from coordinating with each other in relation to TMO for the enhancement, repair or replacement of the equipment within the switching so.</p> <p>Provides MERALCO full maintenance and operational control to facilitate restoration in a shorter time.</p>	
Alternative 2 Construction of Grace-Park Malabon 115 kV Line	<p>It will provide N-1 contingency of the Malabon and Grace Park substations during outage Malabon-TMO-Grace Park 115 kV line caused by the trouble in the Navotas Fishport Switching Station.</p>	<p>MERALCO will not be able to conduct proper maintenance of the TMO switching station and equipment thereat. Thus, possible risks and faults of said switching station may not be immediately addressed and the same may pose threats/impacts to the 115 kV line;</p> <p>There will still be risks to Grace Park-TMO-Malabon 115 kV corridor because the TMO Switching Station forms part of the MERALCO Subtransmission system. Although the Malabon and Grace Park Substations would have a 2nd 115 kV feed, there would still be overloading of Balintawak Delivery Point Substation remaining 3-300 MVA power transformers during N-1 in case of fault/roubles in Navotas Fishport Switching Station.</p> <p>Right-of-Way will be hard to secure in this urban area.</p>

		<p>Takes longer time to complete than Alternative 1 and will not be completed having the same target.</p> <p>This alternative is more expensive than alternative 1.</p>
--	--	---

Table 5: Financial Evaluation of Project Alternatives:

Alternative	Project Name	Project Cost (P in M)	NPV (P in M)	FIRR	B/C Ratio
1	Acquisition of 115 kV Line and 115 kV Switchyard at Navotas Fishport Complex	118.48	55.05	18.96%	1.40
2	Construction of Grace-Park Malabon 115 kV Line	133.44	36.95	17.41%	1.24

IV. Recommendation

Based on the result of technical and financial evaluation, Alternative 1 or 'Acquisition of 115 kV Line and 115 kV Switchyard at Navotas Fishport Complex' will address all of the above-mentioned system constraints and deficiencies. Alternative 1 is better than Alternative 2 since the former can prevent the overloading of the remaining three (3) 300 MVA banks of Balintawak 230kV Delivery Point substation during N-1 when the EG disconnected due to trouble in the said switching station. Further, MERALCO's acquisition of said assets will also result to the following: (a) improved reliability of the Malabon-TMO-Grace Park 115 kV line and this will therefore avoid any N-1 problem with Malabon and Grace Park substations; and (b) system loss reduction. With this project, MERALCO will be able to maintain the switching station and other associated equipment as well as immediately address any concerns/problems in relation thereto.

- Annex A: Expenditure Summary**
- Annex B: Cost-Benefit Analysis**
- Annex C: Project Gantt Chart**

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fishport Complex					
Category		Forecast (US\$, real) (Regulatory Year)			
		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers				
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution				
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		0	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
	Information Systems Equipment (Connection)				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		0	0	0	0

Notes : References to Regulatory Years are for the 12 month period ending on 12/31/2016

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY						
Capital Expenditure - Major Projects						
Local Expenditure						
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)				
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fishport Complex						
Category		Forecast (Php, real) (Regulatory Year)				
		2016	2017	2018	2019	
Regulated Distribution Services Assets						
Network	Land and Land Rights (Distribution Purposes)	300,000				
	Structures and Improvements (Distribution Purposes)	13,635,182				
	Station Equipment					
	Power transformers					
	Switchgear	25,749,280				
	Protective equipment	13,332,115				
	Metering & control equipment	5,658,860				
	Communications equipment					
	Other station equipment	14,486,232				
	Poles, Towers and Fixtures - Distribution	43,186,739				
	Overhead Conductors and Devices - Distribution	2,129,772				
	Underground Conduits - Distribution					
	Underground Conductors and Devices - Distribution					
	Distribution Transformers					
	Power Conditioning Equipment					
	Meters, Metering Instruments & Metering Transformers - Distribution					
	Information technology equipment (distribution)					
	Regulated Entity Property on Consumer's Premises					
	Street Lights and Signal Systems					
	Submarine Cables					
Non-network	Land and Land Rights (non-network)					
	Structures and Improvements (non-network)					
	Office Furniture and Equipment					
	Transportation Equipment					
	Stores Equipment					
	Tools, Shop and Garage Equipment					
	Laboratory Equipment					
	Information Systems Equipment (non-network)					
	Power-operated Equipment					
	Communication Plant and Equipment					
	Miscellaneous Equipment					
	Materials	Materials and supplies (including spares)				
	Subtrans	Transferred subtransmission assets				
	Sub-total Regulated Distribution Services		118,478,179	0	0	0
	Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)					
	Overhead Conductors and Devices (Customer)					
	Underground Conduits (Customer)					
	Underground Conductors and Devices (Customer)					
	Line Transformers (Customer)					
Non-network	Information Systems Equipment (Connection)					
	Land and Land Rights (non-network)					
	Structures and Improvements (non-network)					
	Office Furniture and Equipment					
	Transportation Equipment					
	Stores Equipment					
	Tools, Shop and Garage Equipment					
	Laboratory Equipment					
	Information Systems Equipment (non-network)					
	Power-operated Equipment					
	Communication Plant and Equipment					
	Miscellaneous Equipment					
	Materials	Materials and supplies (including spares)				
	Sub-total Distribution Connection Assets		0	0	0	0
	Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)					
	Land and land rights					
	Structures and improvements					
	Office Furniture and Equipment					
	Transportation Equipment					
	Stores Equipment					
	Tools, Shop and Garage Equipment					
	Laboratory Equipment					
	Information Systems Equipment					
	Communication Plant and Equipment					
	Miscellaneous Equipment					
	Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		118,478,179	0	0	0	

Notes : References to Regulatory Years are for the 12 month period ending on 12/31/2016

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX A: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fishport Complex		Forecast (PhP, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	300,000	0	0	0
	Structures and Improvements (Distribution Purposes)	13,635,182	0	0	0
	Station Equipment				
	Power transformers	0	0	0	0
	Switchgear	25,749,280	0	0	0
	Protective equipment	13,332,115	0	0	0
	Metering & control equipment	5,658,860	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	14,486,232	0	0	0
	Poles, Towers and Fixtures - Distribution	43,186,739	0	0	0
	Overhead Conductors and Devices - Distribution	2,129,772	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Subtrans	0	0	0	0
	Sub-total Regulated Distribution Services	118,478,179	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
Non-network	Information Systems Equipment (Connection)	0	0	0	0
	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Sub-total Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		118,478,179	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX B: COST BENEFIT ANALYSIS CALCULATION

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: ACQUISITION OF 115 KV LINE AND 115 KV SWITCHYARD YARD AT THE NAVOTAS FISHPORT COMPLEX (ALTERNATIVE 1)
YEAR : 2016

I N V E S T M E N T S				E X P E N S E S				R E V E N U E				(W/ DEPRECIATION ADDED BACK)						
REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (PIKWH)	PURCH. POWER (PIKWH)	PURCH. POWER COST	O&M COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MWH)	SELLING RATE (PIKWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX	FREE CASH FLOW
0	2016	118,478	-	118,478	6.94	7.27	-	5,924	3,949	124,109	15,098	8.81	-	-	-	-	-	(118,478)
1	2017		10,013	10,013	7.23	7.57	114,235	5,924	3,949	133,960	15,760	9.17	138,404	14,295	4,288	10,006	13,956	3,942
2	2018		821	821	7.52	7.87	124,087	5,924	3,949	133,960	15,760	9.54	150,313	16,353	4,906	11,447	15,396	14,575
3	2019		892	892	7.83	8.19	134,789	5,924	3,949	144,662	16,451	9.92	163,248	18,586	5,576	13,010	16,960	15,068
4	2020		969	969	8.14	8.53	146,413	5,924	3,949	156,286	17,172	10.32	177,256	21,010	6,303	14,707	18,566	17,687
5	2021		1,052	1,052	8.47	8.87	159,040	5,924	3,949	168,913	17,925	10.74	192,552	23,639	7,092	16,548	20,497	19,445
6	2022		1,242	1,242	8.82	9.23	172,755	7,109	3,949	183,813	18,711	11.18	209,122	25,308	7,992	17,716	21,865	20,423
7	2023		1,349	1,349	9.18	9.61	187,654	7,109	3,949	198,712	19,531	11.63	227,117	28,405	8,521	19,883	23,833	22,591
8	2024		1,465	1,465	9.55	10.00	203,837	7,109	3,949	214,895	20,388	12.10	246,661	31,765	9,930	22,236	26,185	24,836
9	2025		1,591	1,591	9.94	10.40	221,417	7,109	3,949	232,475	21,282	12.59	267,866	35,412	10,824	24,788	28,738	27,273
10	2026		1,827	1,827	10.34	10.83	240,512	7,109	3,949	251,570	22,215	13.10	290,939	39,369	11,811	27,558	31,508	29,916
11	2027		1,878	1,878	10.76	11.27	261,254	8,293	3,949	273,496	23,189	13.63	315,975	42,478	12,743	29,735	33,684	31,857
12	2028		2,039	2,039	11.20	11.72	283,785	8,293	3,949	296,027	24,206	14.18	343,165	47,138	14,141	32,996	36,946	35,068
13	2029		2,215	2,215	11.65	12.20	308,258	8,293	3,949	320,501	25,267	14.75	372,695	52,194	15,658	36,536	40,485	38,446
14	2030		2,406	2,406	12.13	12.70	334,843	8,293	3,949	347,066	26,375	15.35	404,767	57,681	17,304	40,377	44,326	42,111
15	2031		2,713	2,713	12.62	13.21	363,720	8,293	3,949	375,963	27,531	15.97	439,598	63,635	19,091	44,545	48,484	46,088
16	2032		2,839	2,839	13.13	13.75	395,088	9,478	3,949	408,515	28,739	16.61	477,427	68,912	20,674	48,238	52,188	49,475
17	2033		3,084	3,084	13.66	14.31	429,160	9,478	3,949	442,988	29,999	17.28	518,511	75,923	22,777	53,146	57,095	54,256
18	2034		3,350	3,350	14.22	14.89	466,171	9,478	3,949	479,599	31,314	17.98	593,131	83,832	25,080	58,472	62,422	59,337
19	2035		3,639	3,639	15.40	15.49	506,375	9,478	3,949	519,802	32,687	18.71	611,590	91,789	27,537	64,252	68,201	64,851
20	2036		4,052	4,052	16.02	16.78	550,045	9,478	3,949	563,472	34,120	19.47	664,220	100,749	30,224	70,523	74,473	70,834
21	2037		4,294	4,294	16.67	17.46	597,481	10,663	3,949	612,093	35,616	20.25	721,379	109,285	32,786	76,500	80,449	76,397
22	2038		4,664	4,664	17.35	17.87	649,008	10,663	3,949	663,621	37,178	21.07	783,456	119,836	35,951	83,885	87,834	83,540
23	2039		5,067	5,067	18.05	18.90	704,980	10,663	3,949	719,592	38,808	21.93	850,876	131,284	39,385	91,899	95,848	91,184
24	2040		5,503	5,503	18.79	19.67	765,778	10,663	3,949	780,390	40,510	22.81	924,098	143,708	43,112	100,599	104,545	99,478
25	2041		6,077	6,077	19.55	20.47	831,819	10,663	3,949	846,431	42,286	23.73	1,003,621	157,199	47,157	110,033	113,962	108,478
26	2042		6,494	6,494	20.34	21.30	903,556	11,848	3,949	919,353	44,140	24.69	1,089,987	170,634	51,190	119,444	123,393	117,316
27	2043		7,054	7,054	21.17	22.17	981,479	11,848	3,949	997,276	46,076	25.69	1,183,786	186,509	55,953	130,555	134,506	128,012
28	2044		7,662	7,662	22.03	23.07	1,066,123	11,848	3,949	1,081,920	48,096	26.73	1,285,656	203,736	61,121	142,615	146,595	139,511
29	2045		8,323	8,323	22.92	24.00	1,158,939	11,848	3,949	1,173,864	50,203	27.81	1,396,294	222,430	66,729	155,701	159,650	151,988
30	2046						1,257,939	11,848	3,949	1,273,736	52,407	28.94	1,516,452	242,716	72,815	169,901	173,851	165,529

NPV

IRR

B/C

55,049

18.96%

1.40

ANNEX B: COST BENEFIT ANALYSIS CALCULATION

FINANCIAL ANALYSIS
(COST X 1,000)
PROJECT: CONSTRUCTION OF GRACE PARK-MALABON 115 KV LINE (ALTERNATIVE 2)
YEAR: 2016

I N V E S T M E N T S				E X P E N S E S				R E V E N U E				(W/ DEPRECIATION ADDED BACK)						
REF	YEAR	CAPITAL EXPENDITURE	CHANGE IN WORKING CAPITAL	TOTAL INVESTMENTS	PURCH. POWER (PKWH)	PURCH. POWER (PKWH)	PURCH. POWER COST	O&M COST	DEPRECIATION	TOTAL EXPENSES	ENERGY SALES (MWH)	SELLING RATE (PKWH)	TOTAL REVENUE	EARNINGS BEFORE TAX	CORPORATE INCOME TAX	EARNINGS AFTER TAX	EARNINGS AFTER TAX	FREE CASH FLOW
0	2016	133,437	-	133,437	6.94	7.27	-	6,672	4,448	125,355	15,098	8.81	-	-	-	-	-	(133,437)
1	2017	10,076	10,076	10,076	7.23	7.57	114,235	6,672	4,448	135,207	15,098	9.17	138,404	13,048	3,915	9,134	13,582	3,506
2	2018	821	821	821	7.52	7.87	124,087	6,672	4,448	135,207	15,760	9.54	150,313	15,106	4,532	10,574	15,022	14,201
3	2019	892	892	892	7.83	8.19	134,789	6,672	4,448	145,908	16,451	9.92	163,248	17,340	5,202	12,138	16,586	15,694
4	2020	969	969	969	8.14	8.53	146,413	6,672	4,448	157,533	17,172	10.32	177,296	19,763	5,929	13,834	18,282	17,313
5	2021	1,052	1,052	1,052	8.47	8.87	159,040	6,672	4,448	170,159	17,925	10.74	192,552	22,393	6,718	15,675	20,123	19,071
6	2022	1,254	1,254	1,254	8.82	9.23	172,755	8,006	4,448	185,210	18,711	11.18	209,122	23,912	7,174	16,738	21,186	19,932
7	2023	1,242	1,242	1,242	9.18	9.61	187,654	8,006	4,448	200,108	19,531	11.63	227,117	27,009	8,103	18,906	23,354	22,113
8	2024	1,349	1,349	1,349	9.55	10.00	203,837	8,006	4,448	216,292	20,388	12.10	246,661	30,369	9,111	21,258	25,706	24,358
9	2025	1,465	1,465	1,465	9.94	10.40	221,417	8,006	4,448	233,871	21,282	12.59	267,886	34,016	10,205	23,811	28,259	26,794
10	2026	1,591	1,591	1,591	10.34	10.83	240,512	8,006	4,448	252,966	22,215	13.10	290,939	37,973	11,392	26,581	31,029	29,438
11	2027	1,840	1,840	1,840	10.76	11.27	261,254	9,341	4,448	275,042	23,169	13.63	315,975	40,932	12,280	28,653	33,101	31,261
12	2028	1,878	1,878	1,878	11.20	11.72	283,785	9,341	4,448	297,573	24,205	14.18	343,165	45,592	13,678	31,914	36,362	34,485
13	2029	2,039	2,039	2,039	11.65	12.20	308,258	9,341	4,448	322,047	25,267	14.75	372,695	50,648	15,195	35,454	39,902	37,882
14	2030	2,215	2,215	2,215	12.13	12.70	334,843	9,341	4,448	348,631	26,375	15.35	404,767	56,136	16,841	39,295	43,743	41,527
15	2031	2,406	2,406	2,406	12.62	13.21	363,720	9,341	4,448	377,508	27,531	15.97	439,598	62,090	18,627	43,463	47,911	45,504
16	2032	2,725	2,725	2,725	13.13	13.75	395,088	10,675	4,448	410,210	28,739	16.61	478,427	67,217	20,165	47,052	51,500	48,774
17	2033	2,839	2,839	2,839	13.66	14.31	429,160	10,675	4,448	444,283	29,999	17.28	518,511	74,228	22,268	51,550	56,408	53,568
18	2034	3,084	3,084	3,084	14.22	14.89	466,171	10,675	4,448	481,294	31,314	17.98	563,131	81,837	24,551	57,286	61,734	58,649
19	2035	3,350	3,350	3,350	14.80	15.49	506,375	10,675	4,448	521,497	32,687	18.71	611,590	90,093	27,028	63,095	67,513	64,163
20	2036	3,639	3,639	3,639	15.40	16.12	550,045	12,009	4,448	565,158	34,120	19.47	684,220	99,053	29,716	75,208	79,856	75,145
21	2037	4,064	4,064	4,064	16.02	16.78	597,481	12,009	4,448	613,938	35,616	20.25	721,379	107,441	32,232	82,594	87,041	82,748
22	2038	4,294	4,294	4,294	16.67	17.46	649,008	12,009	4,448	665,466	37,178	21.07	783,456	117,991	35,397	90,808	95,056	90,391
23	2039	4,664	4,664	4,664	17.35	18.17	704,980	12,009	4,448	721,437	38,808	21.93	850,876	129,439	38,832	99,304	103,752	98,686
24	2040	5,067	5,067	5,067	18.05	18.90	765,778	12,009	4,448	782,235	40,510	22.81	924,098	141,863	42,559	108,741	113,189	107,686
25	2041	5,503	5,503	5,503	18.79	19.67	831,819	12,009	4,448	848,276	42,286	23.73	1,003,621	155,344	46,603	118,048	122,456	116,406
26	2042	6,089	6,089	6,089	19.55	20.47	903,556	13,344	4,448	921,347	44,140	24.69	1,089,987	168,640	50,592	129,160	133,608	127,115
27	2043	6,494	6,494	6,494	20.34	21.30	981,479	13,344	4,448	999,271	46,076	25.69	1,183,786	184,515	53,354	141,219	145,667	138,614
28	2044	7,054	7,054	7,054	21.17	22.17	1,086,123	13,344	4,448	1,083,915	48,056	26.73	1,285,656	201,742	60,523	154,753	158,753	151,091
29	2045	7,662	7,662	7,662	22.03	23.07	1,158,067	13,344	4,448	1,175,856	50,205	27.81	1,386,294	220,436	66,131	168,505	172,953	164,530
30	2046	8,323	8,323	8,323	22.92	24.00	1,257,939	13,344	4,448	1,275,731	52,407	28.94	1,516,452	240,722	72,215	188,505	193,947	185,947

NPV

IRR

B/C

1.24

Republic of the Philippines
ENERGY REGULATORY COMMISSION
San Miguel Avenue, Pasig City

**IN THE MATTER OF THE
APPLICATION FOR APPROVAL OF
EMERGENCY AND/OR URGENT
MAJOR CAPITAL EXPENDITURE
(CAPEX) PROJECTS,**

ERC CASE NO. _____

**MANILA ELECTRIC COMPANY
(MERALCO),**

Applicant.

X-----X

**JUDICIAL AFFIDAVIT
OF ENGR. FROILAN J. SAVET**

I, **FROILAN J. SAVET**, Filipino, of legal age, married and with office address at 5th floor, Technical Services Building, Meralco Center, Ortigas Avenue, Pasig City, Philippines after being sworn to in accordance with law, fully conscious that I am answering the questions under oath, hereby depose and state THAT:

Q1: What are your professional and educational qualifications?

A1: I am a Professional Electrical Engineer, with PRC No. 0003687. I passed the March 2015 Technical Evaluation for the Upgrading as Professional Electrical Engineer. I also passed the April 1992 Board Examination for Assistant Electrical Engineer and was the 2nd placer of the said exam.

My educational background are as follows:

- **Master of Science in Electrical Engineering (Major in Power), U.P. Diliman, October 2003**
- **Bachelor of Science in Electrical Engineering, Mapua Institute of Technology (MIT), May 1990, Silver Medalist**

Q2: Where are you presently employed?

A2: I am presently employed at MERALCO as Senior Assistant Vice President and Head of Network Planning and Project Management (NPPM) Office.

Q3: How long have you been employed by MERALCO?

A3: I have been employed by MERALCO for twenty five (25) years. I started out as a System Planning Engineer and have gained experience in electric system planning, project management, substation standards, substation design and construction, and distribution connection.

Q4: What are your duties and responsibilities as Senior Assistant Vice President and Head of MERALCO's NPPM?

A4: The following are, among other things, my principal duties and responsibilities:

- Conceptualization of plans for the timely expansion of Meralco's sub-transmission lines, substation, and distribution lines;
- Preparation of planning standards or criteria for the said asset groups;
- Management of the completion of MERALCO sub-transmission lines, substation and distribution lines;
- Management of the network asset planning processes;
- Preparation, review and approval of documents necessary to implement major electrical capital expenditure projects; and
- Compliance to the reportorial requirements of regulatory bodies in relation to electric system expansion.

Q5: Are you familiar with the Application of MERALCO entitled: ***"IN THE MATTER OF THE APPLICATION FOR APPROVAL OF EMERGENCY AND/OR URGENT MAJOR CAPITAL EXPENDITURE (CAPEX) PROJECTS"***?

A5: Yes. I am familiar with said Application as I have participated in the preparation of the said Application as well as its supporting documents.

Q6: What is the Application all about?

A6: In brief, the Application seeks the Energy Regulatory Commission's (ERC) approval of emergency and/or urgent major Capital Expenditure (CAPEX) projects.

Q7: Why is MERALCO filing the instant Application?

A7: The last year of MERALCO's Third Regulatory Period expired on 30 June 2015. The Fourth Regulatory Period (4RP) for the First Entry Group commenced on 1 July 2015 and shall end on 30 June 2019. However, the Honorable Commission has not yet issued the relevant rules to govern the reset process and the filing by the DUs of their reset application. Pending the reset process, MERALCO needs to secure

approval of its forecast CAPEX for the period after 1 July 2015. MERALCO then filed an Application for Approval of its proposed Capital Expenditure (CAPEX) projects for Regulatory Year (RY) 2016 (ERC Case 2015-016 RC).

On 15 June 2016, MERALCO received a copy of the Decision dated 12 April 2016 which partially approved MERALCO's CAPEX program for RY 2016. However, the Honorable Commission also deferred the following projects, without prejudice to refilling:

Project Code	Project Title
MER-2	Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)
MER-4	Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer
MER-11	Rebuilding of Portion of Dasmariñas-FCIE 115kV Line
MER-13	Cut-in of Pinagbuhatan Switching Station
MER-14	Replacement of Power Transformer No.2 at Mandaluyong Substation
MER-15	Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation
MER-20	Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex

Hence, MERALCO is filing the instant Application. Further, this application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled: *"Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects"*. Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system to meet the growing and future needs of its more than 5.78 million customers.

- Q8: During the pendency of the RY2016 Application, did MERALCO inform the Honorable Commission of the urgency of these projects?
- A8: Yes. In fact, MERALCO filed several manifestations and motions with the Honorable Commission, namely:
- a. On 10 April 2015, MERALCO filed an Urgent Motion for Issuance of a Provisional Authority ("Urgent Motion") dated 8 April 2015

requesting that it be allowed to immediately implement its priority projects, the list of which was attached to said Urgent Motion.

- b. On 15 April 2015, MERALCO filed a Motion of even date attaching a detailed list showing a further breakdown of the projects into business segments especially those that are shared by different business segments.
- c. On 11 June 2015, MERALCO filed a Very Urgent Motion for Authority to Commence Implementation of RY 2016 Priority Projects with an attached list of the RY 2016 priority projects ("Very Urgent Motion").
- d. On 2 September 2015, MERALCO again filed a Very Urgent Motion to Resolve, emphasizing the urgency to implement its CAPEX projects to ensure reliability and quality of service and avoid further delays.
- e. On 4 February 2016, MERALCO filed a Manifestation, dated 2 February 2016, informing the Honorable Commission that in the interest of complying with its obligation to provide safe, adequate, reliable and efficient electric service to its customers, Applicant has implemented four (4) of its proposed major CAPEX projects for RY 2016.
- f. On 1 April 2016, MERALCO filed another Manifestation of even date informing the Honorable Commission that in the pursuit of its obligation to provide safe, reliable and continuous electric service to its customers, MERALCO was constrained to implement additional priority CAPEX projects to address the need for capacity upgrades in order to avert multiple power interruptions to its customers and maintain a robust electric distribution infrastructure.

Q9: During the pendency of the RY2016 Application, why did MERALCO implement the projects under this Application?

A9: During its pendency however, MERALCO had no other recourse but to implement several priority projects included in its Application in order to ensure continuous compliance with safety and performance standards of the distribution system, and at the same time, provide the needed capacity for the forecasted growth of future electricity demand within MERALCO's franchise area. These are:

Project Title	Cost (in PhP)
Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	162,580,219.00

Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer	68,161,085.00
Rebuilding of Portion of Dasmariñas-FCIE 115kV Line	75,913,229.00
Replacement of Power Transformer No.2 at Mandaluyong Substation	52,908,466.00

We note that these projects, while not emergency at the time of their original filing under ERC Case No. 2015-016 RC, have become critical and had to be immediately implemented as an emergency CAPEX in order to ensure continuous, safe and reliable electric service and compliance with safety and performance standards of the distribution system. More importantly, the immediate implementation of these projects averted emergency conditions or situations, and at the same time, provided the needed capacity intended for the forecasted growth of future electricity demand within MERALCO's franchise area.

In addition, thereto, MERALCO is also refiling the following major capital projects:

Project Title	Cost (in PhP)
Cut-in of Pinagbuhatan Switching Station	58,635,873.00
Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation	46,443,027.00
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex	118,478,179.00

These three (3) projects are necessary to be acquired immediately in order to readily and quickly address contingencies requiring immediate response. The cut-in of Pinagbuhatan Switching Station project is intended to comply with the N-1 contingency and thus address system constraints and deficiencies. In the case of the spare power transformer, the same is urgently needed in order to have a ready replacement in the event of a failure of MERALCO's commissioned 83MVA power transformers. This will definitely prevent any prolonged and sustained power interruption in the event of a transformer failure. On the other hand, the acquisition of the 115kV line and switchyard at Navotas is urgently needed in order to have full control of such asset that are already part of MERALCO's distribution system.

Q10: You mentioned earlier that you have participated in the preparation of supporting documents to the Application. What are these projects included in the Application and their respective supporting documents?

A10: Annex “A” of the Application elaborates in detail the different Project Information Summaries and their respective supporting documents: (a) Technical and Economic Analysis; (b) Cost Estimates; (c) Expenditure Summary; (d) Cost Benefit Analysis Calculation; and (e) Gantt Chart of the following projects:

Project Title
Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)
Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer
Rebuilding of Portion of Dasmarinas-FCIE 115kV Line
Cut-in of Pinagbuhatan Switching Station
Replacement of Power Transformer No.2 at Mandaluyong Substation
Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex

(The witness showed and identified the original copies of the above-mentioned documents to the counsel.)

Q11: How much are MERALCO’s costs for the emergency and/or urgent CAPEX projects covered by the Application?

A11: MERALCO’s costs for the emergency and/or urgent CAPEX projects are:

Project Title	Cost (in PhP)
Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	162,580,219.00
Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer	68,161,085.00
Rebuilding of Portion of Dasmarinas-FCIE 115kV Line	75,913,229.00
Cut-in of Pinagbuhatan Switching Station	58,635,873.00

Replacement of Power Transformer No.2 at Mandaluyong Substation	52,908,466.00
Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation	46,443,027.00
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex	118,478,179.00

Q12: What will be the impact of MERALCO's proposed CAPEX Program on its current rates?

A12: The CAPEX projects have no immediate impact on MERALCO's rates. However, in light of the resulting benefits of MERALCO's RY 2017 CAPEX Program in the overall service to the electricity consumers, MERALCO respectfully submits that the building block components, particularly the return of capital and return on capital associated therewith, from the time it is put in service and considered used and useful, should be considered as a deferred amount to be included in MERALCO's 4RP reset calculations.

Q13: Can you tell us why you are executing this Judicial Affidavit?

A13: I am executing this Judicial Affidavit to attest to the truthfulness and veracity of the foregoing statements and in support of MERALCO's Application.

IN WITNESS WHEREOF, I have hereunto affixed my signature this 12th day of August 2016 at Pasig City, Philippines.


FRÖILAN J. SAVET
Affiant

SUBSCRIBED AND SWORN to before me this 12th day of August 2016 by Engr. Froilan J. Savet exhibiting SSS ID with No. 3309022139.

Doc. No. 245 ;
Page No. 50 ;
Book No. IV ;
Series of 2016.



ATTY. CARMEN GRACE S. RAMOS
NOTARY PUBLIC

Pasig, Pateros, Taguig & San Juan
Issued on July 13, 2015 at Pasig City
until December 31, 2016

Roll No. 55945; IBP No. 1023723; 01/08/16; RSM Chapter
PTR No. 1473409; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City


Republic of the Philippines)
City of Pasig)S.S.

ATTESTATION

I, **ADRIAN REX C. DIMALANTA**, of legal age, Filipino, with business address 7th floor, Lopez Building Meralco Center, Ortigas Avenue, Pasig City after being duly sworn depose and say:

- 1. I conducted the direct examination of ENGR. FROILAN J. SAVET, the witness to testify on matters in support of the Application entitled **"IN THE MATTER OF THE APPLICATION FOR APPROVAL OF EMERGENCY AND/OR URGENT MAJOR CAPITAL EXPENDITURE (CAPEX) PROJECTS,"** at the afore-mentioned business address;
- 2. I have faithfully recorded the questions asked and the corresponding answers that were given by the witness; and
- 3. Neither I nor any other person then present or assisting him coached the witness regarding his answers.

IN WITNESS WHEREOF, I have hereunto set my hand this 12th day of August 2016 at Pasig City.


ADRIAN REX C. DIMALANTA
Affiant

SUBSCRIBED AND SWORN to before me this 12th day of August 2016 by Atty. Adrian Rex Dimalanta who exhibited his Driver's License with No. N03-03-365433.

Doc. No. 246 ;
Page No. 51 ;
Book No. IV ;
Series of 2016.


ATTY. CARMEN GRACE S. RAMOS
NOTARY PUBLIC
Pasig, Pateros, Taguig & San Juan
Issued on July 13, 2015 at Pasig City
until December 31, 2016
Roll No. 55945; IBP No. 1023723; 01/08/16; RSM Chapter
PTR No. 1473409; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City



ORTIGAS AVENUE, PASIG CITY
0300 PHILIPPINES

ANNEX " C "

SECRETARY'S CERTIFICATE

I, WILLIAM S. PAMINTUAN, a duly elected, qualified and incumbent Assistant Corporate Secretary of the Manila Electric Company (MERALCO), a corporation duly organized and existing under and by virtue of the laws of the Philippines, do hereby certify that:

At the regular meeting of the Board of Directors of the Company duly convened and held on February 23, 2015, at which meeting a quorum was present, acted throughout and voted, the following resolution amending the resolution of the Board on January 27, 2014 on the same subject, was approved and that said amendatory resolution is in full force and effect on the date hereof:

"RESOLVED, that the Board of Directors of the Manila Electric Company (MERALCO) authorize, as it hereby authorizes, Messrs. MANUEL V. PANGILINAN, Chairman, OSCAR S. REYES, President & Chief Executive Officer, SIMEON KEN R. FERRER, Corporate Secretary, ALFREDO S. PANLILIO, Senior Vice President, Head, Customer Retail Services and Head, Corporate Communication, RAMON B. SEGISMUNDO, Senior Vice President & Head, Human Resources & Corporate Services, ROBERTO R. ALMAZORA, Senior Vice President, RAFAEL L. ANDRADA, First Vice President & Treasurer, RUBEN B. BENOSA, First Vice President & Head, Corporate Logistics, Ms. IVANNA G. DELA PEÑA, First Vice President & Head, Regulatory Management Office, WILLIAM S. PAMINTUAN, First Vice President, Assistant Corporate Secretary, Compliance Officer and Head, Legal and Corporate Governance, RONNIE L. APEROCHO, First Vice President & Head, Networks, MARTHYN S. CUAN, Vice President & Head, Corporate Information and Technology, JOSE RONALD V. VALLES, Vice President and Head, Regulatory Affairs, MARIA ZARAH R. VILLANUEVA-CASTRO, Senior Assistant Vice President & Head, Corporate Legal Services, HORATIO ENRICO M. BONA, Assistant Vice President & Head, Litigation Team 2, RAUL G. CORALDE, Assistant Vice President & Head, Litigation Team 1, MICHELLE O. DELOS SANTOS-BONA, Assistant Vice President & Head, Legal Operations Support, EUGENE JUDE DENIS GERARD E. ALABANZA, Senior Manager & Head, Litigation Team 3, CORNELIO MANUEL C. DICCION, Manager & Legal Counsel, and any lawyer or employee of MERALCO that any of them may designate, name or appoint:

- (1) to represent the Company, in the institution, prosecution, and defense of any claim, complaint, action, proceeding, petition, application, protest, suit, or case, for or against the Company, before any court, prosecutor's office, regulatory, quasi-judicial, or administrative body, agency, or office of the national or any local government;
- (2) to sign, execute, and deliver in connection therewith the necessary or appropriate complaint, petition, application, position paper, memorandum, all types of pleadings and motions, verifications, affidavit-complaint, counter-affidavit, affidavit of merit, affidavit of desistance, affidavit of witness, and all other affidavits of whatever nature, certificate of non-forum shopping,

powers of attorney, certifications, and all other instruments as may be necessary or proper;

- (3) to represent the Company or to designate, name, and appoint a representative or an attorney-in-fact in behalf of the company during the investigation, inquest, preliminary investigation, preliminary conference, pre-trial, mediation, conciliation, arbitration, trial, execution, and all other stages of or incidents related to the case, proceeding or action; to negotiate, enter into, and agree to an amicable settlement, compromise agreement, plea bargaining, admissions or stipulations of fact or documents, simplification of issues, limitation on the number of witnesses, alternative modes of dispute resolution, withdrawal, dismissal or waiver of claim or action; and to perform and execute any and all actions or deeds as may aid in the prompt disposition of such cases, proceedings, or actions filed in behalf of or against the Company;

"RESOLVED, FURTHER, that any previous resolution of the Board of Directors on the same subject matter that is inconsistent herewith shall be deemed terminated, superseded and revoked."

Pursuant to the above resolutions, it is hereby certified that MERALCO is authorized to file the Application with the Energy Regulatory Commission (ERC) entitled "IN THE MATTER OF THE APPLICATION FOR APPROVAL OF EMERGENCY AND/OR URGENT MAJOR CAPITAL EXPENDITURE (CAPEX) PROJECTS" and that Atty. JOSE RONALD V. VALLES, Vice President and Head, Regulatory Affairs, is an authorized representative and signatory of the Company with respect to the aforesaid application.

WITNESS THE SIGNATURE of the undersigned as such officer of the Company and its corporate seal hereunto affixed on this ____ day of August 2016.

AUG 12 2016


WILLIAM S. PAMINTUAN
Assistant Corporate Secretary

SUBSCRIBED AND SWORN to before me this AUG 12 2016 day of August 2016, affiant exhibited to me his Taxpayer Identification Number (TIN) 146-473-562, issued by the Bureau of Internal Revenue (BIR) as his competent evidence of identity.

Doc. No. 243;
Page No. 50;
Book No. IV;
Series of 2016.


ATTY. CARMEN GRACE S. RAMOS
NOTARY PUBLIC

Pasig, Paleros, Taguig & San Juan
Issued on July 13, 2015 at Pasig City
until December 31, 2016

Roll No. 55945; IBP No. 1023723; 01/06/16; RSM Chapter
PTR No. 1473409; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City



FILE COPY

ORTIGAS AVENUE, PASIG CITY
0300 PHILIPPINES

August 15, 2016

Office of the Sangguniang Panlungsod
City of Pasig

Gentlemen:


Attached is a copy of a verified Application entitled: "IN THE MATTER OF THE APPLICATION FOR APPROVAL OF EMERGENCY AND/OR URGENT MAJOR CAPITAL EXPENDITURE (CAPEX) PROJECTS," with attached Annexes, being served to your Office, prior to its filing with the Energy Regulatory Commission (ERC).


Please acknowledge receipt thereof in the suggested form attached.

RECEIVED
SECRETARIAT
PASIG CITY COUNCIL

BY: Renjo Jost
DATE: 08/15/16 TIME: 3:47 pm

Very truly yours,


FRANCIS DINO S. ANTONIO
Head, Regulatory Legal


/mnm/ingmd

641 8653

City Council Sec.

Malaya Business Insight

People's Independent Media, Inc.

652 Sto. Tomas St.,

Intramuros, Manila

Tel. Nos. 527-1841 * 527-7242

AFFIDAVIT OF PUBLICATION

I, **Mitchell M. Encarnado**, Filipino of legal age, married and residing at No. 1131 Prudencio St., Sampaloc, Manila after having been duly sworn to in accordance with law, depose and say:

That I am the Advertising Director of Malaya Business Insight, a daily newspaper published, edited and printed in Metro Manila and circulated nationwide, from Monday to Friday with editorial and business offices at 652 Sto. Tomas St., Intramuros, Manila.

That the attached copy of Application from ERC, re:
Manila Electric Company (MERALCO)-Applicant,

was published in Malaya Business Insight in its issue/s

August 15, 2016

In witness whereof, I signed this affidavit in
Manila Philippines, this 15th day of Aug. 2016


MITCHELL M. ENCARNADO
Advertising Director

Subscribed and Sworn to before me this 15th day
of Aug. 2016, in Mla, Philippines, affiant
exhibiting to me his Res. Cert. No. *16013647
issued at Mla on *6-17-2015

SSS No.04-0922169-7.


ATTY. VICENTE C. CRUZ
Notary Public

Until 12-31-2017

PTR No. *2131633

Issued at Q.C., 1-4-2016

Roll No. 33952/NC-NP No. 003

On: IBP: Lifetime Member No. 02322

Doc. No. 441
Page No. 89
Book No. III
Series of 2016

Malaya

VOL. XXXIV 3 SECTIONS

MONDAY, AUGUST 15, 2016 P 25.00/copy

24 PAGES

GOVERNMENTARY COPY

Business Insight

Most read, best source!

b.sinsess@malaya.com.ph

Int'l air traffic
up; PAL leads
local travel

Page A2

DMCI gets
P4.4B new
contracts

Page A3

2017 RH
budget to double
to P4.26B

Page A4

Asia loses its policy
punch as consumers
pile on debt

Page A5

Strong peso, hedging net JG Summit P2B

BY RUELLE CASTRO

THE strong peso and hedging on aviation fuel netted JG Summit Holdings Inc. P2.3 billion for the first half of the year.

The conglomerate said valuation gains from fuel hedging rose to P1.3

Win some, Lose some. JG Summit netted P2.3 billion from strong peso and hedging on aviation fuel but received less dividends from investments in PLDT and Meralco.

DOLE HALTS OPERATIONS Insurgency driving investors away

THE Pilipino Banana Growers and Exporters Association (PBGEA) said insurgents are driving away investors from Mindanao.

The New People's Army (NPA), according to Steve Antig, PBGEA executive director has forced Dole-Stanfilco to shut down operations.

Dole-Stanfilco, a multinational banana firm operating in Tagbina, Surigao del Sur, suffered a series of attacks by the NPA for refusing to pay revolutionary taxes.

PBGEA claimed that the NPA has burned a total of 19 container trucks and caused P20 million in losses to the company since 2010.

"The closure of plantations will lead to unemployment and then to poverty. There will be a domino effect on the local economy

IN THE MATTER OF THE
APPLICATION FOR APPROVAL
OF EMERGENCY AND/OR
URGENT MAJOR CAPITAL
EXPENDITURE (CAPEX)
PROJECTS,

MANILA ELECTRIC COMPANY
(MERALCO),

Applicant.

ERC CASE NO. _____

APPLICATION

Applicant MANILA ELECTRIC COMPANY (MERALCO), through the undersigned counsel, and to this Honorable Commission, most respectfully avers that:

1. Applicant MERALCO is a private corporation duly organized and existing under the laws of the Republic of the Philippines, with principal office located at Lopez Building, Ortigas Avenue, Barangay Ugong, Pasig City. It may be served with notices and other processes of this Honorable Commission through its undersigned counsel at the address indicated herein.
2. MERALCO has a legislative franchise to construct, operate and maintain an electric power distribution system for the conveyance of electric power to the end-users in the cities and municipalities of Metro Manila, Bulacan, Cavite and Rizal, and certain cities/municipalities/barangays in Batangas, Laguna, Quezon and Pampanga, pursuant to Republic Act No. 9209.
3. The Application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled: "Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.
4. However, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

DISCUSSION OF MERALCO'S EMERGENCY CAPEX PROGRAM

5. MERALCO is part of the First Entry Group of distribution utilities that entered Performance Based Regulation ("PBR"). In its Final Determination dated 6 June 2011 in ERC Case No. 2010-069 RC, the Honorable Commission set out its final position on the price control arrangements that would apply to MERALCO for the Third Regulatory Period (3RP) covering the period from 1 July 2011 to 30 June 2015, including its approval of MERALCO's proposed Capital Expenditure (CAPEX) Program, for the said period.
6. The last year of MERALCO's Third Regulatory Period expired on 30 June 2015. The Fourth Regulatory Period (4RP) for the First Entry Group commenced on 1 July 2015 and will end on 30 June 2019. However, the Honorable Commission has not yet issued the relevant rules to govern the reset process and the filing by the DUs of their reset application.
7. As such, on 9 February 2015, MERALCO filed an application for the approval of its CAPEX program for Regulatory Year (RY) 2016. The said application was docketed as ERC Case No. 2015-016 RC.
8. On 10 April 2015, MERALCO filed an Urgent Motion for Issuance of a Provisional Authority ("Urgent Motion") dated 8 April 2015 requesting that it be allowed to immediately implement its priority projects, the list of which was attached to said Urgent Motion.
9. On 15 April 2015, MERALCO filed a Motion of even date attaching a detailed list showing a further breakdown of the projects, into business segments especially those that are shared by different business segments.
10. On 11 June 2015, MERALCO filed a Very Urgent Motion for Authority to Commence Implementation of RY 2016 Priority Projects with an attached list of the RY 2016 priority projects ("Very Urgent Motion").
11. On 2 September 2015, MERALCO again filed a Very Urgent Motion to Resolve, emphasizing the urgency to implement its CAPEX projects to ensure reliability and quality of service and avoid further delays.
12. On 4 February 2016, MERALCO filed a Manifestation, dated 2 February 2016, informing the Honorable Commission that in the interest of complying with its obligation to provide safe, adequate, reliable and efficient electric service to its customers, Applicant has implemented four (4) of its proposed major CAPEX projects for RY 2016.
13. On 1 April 2016, MERALCO filed another Manifestation of even date informing the Honorable Commission that in the pursuit of its obligation to provide safe, reliable and continuous electric service to its customers, MERALCO was constrained to implement additional priority CAPEX projects to address the need for capacity upgrades in order to avert multiple power interruptions to its customers and maintain a robust electric distribution infrastructure.
14. On 15 June 2016, MERALCO received a copy of the Decision dated 12 April 2016 which partially approved MERALCO's CAPEX program for RY 2016. However, the Honorable Commission also deferred the following projects,

16. We note that these projects, while not emergency at the time of their original filing under ERC Case No. 2015-016 RC, have become critical and had to be immediately implemented as an emergency CAPEX in order to ensure continuous, safe and reliable electric service and compliance with safety and performance standards of the distribution system. More importantly, the immediate implementation of these projects averted emergency conditions or situations, and at the same time, provided the needed capacity intended for the forecasted growth of future electricity demand within MERALCO's franchise area.
17. In addition thereto, MERALCO is also refiling the following major capital projects:

Project Title	Cost (in PhP)
Cut-in of Pinagbuhatan Switching Station	58,635,873.00
Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation	46,443,027.00
Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex	118,478,179.00

These projects are necessary to be acquired immediately in order to readily and quickly address contingencies requiring immediate response. The cut-in of Pinagbuhatan Switching Station project is intended to comply with the N-1 contingency and thus address system constraints and deficiencies. In the case of the spare power transformer, the same is urgently needed in order to have a ready replacement in the event of a failure of MERALCO's commissioned 83MVA power transformers. This will definitely prevent any prolonged and sustained power interruption in the event of a transformer failure. On the other hand, the acquisition of the 115kV line and switchyard at Navotas is urgently needed in order to have full control of such asset that are already part of MERALCO's distribution system.

18. In view of the foregoing, MERALCO is refiling the foregoing projects as Emergency/ Urgent Major CAPEX projects. It must be emphasized that MERALCO's customers benefitted from the implementation of these projects as the integrity and reliability of the distribution system was maintained.

Copies of the different Project Information Summaries with supporting documents: (a) Technical and Economic Analysis; (b) Cost Estimates; (c) Expenditure Summary; (d) Cost Benefit Analysis Calculation; and (e) Gantt Chart of the projects are attached herewith as Annexes "A" and series and made integral parts hereof.

19. In further support of the Application, attached hereto as Annex "B" is the Judicial Affidavit of Mr. Froilan J. Savet, Senior Assistant Vice-President and Head of MERALCO's Network Planning and Project Management Office.

PRAYER

WHEREFORE, it is respectfully prayed to this Honorable Commission that the instant Application be APPROVED and that the building block components associated with the foregoing Major CAPEX projects from the time the same are put in service and considered use and useful be recognized as a deferred amount to be included in MERALCO's subsequent regulatory reset calculations.

Other relief just and equitable under the premises are likewise prayed for.

Pasig City, 12 August 2016.

MANILA ELECTRIC COMPANY

Applicant

MERALCO Compound
Ortigas Avenue, Pasig City

By:

FRANCIS DINO S. ANTONIO
Counsel for Applicant

Roll of Attorneys No. 48145

PTR No. 1473407; 01/21/16; Pasig City

IBP No. 1023724; 01/08/16; RSM

MCLE Compliance No. V-0004608; 6 November 2014

HAZEL ROSE B. SEE
Counsel for Applicant

Roll of Attorneys No. 48265

PTR No. 1473408; 01/21/16; Pasig City

IBP LRN No. 06460; 1/16/07; QC

MCLE Compliance No. V-0002589; 9 June 2014

MONICA M. MARTIN
Counsel for Applicant

Roll of Attorneys No. 55693

PTR No. 1473411; 01/21/16; Pasig City

IBP No. 1023726; 01/08/16; RSM

MCLE Compliance No. V-0002591; 9 June 2014

ADRIAN REX C. DIMALANTA
Counsel for Applicant

Roll of Attorneys No. 61149

PTR No. 1473413; 1/21/16; Pasig City

IBP No. 1023729; 01/08/16; PPLM

MCLE Compliance No. V-0002586; 9 June 2014

7th Floor, Lopez Building, Ortigas Avenue
Brgy. Ugong, Pasig City
Telephone Number 1622-2260; Fax No. 1622-3550

Republic of the Philippines
Pasig City

J.S.S.

• FROM PAGE B1 •

ANTI-DRUGS

of the National Highway in Barangay EjC Montilla, one of two men on a motorcycle tailing him opened fire, hitting him several times in the body.

The killers escaped towards Isulan town. Two bullet casings for a .45 caliber pistol were recovered at the crime scene.

Police have yet to establish the motive behind the killing.

Guira's killing came a day after PO2 Ryan Casiban, a member of the Cordova Police Station in Cebu, was found dead Friday night, two days after he went missing.

Reports said Casiban wrote in the station's blotter book that retired Deputy Director General Marcelo Garbo and retired Chief Supt. and now Daanbantayan Mayor Vicente Loot were alleged protectors of drug syndicates.

Garbo and Loot were among the five generals named by President Duterte as involved in illegal drugs. The others were Director Joel Pagdilao, Chief Supt. Edgardo Tinio, and Chief Supt. Bernardo Diaz.

Reports said Casiban was found by residents of Barangay Agus in Lapu-lapu City at around 9 p.m. Friday in a grassy portion of the barangay.

Police crime scene operatives recovered from the victim a Glock .9 mm pistol, three magazines with 23 bullets, a pair of handcuffs, a cell phone, and a wallet containing various IDs and papers.

Casiban's colleagues said he was supposed to be on duty from 8 p.m. on Tuesday up to 8 a.m. Wednesday but left his post at around 3 a.m. Wednesday and went missing.

In Cavite, an alleged drug suspect was shot dead by still unidentified men in Dasmarinas City Saturday night.

Police identified the fatality as Roderick Permejo, who is in the city police's drug watch list. He died on the spot due to a lone gunshot wound in the head.

Reports said residents of Barangay San Francisco 2 heard a gunshot at around 7 p.m. and later saw the victim sprawled on the ground, with a carton on top his body which bore the words "PUSHER AKO HUWAG TULARAN".

A bullet shell for a .45 cali-

ber pistol was recovered the area.

CCP WITHDRAWS SUPPORT

The Communist Party of Philippines has withdrawn support of President Duterte campaign against the proliferation of illegal drugs, saying it has turned "anti-people anti-democratic."

The CPP said Duterte's drug war has "rapidly spun into a frenzied campaign extra-judicial killings and lante murders perpetrated by the police and police-led criminal syndicates."

"The rights of tens of thousands of people are violated as the criminal justice system is upturned," the said, adding that police have summarily executed peddlers and users.

"Hundreds have been killed while 'resisting arrest' or under custody and detention police cars as well as in the added the CPP, the political of the New People's Army.

Last month, the CPP air support behind Duterte's drug campaign, saying it is the President's "reprehensible illegal drug trade and its effects on the Filipino people."

"The proliferation of drugs, especially shabu, an concomitant rise in incidence of violent crime serves the petuation of the ruling system the CPP said then.

In its latest statement to reporters on Saturday night CPP said no amount of killing put an end to the drug men.

It said the NPA will continue operations to arrest and drug trade operators and operators but said this "will no longer considered as cooperative with Duterte regime's undemocratic and anti-people war on drugs."

"As before, the NPA will continue to exercise due process dealing with suspects, such those PNP officers present custody in Compostela V. and Surigao del Sur," the group added, referring to Chief Arnold Ongachen, the chief of Gov. Generoso in Compostela Valley; and Richard Yu of Carmen police station in Surigao del PNP who were abducted by rebels last May 29, and Ju respectively. - With Victor R

HEAVY

been affected in Metro Manila, Central Luzon, Calabarzon, Western Visayas, and the Autonomous Region in Muslim Mindanao.

Of the number, 5,139 families or 24,225 persons are housed in 52 evacuation centers - 2,657 families or 12,481 persons of them are from Metro Manila. Marikina had the most number of evacuees with 1,883 families or 8,895 persons.

The Armed Forces' Joint Task Force National Capital Region has deployed 10 trucks to Marikina City to assist the city's disaster risk reduction and management office in the distribution of relief goods.

Many areas in Metro Manila were flooded but NDRRMC executive director and concurrent Office of Civil Defense director Ricardo Jalad said floods have subsided as of 3 p.m. yesterday.

He attributed the flooding to clogged drainage systems in the metropolis.

Weather forecaster Aldazar said the storm with in-

p.m. yesterday and was moving towards Japan.

The LPA was seen over West Philippine Sea, going China.

Aurelio said both weather disturbances are not expected to enter the country, but enhance the southwest monsoon in the next few days.

"Water level at the La Ramon Dam in Quezon City continues to be near its spilling level was at 80.06 meters or 9.1 meters short of the spill level of 80.15 meters, as of p.m. yesterday," said PAG- hydrologist Jason Bausa.

An overflow will affect barangays along Tullahan River from Fairview to the boun of Bagbag and Baesa, in Que City, and may bring flood some portions of Valenzuela, Malabon, and Navotas cities.

Water level at Ipo dam reached 101.50 meters, breaching its spill level of 101 meters.

Water levels at Angat Dam, Bulacan, Magat Dam in Isat Ambuklao and Binga dam; Benguet, and San Roque Dam Panagasinan continued to be

Commission's Resolution No. 26, Series of 2009, entitled: "Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.

4. However, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

DISCUSSION OF MERALCO'S EMERGENCY CAPEX PROGRAM

5. MERALCO is part of the First Entry Group of distribution utilities that entered Performance Based Regulation ("PBR"). In its Final Determination dated 6 June 2011 in ERC Case No. 2010-069 RC, the Honorable Commission set out its final position on the price control arrangements that would apply to MERALCO for the Third Regulatory Period (3RP) covering the period from 1 July 2011 to 30 June 2015, including its approval of MERALCO's proposed Capital Expenditure (CAPEX) Program, for the said period.
6. The last year of MERALCO's Third Regulatory Period expired on 30 June 2015. The Fourth Regulatory Period (4RP) for the First Entry Group commenced on 1 July 2015 and will end on 30 June 2019. However, the Honorable Commission has not yet issued the relevant rules to govern the reset process and the filing by the DUs of their reset application.
7. As such, on 9 February 2015, MERALCO filed an application for the approval of its CAPEX program for Regulatory Year (RY) 2016. The said application was docketed as ERC Case No. 2015-016 RC.
8. On 10 April 2015, MERALCO filed an Urgent Motion for Issuance of a Provisional Authority ("Urgent Motion") dated 8 April 2015 requesting that it be allowed to immediately implement its priority projects, the list of which was attached to said Urgent Motion.
9. On 15 April 2015, MERALCO filed a Motion of even date attaching a detailed list showing a further breakdown of the projects into business segments especially those that are shared by different business segments.
10. On 11 June 2015, MERALCO filed a Very Urgent Motion for Authority to Commence Implementation of RY 2016 Priority Projects with an attached list of the RY 2016 priority projects ("Very Urgent Motion").
11. On 2 September 2015, MERALCO again filed a Very Urgent Motion to Resolve, emphasizing the urgency to implement its CAPEX projects to ensure reliability and quality of service and avoid further delays.
12. On 4 February 2016, MERALCO filed a Manifestation, dated 2 February 2016, informing the Honorable Commission that in the interest of complying with its obligation to provide safe, adequate, reliable and efficient electric service to its customers, Applicant has implemented four (4) of its proposed major CAPEX projects for RY 2016.
13. On 1 April 2016, MERALCO filed another Manifestation of even date informing the Honorable Commission that in the pursuit of its obligation to provide safe, reliable and continuous electric service to its customers, MERALCO was constrained to implement additional priority CAPEX projects to address the need for capacity upgrades in order to avert multiple power interruptions to its customers and maintain a robust electric distribution infrastructure.
14. On 15 June 2016, MERALCO received a copy of the Decision dated 12 April 2016 which partially approved MERALCO's CAPEX program for RY 2016. However, the Honorable Commission also deferred the following projects, without prejudice to refiling:

Project Code	Project Title
MER-2	Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)
MER-4	Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer
MER-11	Rebuilding of Portion of Dasmariñas-FCIE 115kV Line
MER-13	Cut-in of Pinagbuhatan Switching Station
MER-14	Replacement of Power Transformer No.2 at Mandaluyong Substation
MER-15	Spare 83MVA 110 kV-34.5 kV-13.8 kV Power Transformer with OLTC for GIS Substation
MER-20	Acquisition of 115 kV Line and 115 kV Switchyard at the Navotas Fish Port Complex

15. In the light of said decision, Applicant hereby refiles the following as major emergency capital projects, to wit:

Project Title	Cost (in PhP)
Expansion of Bagbaguin 115 kV-34.5 kV Substation (2nd Bank)	162,580,219.00
Installation of 34.5 kV Metalclad Switchgear at Dasmariñas 83 MVA Power Transformer	68,161,085.00
Rebuilding of Portion of Dasmariñas-FCIE 115kV Line	75,913,229.00
Replacement of Power Transformer No.2 at Mandaluyong Substation	52,908,466.00

18. In view of the foregoing, MERALCO is refiling the foregoing projects as Emergency/ Urgent Major CAPEX projects. It must be emphasized that MERALCO's customers benefitted from the implementation of these projects as the integrity and reliability of the distribution system was maintained.

Copies of the different Project Information Summaries with supporting documents: (a) Technical and Economic Analysis; (b) Cost Estimates; (c) Expenditure Summary; (d) Cost Benefit Analysis Calculation; and (e) Gantt Chart of the projects are attached herewith as Annexes "A" and series and made integral parts hereof.

19. In further support of the Application, attached hereto as Annex "B" is the Judicial Affidavit of Mr. Froilan J. Savat, Senior Assistant Vice-President and Head of MERALCO's Network Planning and Project Management Office.

PRAYER

WHEREFORE, it is respectfully prayed to this Honorable Commission that the instant Application be APPROVED and that the building block components associated with the foregoing Major CAPEX projects from the time the same are put in service and considered use and useful be recognized as a deferred amount to be included in MERALCO's subsequent regulatory reset calculations.

Other relief just and equitable under the premises are likewise prayed for.

Pasig City, 12 August 2016.

MANILA ELECTRIC COMPANY

Applicant

MERALCO Compound
Ortigas Avenue, Pasig City

By:


FRANCIS DINO S. ANTONIO
Counsel for Applicant

Roll of Attorneys No. 48145
PTR No. 1473407; 01/21/16; Pasig City
IBP No. 1023724; 01/08/16; RSM

MCLE Compliance No. V-0004608; 6 November 2014


HAZEL ROSE B. SEE

Counsel for Applicant

Roll of Attorneys No. 48265
PTR No. 1473408; 01/21/16; Pasig City
IBP LRN No. 06460; 1/16/07; QC

MCLE Compliance No. V-0002589; 9 June 2014


MONICA M. MARTIN

Counsel for Applicant

Roll of Attorneys No. 55693
PTR No. 1473411; 01/21/16; Pasig City
IBP No. 1023726; 01/08/16; RSM

MCLE Compliance No. V-0002591; 9 June 2014


ADRIAN REX C. DIMALANTA

Counsel for Applicant

Roll of Attorneys No. 61149
PTR No. 1473413; 1/21/16; Pasig City
IBP No. 1023729; 01/08/16; PLPM

MCLE Compliance No. V-0002586; 9 June 2014

7th Floor, Lopez Building, Ortigas Avenue

Brgy. Ugong, Pasig City

Telephone Number 1622-2260; Fax No. 1622-3550

Republic of the Philippines
Pasig City


) S.S.

VERIFICATION AND CERTIFICATE OF NON-FORUM SHOPPING

I, JOSE RONALD V. VALLES, Filipino, of legal age and with office address at 7th Floor, Lopez Building, Ortigas Avenue, Pasig City, after being sworn to in accordance with law, hereby depose and say, that:-

- I am the Vice-President and Head of the Regulatory Affairs Office of Applicant Manila Electric Company;
- I have been authorized by the Board of Directors of the Applicant to cause the preparation and filing of the instant Application, I have read and understood the allegations contained therein and the same are true and correct based on my personal knowledge and authentic records made available to me in the ordinary course of business of the Applicant;
- I have been authorized by the Board of Directors to certify that Applicant has not heretofore commenced any other action or proceeding involving the same issues in the Supreme Court, the Court of Appeals, or any other tribunal or agency and to the best of my knowledge, no such action or proceeding is pending in the Supreme Court, the Court of Appeals, or any other tribunal or agency. A copy of the Secretary's Certificate authorizing the undersigned to sign this Verification and Certification is attached as Annex "C" of this Application and made integral part hereof;
- Except for the application for the approval of Applicant's Capital Expenditure Program for Regulatory Year (RY) 2016 docketed as ERC Case No. 2015-016 RC, where a decision was already rendered by the Commission and a Motion for Reconsideration was filed by an Intervenor, there is no other similar action or proceedings involving the same subject matter before the Commission or any other tribunal or agency. If I should hereafter learn that a similar action or proceeding has been filed or is pending before the Supreme Court, the Court of Appeals, or any other tribunal or agency, I undertake to report such fact within five (5) days therefrom to this Honorable Commission.

IN WITNESS WHEREOF, I have hereunto affixed my signature this 12th day of August 2016 at Pasig City, Philippines.


JOSE RONALD V. VALLES

SUBSCRIBED AND SWORN to before me this 12th day of August 2016, by affiant having exhibited his Social Security System (SSS) ID bearing the number 33-10900088.

Doc. No. 244:

Page No. 50:

Book No. 42:

Series of 2015.

Malaya - Aug. 15, 2016

illegal drugs. The others were Director Joel Pagdilao, Chief Supt. Edgardo Tinio, and Chief Supt. Bernardo Diaz.

Reports said Casiban was found by residents of Barangay Agus in Lapu-lapu City at around 9 p.m. Friday in a grassy portion of the barangay.

Police crime scene operatives recovered from the victim a Glock .9 mm pistol, three magazines with 23 bullets, a pair of handcuffs, a cell phone, and a wallet containing various IDs and papers.

Casiban's colleagues said he was supposed to be on duty from 8 p.m. on Tuesday up to 8 a.m. Wednesday but left his post at around 3 a.m. Wednesday and went missing.

In Cavite, an alleged drug suspect was shot dead by still unidentified men in Dasmariñas City Saturday night.

Police identified the fatality as Roderick Permejo, who is in the city police's drug watch list. He died on the spot due to a lone gunshot wound in the head.

Reports said residents of Barangay San Francisco 2 heard a gunshot at around 7 p.m. and later saw the victim sprawled on the ground with a carton on top his body which bore the words "PUSHER AKO HUWAG TULARAN".

A bullet shell for a .45 cali-

police cars as well as in added the CPP, the politics of the New People's Army

Last month, the CPP air support behind Duterte's drug campaign, saying it is the President's "reprehends the illegal drug trade and its effects on the Filipino people."

"The proliferation of drugs, especially shabu, are concomitant rise in incidence of violent crime serves the perpetuation of the ruling system," the CPP said then.

In its latest statement on to reporters on Saturday night CPP said no amount of killing put an end to the drug men.

It said the NPA will continue operations to arrest and drug trade operators and people but said this "will no longer considered as cooperative with Duterte regime's undemocratic and anti-people war on drugs."

"As before, the NPA will continue to exercise due process dealing with suspects, such those PNP officers present custody in Compostela Valley and Surigao del Sur," the group added, referring to Chief Arnold Ongachen, the chief of Gov. Generoso in Compostela Valley; and Richard Yu of Carmen police station in Surigao del PNP who were abducted by rebels last May 29, and July respectively. - With Victor R.

HEAVY

been affected in Metro Manila, Central Luzon, Calabarzon, Western Visayas, and the Autonomous Region in Muslim Mindanao.

Of the number, 5,139 families or 24,225 persons are housed in 52 evacuation centers - 2,657 families or 12,481 persons of them are from Metro Manila. Marikina had the most number of evacuees with 1,883 families or 8,895 persons.

The Armed Forces' Joint Task Force National Capital Region has deployed 10 trucks to Marikina City to assist the city's disaster risk reduction and management office in the distribution of relief goods.

Many areas in Metro Manila were flooded but NDRRMC executive director and concurrent Office of Civil Defense director Ricardo Jalad said floods have subsided as of 3 p.m. yesterday. He attributed the flooding to clogged drainage systems in the metropolis.

Weather forecaster Aldemar Aurelio said the storm with international name "Chantu" was spotted some 2,080 kilometers east of Itbayat, Batanes as of 2

p.m. yesterday and was moving towards Japan.

The LPA was seen over West Philippine Sea, going China.

Aurelio said both weather disturbances are not expected to enter the country, "but to enhance the southwest monsoon in the next few days."

Water level at the La Mesa Dam in Quezon City continued to be near its spilling level, was at 80.06 meters or 9 centimeters short of the spill level of 80.15 meters, as of p.m. yesterday, said PAGASA hydrologist Jason Bausa.

An overflow will affect barangays along Tullahan River from Fairview to the bounds of Bagbag and Bacsa, in Quezon City, and may bring floods some portions of Valenzuela, Malabon, and Navotas cities.

Water level at Ipo dam reach 101.50 meters, breaching its spilling level of 101 meters.

Water levels at Angat Dam Bulacan, Magat Dam in Isabela, Ambuklao and Binga dams Benguet, and San Roque Dam Pangasinan continued to be "low and very far" from its respective spilling levels. - With Angelo Lopez de Leon and Euan Orías

SENATE

with Cha-cha discussions ahead of the 2017 national budget.

"It's the committee chairman's prerogative to set the schedule of the hearing," said Jeeno Arellano, Drilon's media relations officer.

Drilon said, "The committee understands the importance of this undertaking as part of the agenda of the Duterte administration and has therefore decided to give it the highest priority."

"We have a really big task ahead of us," Drilon said, stressing that "an undertaking as monumental as revising the Constitution needs the active and direct cooperation and participation of every Filipino."

Drilon vowed that all views and opinions will be heard and taken into consideration, and

that "no one will be left in the dark."

To ensure that the hearing will be consultative, the committee will invite as resource person representatives of various sectors such as business, labor, academe, and civil society, as well as constitution and legal experts and former Supreme Court justices.

The panel plans hold a series of public hearings outside Metro Manila such as the cities of Baguio, Cebu and Davao.

Drilon said thorough consultations are needed in light of the recent survey showing that Filipinos are divided on the question of whether to amend or revise the Constitution.

Drilon is the author of Resolution of Both Houses No. calling for a constitutional convention to amend or revise the Constitution.