


Republic of the Philippines
ENERGY REGULATORY COMMISSION
 San Miguel Avenue, Pasig City



IN THE MATTER OF THE
 APPLICATION FOR APPROVAL
 OF THE EMERGENCY
 INSTALLATION OF ONE (1) 83
 MVA POWER TRANSFORMER
 AT NORTH PORT SUBSTATION,

APR 08 2016

ERC CASE NO. 2016-040 RC

**MANILA ELECTRIC COMPANY
 (MERALCO),**

Applicant.

X-----X

APPLICATION

Applicant **MANILA ELECTRIC COMPANY (MERALCO)**,
 through the undersigned counsel, and to this Honorable Commission,
 most respectfully avers that:

1. Applicant is a private corporation duly organized and existing under the laws of the Republic of the Philippines, with principal office located at Lopez Building, Ortigas Avenue, Barangay Ugong, Pasig City. It may be served with notices and other processes of this Honorable Commission through its undersigned counsel at the address indicated herein.

2. Applicant has a legislative franchise to construct, operate and maintain an electric power distribution system for the conveyance of electric power to the end-users in the cities and municipalities of Metro Manila, Bulacan, Cavite and Rizal, and certain cities/municipalities/barangays in Batangas, Laguna, Quezon and Pampanga, pursuant to Republic Act No. 9209.

3. Applicant seeks the Honorable Commission's approval of its emergency installation of one (1) 83 MVA, 115 kV-34.5 kV, three (3)-phase power transformer with On-Load Tap Changer (OLTC) for

the replacement of the North Port Substation's defective Power Transformer Bank No. 2.

4. The Application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled: "*Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects*". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.

5. However, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

BACKGROUND

6. The North Port Substation is located at Lot 1, Tayuman, Tondo, Manila. The said substation has six (6) Power Transformer Banks. Power Transformer Bank Nos. 1, 2 and 6 have a rating of 115kV-34.5kV, while the remaining banks (3, 4 and 5) have a 34.5kV-6.24kV rating. However, the Power Transformer Bank Nos. 3, 4 and 5 are only drawing power from Bank Nos. 1, 2 and 6.

7. On 15 December 2015, North Port Power Transformer Bank No. 2 was tripped out by transformer differential relay with targets of phases B & C due to exploded high side bushings (H1 & H2).

8. Thus, the power transformer was immediately subjected to initial test on 16 December 2015 that showed relatively low insulation resistance measured on primary to ground (H-G) and carbonized insulating oil on the OLTC and main tank. The test also indicated that there was a need to replace the damaged bushings.

9. On 20 December 2015, Winding Resistance and Turn Ratio test was performed on the power transformer without primary and secondary bushings. The results showed relatively low winding resistance on H1-H0 windings and low % turn ratio on H0H1-X0X1 windings, and confirmed that there was a need to replace the bushings and recondition the insulating oil.

10. Accordingly, the tripping out of North Port Power Transformer Bank No. 2 necessitated the transfer of its load to adjacent power transformers with 115 kV-34.5 kV rating namely, North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2.

11. With such a setup, the North Port Bank No. 6 was operating above critical level at 80.1% that can adversely affect the quality of electric service to the various major and vital customers in the area such as University of Sto. Tomas, Chinese General Hospital, Department of Public Works and Highways, Asian Terminals, Inc., Asia Brewery, Inc., Philippine Ports Authority, Philippine National Railways and the City Government of Manila.

12. Considering the critical effect of shifting the load of the power transformer to the adjacent North Port Bank No. 6, a stop gap measure had to be undertaken. Applicant had to use an available 83 MVA Power Transformer and temporarily install the same to replace the North Port Power Transformer Bank No. 2 so that the latter power transformer can be pulled out for further testing. The new Power Transformer was energized on 26 January 2016. Shown below are the loadings of the affected power transformers with and without the replacement of North Port Power Transformer Bank No. 2.

Table 1: Without Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	80.1%
Loading of Tutuban 83-MVA Bank No. 2	55.0%
System Loss	8,479,172 kWh

Table 2: With Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	37.1%
Loading of Tutuban 83-MVA Bank No. 2	45.3%
Loading of North Port 83-MVA Bank No. 2	52.6%
System Loss	8,229,062 kWh

13. The new 83 MVA Power Transformer had to be temporarily installed in order to normalize the level of quality of electric service of the affected customers in the City of Manila.

14. Several preparatory activities had to be undertaken before the final testing of the replaced power transformer such as, fabrication of adapter for bushings, draining of carbonized insulating oil, and installation of adapters and replacement of test bushings and sealing.

15. On 24 February 2016, a final test was conducted on the power transformer with replaced bushings. The results of the final test were released on 03 March 2016 where the Power Transformer Bank No. 2 was declared defective since the measured turns ratio of 90.01% on H0, H1-X0X1 windings exceeded the limits due turn-to-turn short on H0H1 winding.¹ The Dissolved Gas Analysis (DGA) also showed high generation of combustible gases at the time of fault as verified in the field and laboratory equipment. At this point, the new 83 MVA Power Transformer that was earlier temporarily installed was considered a permanent replacement.

16. It was extremely important for the Applicant to immediately implement the replacement of the defective transformer at North Port Substation in order to serve and promote public interest and welfare in a more suitable and adequate manner, as power interruptions in the affected areas will be avoided and affected customers will not be burdened with higher line losses resulting from emergency load shifting.

17. The cost of the emergency replacement including the cost of the 83 MVA, 115 kV–34.5 kV, three-phase power transformer with OLTC installed at North Port Substation is **FIFTY FOUR MILLION SEVEN HUNDRED SIXTY TWO THOUSAND THREE HUNDRED EIGHTY EIGHT & 98/100 PESOS (Php54,762,388.98)**. This amount also includes costs of transformer oil, taxes, duties, brokerage, trucking services and installation.

18. In further support of the Application, attached hereto are the following documents:

- **Annex “A” – Emergency CAPEX Project Information Summary with supporting documents: (i) Technical and Economic Analysis, (ii) Cost Estimates; (c) Expenditure**

¹ As per IEEE Standard C57.12.00-2006, acceptable tolerance values for winding ratios should be within $\pm 0.5\%$ of the nameplate voltages.

Summary; (iii) Cost Benefit Analysis Calculation; and (iv) Gantt Chart;

- **Annex “B”** – Documents showing the results of tests conducted on Power Transformer Bank No.2; and
- **Annex “C”** – Judicial Affidavit of Engr. Jose Mari P. Melendres, Vice President and Head of Applicant’s Sub-transmission Services Office.

PRAYER

WHEREFORE, it is respectfully prayed to this Honorable Commission that the emergency installation of one (1) 83 MVA, 115 kV – 34.5 kV, three-phase power transformer with OLTC at the North Port Substation be **APPROVED**.

Other relief just and equitable under the premises are likewise prayed for.


Pasig City, 04 April 2016.

MANILA ELECTRIC COMPANY

Applicant

Lopez Building,
Ortigas Avenue,
Barangay Ugong, Pasig City

By:




JOSE RONALD V. VALLES

Roll of Attorneys No. 42281

PTR No. 1473406; 01/21/16; Pasig City

IBP No. 1023722; 01/08/16; RSM

MCLE Compliance No. V-0002590; 9 June 2014



FRANCIS DINO S. ANTONIO

Counsel for Applicant

Roll of Attorneys No. 48145

PTR No. 1473407; 01/21/16; Pasig City

IBP No. 1023724; 01/08/16; RSM

MCLE Compliance No. V-0004608; 6 November 2014



HAZEL ROSE B. SEE


Counsel for Applicant

Roll of Attorneys No. 48265

PTR No. 1473408; 01/21/16; Pasig City

IBP LRN No. 06460; 1/16/07; QC

MCLE Compliance No. V-0002589; 9 June 2014



MONICA M. MARTIN

Counsel for Applicant

Roll of Attorneys No. 55693

PTR No. 1473411; 01/21/16; Pasig City

IBP No. 1023726; 01/08/16; RSM

MCLE Compliance No. V-0002591; 9 June 2014

7th Floor, Lopez Building
Ortigas Avenue, Barangay Ugong, Pasig City
Tel no. 1622-2260; Fax No: 1622-3550
Email: regulatory.legal.admin@meralco.com.ph

Republic of the Philippines)
City of Pasig) S.S.

VERIFICATION
and CERTIFICATION ON NON-FORUM SHOPPING

I, **RONNIE L. APEROCHO**, of legal age, married, with office address at Manila Electric Company, Technical Services Building, Meralco Center, Ortigas Avenue, Pasig City, hereby state under oath that:

1. I am the First Vice President and Head of Networks, Manila Electric Company, who is authorized to represent it in this Application as per the attached Secretary's Certificate (Annex "D");

2. I have caused the preparation of the instant Application and read the contents thereof, and I attest that the allegations herein contained are true and correct based on my personal knowledge and on authentic records;


3. I have not commenced any other action or proceeding involving the same issues in the Supreme Court, the Court of Appeals or any court, tribunal, or quasi-judicial agency and, to the best of my knowledge, no such other action or claim is pending therein; and,

4. Should I hereinafter learn that the same or a similar action or claim has been filed or is pending in the Supreme Court, the Court of Appeals or any court, tribunal, or quasi-judicial agency, I shall report the said fact within five (5) days from discovery thereof to this Honorable Commission.


RONNIE L. APEROCHO
Affiant

SUBSCRIBED and SWORN to before me this ____ day of APR 05 2016 2016, affiant exhibited to me his SSS ID No. 03-15624854 issued in the Philippines.

Doc. No. 280 ;
Page No. 57 ;
Book No. III ;
Series of 2016.


ATTY. MONICA M. MARTIN
NOTARY PUBLIC
Pasig, Paleros, Taguig & San Juan
Issued on July 13, 2015 at Pasig City
until December 31, 2016
Roll No. 55693; IBP No. 1023726; 01/08/16; RSM Chapter
PTR No. 1473411; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City

MANILA ELECTRIC COMPANY			
Emergency Project Information Summary			
Project Code	N/A	Priority Ranking	Emergency
Project Title	EMERGENCY REPLACEMENT OF POWER TRANSFORMER BANK NO. 2 AT NORTH PORT SUBSTATION		
Project Type	Renewal		
Project Driver	Network: Asset Condition		
Project Cost (in millions)	Forex: USD 1.12 M	Local: PHP 1.93 M	Total: PHP 54.76 M
Regulatory Year	RY2016	Commissioning Date	January 2016
Project Description	<p>The emergency Capital Expenditure (CAPEX) project is for the replacement of the defective 83 MVA, 115 kV – 34.5 kV, three-phase Power Transformer with On Load Tap Changer (OLTC) at North Port Substation.</p> <p>The scope of project includes among other things:</p> <ul style="list-style-type: none">• Unspotting of Power Transformer• Hauling of Power Transformer and acc.• Spotting of Power Transformer• Pre-Assembly Test (Dew Point / Core to ground)• Power Transformer Assembly and Harness/Acc.• Vacuum Drying / Leak Test• Mobilization of Oil Machine• Mobilization of ISO Tank with oil• Oil Reconditioning• Oil Filling• Hot Oil Circulation• Stabilizing / Bleeding• Electrical / Calibration Testing• Chemical testing• Final Re-touch and Clearing• De-mobilization of Heavy equipment• Protection Works and Other Substation Works• Pre-Com Checklist and Final Inspection• Commissioning• Site Clearing and Material Return• Activities for final testing of faulted power transformer		
Project Justification	<p>The North Port Substation is located at Lot 1, Tayuman, Tondo, Manila. The said substation has six (6) Power Transformer Banks. Power Transformer Bank Nos. 1, 2 and 6 have a transformation rating of 115kV-34.5kV, while the remaining banks (3, 4 and 5) have a 34.5kV-6.24kV rating. But Power Transformer Bank Nos. 3, 4 and 5 are merely drawing power from Bank Nos. 1, 2 and 6.</p> <p>When Power Transformer Bank No. 2 was tripped by differential relay with phases B & C targets due to exploded high side bushings (H₁ & H₂), the transformer was subjected to some tests: (a) Initial Test which showed relatively low insulation resistance measured on primary to ground (H-G), carbonized insulating oil on the OLTC and main tank; and damaged bushings should be replaced; and (b) Winding Resistance and Turn Ratio test on the power transformer without primary and secondary bushings that showed relatively</p>		

MANILA ELECTRIC COMPANY

Emergency Project Information Summary



low winding resistance on H1H0 windings and low % turn ratio on H0H1-X0X1 windings and that there is a need to replace the bushings and recondition the insulating oil.

Considering the failure of the North Port Power Transformer Bank No. 2, its load had to be transferred to adjacent power transformers with 115 kV-34.5 kV rating namely, North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2.

With such a setup, the North Port Bank No. 6 had to be operated above critical level at 80.1%. This may adversely affect the quality of electric service to the various major and vital customers in the area such as University of Santo Tomas, Chinese General Hospital, Department of Public Works and Highways, Asian Terminals, Inc., Asia Brewery, Inc., Philippine Ports Authority, Philippine National Railways and the City Government of Manila.

As stop gap measures to the possible adverse effects of said load shifting to customers in the area and distribution system, Applicant temporarily installed and used an available 83 MVA Power Transformer to replace the North Port Power Transformer Bank No. 2 so that the latter power transformer can be pulled out for further testing and in order to normalize the level of quality of electric service of the affected customers in the City of Manila.

The new Power Transformer was energized on 26 January 2016.

Several preparatory activities had to be undertaken before the final testing of the replaced power transformer such as, fabrication of adapter for bushings, draining of carbonized insulating oil, and installation of adapters and replacement of test bushings and sealing.

On 24 February 2016, a final test was conducted on the power transformer with replaced bushings. The result of the final test was released on 03 March 2016 where the Power Transformer Bank No. 2 was declared defective since the measured turns ratio of 90.01% on H0H1-X0X1 windings exceeded the limits due turn-to-turn short on H0H1 winding.¹ The Dissolved Gas Analysis (DGA) also showed high generation of combustible gases at the time of fault as verified in the field and laboratory equipment. At this point, the new 83 MVA Power Transformer that was earlier temporarily installed was considered a permanent replacement.

Annex A	Technical and Economic Analysis
Annex B	Project Cost
Annex C	Real to Nominal Conversion Worksheet
Annex D	Cost Benefit Analysis Calculation
Annex E	Gantt Chart

¹ As per IEEE Standard C57.12.00-2006, acceptable tolerance values for winding ratios should be within $\pm 0.5\%$ of the nameplate voltages.

ANNEX A: TECHNICAL AND ECONOMIC ANALYSIS

1. BACKGROUND

1.1. Existing System

The North Port substation has six (6) power transformer banks. The 83-MVA Power Transformer Bank No. 2 is a seventeen (17) year old, 83 MVA, 115 kV – 34.5 kV, three-phase power transformer with on-load tap changer (OLTC).

On 15 December 2015, the 83 MVA Power Transformer Bank No. 2 was tripped out by transformer differential relay with targets of phases B & C due to exploded high side bushings (H₁ & H₂). Hence, the transformer without bushings was subjected to initial test and Winding Resistance and Turn Ratio test.

However, the loads of the power transformer had to be transferred to adjacent power transformers with 115-34.5 kV rating namely, North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2 in order to serve the load requirements of Power Transformer Bank 2. As a consequence, North Port Bank No. 6 was operating above critical level. Thus, this can adversely affect the quality of electric service to affected customers in the City of Manila.

As stop gap measures, Applicant had to temporarily install and use the available 83 MVA Power Transformer so as to replace the North Port Power Transformer Bank No. 2 so that the latter transformer can be pulled out for further testing. The new Power Transformer was energized on 26 January 2016.

Also, several preparatory activities had been undertaken before the final testing of the replaced power transformer.

As above-mentioned, a final test was conducted on the power transformer with replaced bushings. The results of the final test was released on 03 March 2016 where the Power Transformer Bank No. 2 was declared defective. The DGA also showed high generation of combustible gases at the time of fault as verified in the field and laboratory equipment. At this point, the new 83 MVA Power Transformer that was earlier temporarily installed was considered a permanent replacement.

1.2. Planning Criteria and Standards

In planning for the renewal and refurbishment projects of its distribution system, MERALCO adheres to the following policies and criteria:

1.2.1. Planning Policies

Substation Maintenance/Planning Policies

- For 34.5 KV primary rating & below – inspection at least once a month
- For 115 KV/230 KV rating – inspection at least twice a month

- Thermographic Scanning and Ultrasonic Detection -at least every three months.
- Electrical Testing – every 2 years
- Oil Sampling/Testing – every year
- Dissolved Gas Analysis (DGA) – Every 3 months for 80MVA & below
- Dissolved Gas Analysis – Monthly for above 80MVA rating

1.2.2. Planning Criteria

CAPEX Projects (Maintenance) Planning Criteria

The replacement of power transformers is driven by the following criteria:

- Condition and age
 - Failure of winding ratio test.
 - Combination of optimized asset life and constant failure of electrical testing
- Technological obsolescence
 - Combination of optimized asset life and problem of parts due to obsolescence
- Compliance to regulatory and statutory requirements
 - Such as voltage variations requirements to meet customer needs
- Project NPV>0, FIRR>WACC, B/C>1.0
 - NPV – Net Present Value
 - FIRR – Finance Internal Rate of Return
 - WACC – Weighted Average Cost of Capital
 - B/C – Benefit to Cost Ratio

2. PERFORMANCE ASSESSMENT

The tripping out of North Port 83-MVA Power Transformer Bank No. 2 has resulted in the following constraints and deficiencies:

- The loads of the power transformer had to be transferred to adjacent power transformers with 115-34.5 kV rating in order to serve the load requirements of Power Transformer Bank 2;
- The transfer of loads of Power Transformer Bank No.2 to said adjacent transformers resulted in above-critical loading of North Port Bank No.6;and
- The said loading level of North Port 133-MVA Bank No. 6 should be immediately mitigated/addressed considering that its above-critical loading can adversely affect the quality of electric service to the various major and vital customers in the area such as University of Santo Tomas, Chinese General Hospital, Department of Public Works and Highways, Asian Terminals, Inc., Asia Brewery, Inc., Philippine Ports Authority, Philippine National Railways and the City Government of Manila.

2.1. Analysis

2.1.1 Qualitative Performance Measures

Parameter Under Consideration	Result without Project	Result with Project
Loading of existing North Port 133-MVA Bank No. 6 (Condition: North Port Transformer Bank no. 2 is out)	Critical level	Within normal loading condition
System Loss	Higher system loss	Lower system loss

2.1.2 Quantitative Performance Measures

Table 1: Without Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	80.1%
Loading of Tutuban 83-MVA Bank No. 2	55.0%
System Loss	8,479,172 kWh

Table 2: With Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	37.1%
Loading of Tutuban 83-MVA Bank No. 2	45.3%
Loading of North Port 83-MVA Bank No. 2	52.6%
System Loss	8,229,062 kWh

2.2. Specific Planning Criteria breached

In this project, the transformer failed the Winding Ratio, DGA and Oil Insulating tests and was recommended for immediate replacement.

3. PROJECT FORMULATION AND EVALUATION

3.1 Project Alternative

In the process of determining the most cost-effective solution to address the identified deficiencies, MERALCO generated several technically-feasible alternatives that could satisfy the requirements in a timely and efficient manner.

The problem and project alternatives are summarized below:

Problem Description	Defective Power Transformer	
Project Alternatives		Classification
Alternative 1	Replace the existing transformer with a new transformer with OLTC.	Stand-alone
Alternative 2	Transfer the load to adjacent transformers without replacement of North Port Transformer Bank No.2	Stand-alone

3.1.1 Alternative 1

Alternative 1 is replacement of the defective Power Transformer Bank No. 2 with a new 83 MVA power transformer with OLTC. With the implementation of this alternative, the load requirements of Power Transformer Bank 2 will be served without any dire impacts to the distribution system and customers.

3.1.2 Alternative 2

Alternative 2 pertains to the transfer the loads of North Port Transformer Bank No.2 to North Port 133-MVA Bank No. 6 and Tutuban 83-MVA Bank No. 2.

The repair of Power Transformer Bank No.2 was also considered but this will take a longer period of time as compared to when the same is replaced. During the period of repair, Applicant will have to resort to load shifting from North Port Power Transformer Bank No.2 to the said adjacent power transformers and this may compromise the safety, reliability and security of the distribution system

The scope of work will include not only the repair of the transformer but also transport of the transformer from North Port substation to the supplier's factory which in this case is from PT

CG Power Systems in Bogor, Indonesia and back. In the past, price quotation for repair only of similar transformer is in the amount of Php 33 M.

3.2 Technical Analysis

The following table summarizes the comparison of the advantages and disadvantages of the alternatives:

Alternative	Advantages	Disadvantages
<p>Alternative 1</p> <p>Replace the existing transformer with a new transformer with OLTC.</p>	<ul style="list-style-type: none"> Considering that there will be no transfer of loads from Power Transformer Bank No.2 to adjacent power transformers with 115kV -34.5kV rating, North Port Bank No. 6 will not be loaded above critical level. There will be no problems/concerns on loading of North Port 133-MVA Bank No. 6 and the quality and reliability of electric service to customers in said area will not be affected; Lower system loss in the affected area; and This will restore normal distribution line flexibility and ultimately ensure the reliability of the distribution system. 	<p>There is no significant disadvantage.</p>
<p>Alternative 2</p> <p>Transfer the load to adjacent transformers without replacement of North Port Transformer Bank No.2</p>	<ul style="list-style-type: none"> There is no advantage. 	<ul style="list-style-type: none"> Critical loading of North Port Bank No. 6.; The loading level of the above-mentioned power transformer bank pose serious distribution concern such that it can adversely affect the

Alternative	Advantages	Disadvantages
		<p>quality of electric service to customers in the area;</p> <ul style="list-style-type: none"> • This will increase the system loss in the affected area; and • The poor distribution line flexibility may adversely affect the reliability of the distribution system

3.2 Financial Analysis

The financial evaluations of the alternative projects are summarized in the following table:

Project Alternative	Project Description	Net Present Value (NPV) (in millions)	(FIRR)	B/C
Alternative 1	Replace the existing transformer with a transformer with OLTC	291.89	15%	1.18
Alternative 2	Transfer the load to adjacent transformers without replacement of North Port Transformer Bank No.2	-8,002.21	8.76%	0.82

4. RECOMMENDATION

Replacement of the failed 83-MVA Power Transformer at North Port Substation with a new 83-MVA Power Transformer will resolve systems constraints and deficiencies considering that it prevents the above critical loading of North Port Bank No. 6.

Without the emergency project, there will be increased exposure of the affected 34.5kV distribution lines due to emergency load shifting. Also, there will be constraints in accommodating additional loads due to inadequate capacity.

Scope of work

- Replacement of 83MVA power transformer with OLTC.
- Unspotting of Power Transformer

- Hauling of Power Transformer and acc.
- Spotting of Power Transformer
- Spotting of RCC
- Pre-Assembly Test (Dew Point / Core to ground)
- Mobilization of Heavy Eqpt
- Uncrating of Accessories (at temporary storage)
- Hauling of Accessories to Site
- Power Transformer Assembly and Harness/Acc.
- Vacuum Drying / Leak Test
- Mobilization of Oil Machine
- Mobilization of ISO Tank with oil
- Oil Reconditioning
- Oil Filling
- Hot Oil Circulation
- Stabilizing / Bleeding
- Electrical / Calibration Testing
- Chemical testing
- Final Re-touch and Clearing
- De-mobilization of Heavy equipment
- Protection Works and Other Substation Works
- Pre-Com Checklist and Final Inspection
- Commissioning
- Site Clearing and Material Return
- Activities for final testing of faulted power transformer

4.1. Impact

This will resolve the above-mentioned constraints and deficiencies of the distribution system in Manila.

ANNEX B: PROJECT COST

The project cost includes labor and material costs. The material costs are based on the moving average price of the equipment that will be used in relation to this project. The cost includes required foundation, transformer oil, taxes, duties, brokerage, trucking services and installation.

Table 1: Detailed Cost Estimates by RDWR Asset Categories

Asset category	Labor Cost	Material Cost	Other Cost	Sub-Total
Power transformer	1,521,101.73	52,831,998.47	409,288.76	54,762,388.98
Total (PhP)	1,521,101.73	52,831,998.47	409,288.76	54,762,388.98

Table 2: Summary of Cost Estimates

Description	Quantity	Major Equipment	Total
North Port Power Transformer	1	83 MVA, 115kVY-34.5kVY-13.8kVD three-phase power transformer with On –Load Tap Changer (OLTC)	54,762,388.98
Total (PhPReal 2016)			54,762,388.98

Table 3. Cost Component Breakdown

Cost Component	RY 2016
Local	1,930,390.51
FOREX (US \$)	1,118,603.91
Total (PhP, Real 2016)	54,762,388.98

ANNEX C: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
US\$ Expenditure (including all international expenditure)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (US\$ COMPONENT)			
Replacement of Power Transformer No. 2 (83 MVA, 115kV-34.5kV) at North Port Substation					
		Forecast (US\$, real) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers	1,118,604			
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution				
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Transferred subtransmission assets				
Materials	Materials and supplies (including spares)				
Subtrans	Transferred subtransmission assets				
Sub-total Regulated Distribution Services		1,118,604	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
Non-network	Information Systems Equipment (Connection)				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
Materials	Materials and supplies (including spares)				
Sub-total Distribution Connection Assets		0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
Sub-total Regulated Retail Services Assets		0	0	0	0
TOTAL CAPEX		1,118,604	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on Jun 30 of the year noted.

HISTORICAL EXPENDITURE CONVERTED TO REAL EXPENDITURE

Category	
Regulated Distribution Services Assets	
Network	Land and Land Rights (Distribution Purposes) Structures and Improvements (Distribution Purposes) Station Equipment Power transformers Switchgear Protective equipment Metering & control equipment Communications equipment Other station equipment Poles, Towers and Fixtures - Distribution Overhead Conductors and Devices - Distribution Underground Conduits - Distribution Underground Conductors and Devices - Distribution Distribution Transformers Power Conditioning Equipment Meters, Metering Instruments & Metering Transformers - Distribution Information technology equipment (distribution) Regulated Entity Property on Consumer's Premises Street Lights and Signal Systems Submarine Cables
Non-network	Land and Land Rights (non-network) Structures and Improvements (non-network) Office Furniture and Equipment Transportation Equipment Stores Equipment Tools, Shop and Garage Equipment Laboratory Equipment Information Systems Equipment (non-network) Power-operated Equipment Communication Plant and Equipment Miscellaneous Equipment
Materials	Materials and supplies (including spares)
Subtrans	Transferred subtransmission assets
Sub-total Regulated Distribution Services	
Distribution Connection Services Assets	
Network	Poles, Towers and Fixtures (Customer) Overhead Conductors and Devices (Customer) Underground Conduits (Customer) Underground Conductors and Devices (Customer) Line Transformers (Customer) Information Systems Equipment (Connection)
Non-network	Land and Land Rights (non-network) Structures and Improvements (non-network) Office Furniture and Equipment Transportation Equipment Stores Equipment Tools, Shop and Garage Equipment Laboratory Equipment Information Systems Equipment (non-network) Power-operated Equipment Communication Plant and Equipment Miscellaneous Equipment
Materials	Materials and supplies (including spares)
Sub-total Distribution Connection Assets	
Regulated Retail Services Assets	
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering) Land and land rights Structures and improvements Office Furniture and Equipment Transportation Equipment Stores Equipment Tools, Shop and Garage Equipment Laboratory Equipment Information Systems Equipment Communication Plant and Equipment Miscellaneous Equipment
Sub-total Regulated Retail Services Assets	
TOTAL CAPEX	

ANNEX C: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Local Expenditure					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (LOCAL COMPONENT)			
Replacement of Power Transformer No. 2 (83 MVA, 115kV-34.5kV) at North Port Substation					
Category		Forecast (PhP, real) (Regulatory Year)			
		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)				
	Structures and Improvements (Distribution Purposes)				
	Station Equipment				
	Power transformers	1,930,391			
	Switchgear				
	Protective equipment				
	Metering & control equipment				
	Communications equipment				
	Other station equipment				
	Poles, Towers and Fixtures - Distribution				
	Overhead Conductors and Devices - Distribution				
	Underground Conduits - Distribution				
	Underground Conductors and Devices - Distribution				
	Distribution Transformers				
	Power Conditioning Equipment				
	Meters, Metering Instruments & Metering Transformers - Distribution				
	Information technology equipment (distribution)				
Non-network	Regulated Entity Property on Consumer's Premises				
	Street Lights and Signal Systems				
	Submarine Cables				
	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Subtotal Regulated Distribution Services	1,930,391	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)				
	Overhead Conductors and Devices (Customer)				
	Underground Conduits (Customer)				
	Underground Conductors and Devices (Customer)				
	Line Transformers (Customer)				
	Information Systems Equipment (Connection)				
Non-network	Land and Land Rights (non-network)				
	Structures and Improvements (non-network)				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment (non-network)				
	Power-operated Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Materials and supplies (including spares)				
	Subtotal Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)				
	Land and land rights				
	Structures and improvements				
	Office Furniture and Equipment				
	Transportation Equipment				
	Stores Equipment				
	Tools, Shop and Garage Equipment				
	Laboratory Equipment				
	Information Systems Equipment				
	Communication Plant and Equipment				
	Miscellaneous Equipment				
	Subtotal Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		1,930,391	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

HISTORICAL EXPENDITURE CONVERTED TO REAL EXPENDITURE

Category	
Regulated Distribution Services Assets	
Network	Land and Land Rights (Distribution Purposes)
	Structures and Improvements (Distribution Purposes)
Non-network	Station Equipment
	Power transformers
	Switchgear
	Protective equipment
	Metering & control equipment
	Communications equipment
	Other station equipment
	Poles, Towers and Fixtures - Distribution
	Overhead Conductors and Devices - Distribution
	Underground Conduits - Distribution
	Underground Conductors and Devices - Distribution
	Distribution Transformers
	Power Conditioning Equipment
	Meters, Metering Instruments & Metering Transformers - Distribution
	Information technology equipment (distribution)
	Regulated Entity Property on Consumer's Premises
	Street Lights and Signal Systems
	Submarine Cables
	Land and Land Rights (non-network)
	Structures and Improvements (non-network)
Materials	Office Furniture and Equipment
	Transportation Equipment
	Stores Equipment
	Tools, Shop and Garage Equipment
	Laboratory Equipment
	Information Systems Equipment (non-network)
	Power-operated Equipment
	Communication Plant and Equipment
	Miscellaneous Equipment
	Materials and supplies (including spares)
Subtrans	
Transferred subtransmission assets	
Sub-total Regulated Distribution Services	
Distribution Connection Services Assets	
Network	Poles, Towers and Fixtures (Customer)
	Overhead Conductors and Devices (Customer)
Non-network	Underground Conduits (Customer)
	Underground Conductors and Devices (Customer)
	Line Transformers (Customer)
	Information Systems Equipment (Connection)
	Land and Land Rights (non-network)
	Structures and Improvements (non-network)
	Office Furniture and Equipment
	Transportation Equipment
	Stores Equipment
	Tools, Shop and Garage Equipment
Materials	Laboratory Equipment
	Information Systems Equipment (non-network)
	Power-operated Equipment
	Communication Plant and Equipment
	Miscellaneous Equipment
	Materials and supplies (including spares)
Sub-total Distribution Connection Assets	
Regulated Retail Services Assets	
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)
	Land and land rights
	Structures and improvements
	Office Furniture and Equipment
	Transportation Equipment
	Stores Equipment
	Tools, Shop and Garage Equipment
	Laboratory Equipment
	Information Systems Equipment
	Communication Plant and Equipment
	Miscellaneous Equipment
	Sub-total Regulated Retail Services Assets
TOTAL CAPEX	

ANNEX C: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, real)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, REAL)			
Replacement of Power Transformer No. 2 (83 MVA, 115kV-34.5kV) at North Port Substation					
		Forecast (PhP, real) (Regulatory Year)			
		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	0	0	0	0
	Structures and Improvements (Distribution Purposes)	0	0	0	0
	Station Equipment				
	Power transformers	54,762,389	0	0	0
	Switchgear	0	0	0	0
	Protective equipment	0	0	0	0
	Metering & control equipment	0	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	0	0	0	0
	Poles, Towers and Fixtures - Distribution	0	0	0	0
	Overhead Conductors and Devices - Distribution	0	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials	0	0	0	0
	Subtrans	0	0	0	0
	Sub-total Regulated Distribution Services	54,762,389	0	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
	Information Systems Equipment (Connection)	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials	0	0	0	0
	Sub-total Distribution Connection Assets	0	0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets	0	0	0	0
TOTAL CAPEX		54,762,389	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

ANNEX C: EXPENDITURE SUMMARY

MANILA ELECTRIC COMPANY					
Capital Expenditure - Major Projects					
Total Expenditure, local and foreign (PhP, nominal)					
PROJECT NAME:		CAPITAL EXPENDITURE - MAJOR PROJECTS (TOTAL, NOMINAL)			
Replacement of Power Transformer No. 2 (83 MVA, 115kV-34.5kV) at North Port Substation		Forecast (PhP, nominal) (Regulatory Year)			
Category		2016	2017	2018	2019
Regulated Distribution Services Assets					
Network	Land and Land Rights (Distribution Purposes)	0	0	0	0
	Structures and Improvements (Distribution Purposes)	0	0	0	0
	Station Equipment				
	Power transformers	54,762,389	0	0	0
	Switchgear	0	0	0	0
	Protective equipment	0	0	0	0
	Metering & control equipment	0	0	0	0
	Communications equipment	0	0	0	0
	Other station equipment	0	0	0	0
	Poles, Towers and Fixtures - Distribution	0	0	0	0
	Overhead Conductors and Devices - Distribution	0	0	0	0
	Underground Conduits - Distribution	0	0	0	0
	Underground Conductors and Devices - Distribution	0	0	0	0
	Distribution Transformers	0	0	0	0
	Power Conditioning Equipment	0	0	0	0
	Meters, Metering Instruments & Metering Transformers - Distribution	0	0	0	0
	Information technology equipment (distribution)	0	0	0	0
	Regulated Entity Property on Consumer's Premises	0	0	0	0
	Street Lights and Signal Systems	0	0	0	0
	Submarine Cables	0	0	0	0
Non-network	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Transferred subtransmission assets	0	0	0	0
	Sub-total Regulated Distribution Services		54,762,389	0	0
Distribution Connection Services Assets					
Network	Poles, Towers and Fixtures (Customer)	0	0	0	0
	Overhead Conductors and Devices (Customer)	0	0	0	0
	Underground Conduits (Customer)	0	0	0	0
	Underground Conductors and Devices (Customer)	0	0	0	0
	Line Transformers (Customer)	0	0	0	0
Non-network	Information Systems Equipment (Connection)	0	0	0	0
	Land and Land Rights (non-network)	0	0	0	0
	Structures and Improvements (non-network)	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment (non-network)	0	0	0	0
	Power-operated Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Materials and supplies (including spares)	0	0	0	0
	Sub-total Distribution Connection Assets		0	0	0
Regulated Retail Services Assets					
	Meters, Instruments & Metering Transformers (Consumer Consumption Metering)	0	0	0	0
	Land and land rights	0	0	0	0
	Structures and Improvements	0	0	0	0
	Office Furniture and Equipment	0	0	0	0
	Transportation Equipment	0	0	0	0
	Stores Equipment	0	0	0	0
	Tools, Shop and Garage Equipment	0	0	0	0
	Laboratory Equipment	0	0	0	0
	Information Systems Equipment	0	0	0	0
	Communication Plant and Equipment	0	0	0	0
	Miscellaneous Equipment	0	0	0	0
	Sub-total Regulated Retail Services Assets		0	0	0
TOTAL CAPEX		54,762,389	0	0	0

Notes : References to Regulatory Years are for the 12-month period ending on June 30 of the year noted.

Manila Electric Company
COST-BENEFIT-ANALYSIS TEMPLATE



ANNEX " D "

Project Name :
Brief Description :

Replacement of Power Transformer No. 2 (83 MVA, 115KV-34.5KV) at North Port Substation
The project is to replace the defective Power Transformer Bank No. 2 with a new 83 MVA power transformer with OLTC. With the implementation of this alternative, the load requirements of Power Transformer Bank 2 will be served without any dire impacts to the distribution system and customers.

2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030
Year 0	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Year 11	Year 12	Year 13	Year 14

(Peso amounts in thousands)

CASH INFLOWS

Operational Savings
Avoided cost
Additional Revenue
Intangible benefits

6,803.03	6,803.03	6,939.09	6,939.09	59,942.31										
6,803	6,803	6,939	6,939	59,942	0	0	0	0	0	0	0	0	0	0

CASH OUTFLOWS

Investment
Maintenance cost
Dislocation cost
Intangible cost
Net Tax Effect

54,762.39	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	32.20	-	-	-	32.84	-	34.17	-	3,432.11	-	35.54	-	36.25
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
54,762	0	32	0	33	0	33	0	34	0	3,432	0	36	0	36

NET CASH FLOWS

(47,959)	6,803	6,907	6,939	59,909	0	(33)	0	(34)	0	(3,432)	0	(36)	0	(36)
----------	-------	-------	-------	--------	---	------	---	------	---	---------	---	------	---	------

30 years

WACC 14.97%

IRR	15%
NPV	291.89
B / C	1.18

(in thousands)

2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046
Year 15	Year 16	Year 17	Year 18	Year 19	Year 20	Year 21	Year 22	Year 23	Year 24	Year 25	Year 26	Year 27	Year 28	Year 29	Year 30
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3,569.39	-	36.97	-	37.71	3,712.17	-	39.22	-	40.00	3,860.66	-	40.80	-	41.62	4,015.08
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
3,569	0	37	0	38	3,712	0	39	0	40	3,861	0	41	0	42	4,015
(3,569)	0	(37)	0	(38)	(3,712)	0	(39)	0	(40)	(3,861)	0	(41)	0	(42)	(4,015)

Manila Electric Company

COST-BENEFIT-ANALYSIS TEMPLATE



Project Name : Permanent Loadshift prior to next RP filing

Brief Description : The project pertains to the transfer the loads of North Port Transformer Bank No.2 to adjoining banks particularly Tutuban 83-MVA Bank No. 2 and North Port Bank No. 6 and without replacement of North Port Transformer Bank No.2

	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029
	Year 0	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Year 11	Year 12	Year 13
(Peso amounts in thousands)														
CASH INFLOWS														
Operational Savings	13,690.60	13,690.60	13,690.60	13,690.60										
Avoided cost														
Additional Revenue														
Intangible benefits														
	13,691	13,691	13,691	13,691	0	0	0	0	0	0	0	0	0	0
CASH OUTFLOWS														
Investment	126.27	126.27	3,246.90	3,246.90	59,942.31	-			-	-	-	-	-	-
Maintenance cost	139	-	-	-	-	-	-	-	-	-	-	-	-	-
Dislocation cost	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Intangible cost	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Net Tax Effect	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	266	126	3,247	3,247	59,942	0	0	0	0	0	0	0	0	0
NET CASH FLOWS	13,425	13,564	10,444	10,444	(59,942)	0	0	0	0	0	0	0	0	0

30 years


WACC 14.97%

IRR	8.76%
NPV	(8,002.21) (in thousands)
B/C	0.82

2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046
Year 14	Year 15	Year 16	Year 17	Year 18	Year 19	Year 20	Year 21	Year 22	Year 23	Year 24	Year 25	Year 26	Year 27	Year 28	Year 29	Year 30
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Initial Gantt Chart for the Replacement of North Port Bank 2

ANNEX " E "



() PMT () Serviced () Reconditioned () New ☒ Faulted () Others

INSULATION POWER FACTOR TEST						INSULATION RESISTANCE (meg-ohms)				TESTS ON THE INSULATING OIL						
Winding	Cap.	mA	watts	% IPF @ ____ °C	% IPF @ 20°C	Aft. 1 min.		Aft. 10 min			DBV	IFT	NN	COLOR	% IPF @ 20 °C	WATER CONTENT
H - G						500 V	2500 V	500 V	2500 V	P.I.						
X - G							4.62				TCG Content =					
Y - G	- NOT CONDUCTED -						2986				Key Gases that Exceeded Normal Limit					
H - X							4900				() H ₂	() O ₂	() C ₂ H ₂	() C ₂ H ₄		
X - Y							2806				() CO	() CO ₂	() C ₄ H ₄	() None		
Y - H							6320				Interpretation:					
							5230									
EXCITING CURRENT MEASUREMENT (mA)						TTR TEST: As Fnd Tap:										
Wndg.	2.5KV	5.0KV	7.5KV	10kv	Winding	As Fnd.	Comp.	% Ratio								
H H																
H H	- NOT CONDUCTED -				- NOT CONDUCTED -											
H H																
LIGHTNING ARRESTERS			WINDING RESISTANCE			FULL VOLTAGE EXCITATION										
Phase	mA	watts	Wndg.	at ____	at 75°C	Winding	Core Loss (Watts)									
PRIM.A																
PRIM.B																
PRIM.C																
SEC.A						Winding	I ex (amperes)									
SEC.B																
SEC.C																
TERT.A																
TERT.B																
TERT.C																
						CORE-TO-GRD. INS. RES. (meg-ohms)										
						at 500V		at 2500V								
NO.	OIL Level		BUSHINGS				Hot Collar		BUSHING DATA			OIL-CONSERVATION METHOD				
	HI	LO	mA	watts	% IPF @ ____ °C	% IPF @ 20°C	mA	watts	Make	Serial Number	Factory % IPF	() Gas-Blanketed / Sealed ✓ Conservator () Other				
H1												GENERAL CONDITIONS				
H2																
H3																
H0																
X1												Insulating Oil				
X2																
X3																
X0																
Y1												Winding Tap-Charger				
Y2												Winding Insulation				
Y3												Bushings				
												Lightning Arresters				
												Cooling Fans				

SUBSTATION PREVENTIVE MAINTENANCE PROCEDURE

POWER TRANSFORMER TEST REPORT

ANNEX " B-1 "

PM-DSSB-251.02
Rev. Code: 01

Page 1 of 1

Effectivity Date: February 25, 2011

Location: NORTH PORT S/S

PXF Unit No.: 2

Date Tested: December 20, 2015

Make: PAUWELLS

Serial No.: 98.4.0785 Class: ONAN-ONAF1-2 Type: ORV-50/230

~~KVA~~ (11) 50/66.67/83.33

Voltage Rating: 110/34.5/13.8kV Oil Temp.: 35°C Wdg. Temp.: 35°C

Tested by: EM, GV, PM, ED

Weather: Fair Ambient Temp.: 32°C % Rel. Humidity: 60

Witnessed by: Mr. J. E. Co

() PMT () Serviced () Reconditioned () New (X) Faulted () Others

INSULATION POWER FACTOR TEST							INSULATION RESISTANCE (meg-ohms)					TESTS ON THE INSULATING OIL						
Winding	Cap.	mA	watts	% IPF @ ____ °C	% IPF @ 20 °C		Aft. 1 min.		Aft. 10 min			DBV	IFT	NN	COLOR	% IPF @ 20 °C	WATER CONTENT	
500 V	2500 V	500 V	2500 V	P.I.	39			39.7 - 0.5			1.7							
H-G												TCG Content = 7.31%						
X-G												Key Gases that Exceeded Normal Limit						
Y-G	- NOT CONDUCTED -											<div> <div>H₂</div> <div>O₂</div> <div>C₂H₂</div> <div>C₂H₄</div> </div>						
H-X												<div> <div>CO</div> <div>CO₂</div> <div>C₂H₄</div> <div>None</div> </div>						
X-Y												Interpretation: <u>Arching w/ high discharge current and temperature (see separate report)</u>						
Y-H												LOADING						
EXCITING CURRENT MEASUREMENT (mA)							TTR TEST: As Fnd Tap: 1(121,000V)											
Wndg.	2.5KV	5.0KV	7.5KV	10kv	Winding	As Fnd.	Comp.	% Ratio										
H H					H ₀ H ₁ -X ₀ X ₁	3.157	3.507	90.014										
H H					H ₀ H ₂ -X ₀ X ₂	3.497	3.507	99.708										
H H					H ₀ H ₃ -X ₀ X ₃	3.494	3.507	99.622										
LIGHTNING ARRESTERS				WINDING RESISTANCE			FULL VOLTAGE EXCITATION					VISUAL INSPECTION						
Phase	mA	watts	Wndg.	at 35°C	at 75°C	Winding	Core Loss (Watts)				Oil Level <u>LOW OIL LEVEL</u>							
PRIM. A			H ₀ H ₁	70.5mΩ	81.0mΩ						Oil Leaks <u>TOP OF PXF</u>							
PRIM. B			H ₀ H ₂	169.2mΩ	194.3mΩ						Dehydrator <u>OK</u>							
PRIM. C			H ₀ H ₃	168.8mΩ	193.9mΩ						Cooling Fans <u>OK</u>							
SEC. A			X ₀ X ₁	10.87mΩ	12.62mΩ	Winding	I _{ex} (amperes)				N ₂ Pressure <u>-</u>							
SEC. B			X ₀ X ₂	10.65mΩ	12.37mΩ						<div> <div>VECTOR DIAGRAM</div> </div>							

Instruments Used: TR-30, TO-4

REMARKS: Tested without primary and secondary bushings. Results of winding resistance and turns ratio are as follows: 1.) relatively low winding resistance on H₀H₁ winding 2.) Low % turns ratio on H₀H₁ - X₀X₁ windings. For final test after replacement of damage bushings and reconditioning of insulating oil.

Received by:

Checked by:

Approved by: _____

Retention: EQUIPMENT LIFE



SUBSTATION PREVENTIVE MAINTENANCE PROCEDURE
POWER TRANSFORMER TEST REPORT

ANNEX " B-2 "

PM-DSSB-251.02
Rev. Code: 01

Page 1 of 1

Effectivity Date: February 25, 2011

Location: NORTH PORT S/S

PXF Unit No.: 2

Date Tested: February 24, 2016

Make: PAWELLS

Serial No.: 98.4.0785 Class: ONAN/ONAF-2 Type: ORV-50/230

KVA: (11) 50/66.67/83.33

Voltage Rating: 10/34.5/13.8KV Oil Temp.: 35°C Wdg. Temp.: 35°C

Tested by: EM, GV, PM, ED

Weather: FAIR Ambient Temp.: 32°C % Rel. Humidity: 57

Witnessed by: Mr. J. ECO

() PMT () Serviced () Reconditioned () New (X) Faulted () Others

INSULATION POWER FACTOR TEST						INSULATION RESISTANCE (meg-ohms)					TESTS ON THE INSULATING OIL						
Winding	Cap.	mA	watts	% IPF		Aft. 1 min.		Aft. 10 min.		P.I.	DBV	IFT	NN	COLOR	% IPF @ 20 °C	WATER CONTENT	
				@ 35 °C	@ 20 °C	500 V	2500 V	500 V	2500 V								
H-G		17.0	18.0	10.6	5.40		4.67										
X-G		6.1	1.1	1.803	0.92		2986										
Y-G		63	9.7	1.460	0.74		4900										
H-X		33	5.4	1.636	0.83		2800										
X-Y		59	10.8	1.183	0.93		6320										
Y-H		0.45	0.055	1.222	0.67		5230										
EXCITING CURRENT MEASUREMENT (mA)						TTR TEST: As Fnd Tap: 1 (12/08/16)						TESTS ON THE INSULATING OIL					
Wdg.	2.5KV	5.0KV	7.5KV	10kv	Winding	As Fnd.	Comp.	% Ratio									
H ₀ H ₁	- HIGH EXCITING CURRENT -				H ₀ H ₁ -X ₀ X ₁	3.157	3.507	90.014									
H ₀ H ₂					H ₀ H ₂ -X ₀ X ₂	3.407	3.507	99.708									
H ₀ H ₃					H ₀ H ₃ -X ₀ X ₃	3.464	3.507	99.622									
LIGHTNING ARRESTERS						WINDING RESISTANCE				FULL VOLTAGE EXCITATION				LOADING			
Phase	mA		watts		Wdg.	at 35°C		at 75°C		Winding	Core Loss (Watts)			VISUAL INSPECTION			
PRIM. A					H ₀ H ₁	70.5mΩ		8.0mΩ						Oil Level <u>LOW OIL LEVEL</u>			
PRIM. B					H ₀ H ₂	169.2mΩ		194.3mΩ						Oil Leaks <u>TOP OF PXF</u>			
PRIM. C					H ₀ H ₃	168.8mΩ		193.9mΩ						Dehydrator <u>OK</u>			
SEC. A					X ₀ X ₁	10.87mΩ		12.61mΩ		Winding	I ex (amperes)			Cooling Fans <u>OK</u>			
SEC. B					X ₀ X ₂	10.65mΩ		12.37mΩ						N ₂ Pressure <u>-</u>			
SEC. C					X ₀ X ₃	10.69mΩ		12.41mΩ						VECTOR DIAGRAM			
TERT. A																	
TERT. B														CORE-TO-GRD. INS. RES. (meg-ohms)			
TERT. C														at 500V at 2500V			
NO.	Oil Level		BUSHINGS				Hot Coker		BUSHING DATA			OIL-CONSERVATION METHOD					
	HI	LO	mA	watts	% IPF @ 35 °C	% IPF @ 20 °C	mA	watts	Make	Serial Number	Factory % IPF	() Gas-Blanketed / Sealed					
H1												(X) Conservator () Other					
H2																	
H3																	
H0																	
X1																	
X2																	
X3																	
X0																	
Y1																	
Y2-Y6																	
Y3																	

Instruments Used: DTS-1K, MG-5K4, TTR-30, TD-4

REMARKS: Final test after replacement of all damage bushings and reconditioning of oil. Below is the summary of findings:

1.) low % ratio (90.014%) at H₀H₁-X₀X₁ wdg., 2.) low wdg. resistance at H₀H₁ wdg., 3.) High exciting current on H₀H₁ wdg., 4.) High % IPF at primary to ground (H-G) wdg. Above transformer is declared defective and recommended for replacement.

Received by: _____

Checked by: [Signature]

Approved by: [Signature]

Republic of the Philippines
ENERGY REGULATORY COMMISSION
San Miguel Avenue, Pasig City

ANNEX "C" "

IN THE MATTER OF THE
APPLICATION FOR APPROVAL
OF THE EMERGENCY
INSTALLATION OF ONE (1) 83
MVA POWER TRANSFORMER
AT NORTH PORT SUBSTATION,

ERC CASE NO. _____

MANILA ELECTRIC COMPANY
(MERALCO),

Applicant.

X-----X

JUDICIAL AFFIDAVIT
OF ENGR. JOSE MARI P. MELENDRES

I, **JOSE MARI P. MELENDRES**, Filipino, of legal age, married and with office address at 4th floor, Technical Services Building, Ortigas Avenue, Barangay Ugong, Pasig City, Philippines after being sworn to in accordance with law, fully conscious that I am answering the questions under oath and with knowledge that I may face criminal liability for false testimony and perjury, hereby depose and state THAT:

Q1: What are your professional and educational qualifications?

A1: I am a licensed Professional Electrical Engineer. I passed the PEE Board Examination in 2004.

I have a Bachelor of Science degree in Electrical Engineering from Mapua Institute of Technology and a Master of Science in Electrical Engineering from University of the Philippines.

Q2: Where are you presently employed?

A2: I am presently employed at Manila Electric Company (MERALCO) as Vice President and Head of the Sub-transmission Services Office. Prior to that, I held the following positions: (a) Head of Substation Services Asset Management (SSAM) effective April 11, 2011 and (b) Head of Substation since April 1, 2006.

Q3: How long have you been employed by MERALCO?

A3: I have been employed by MERALCO for thirty-two (32) years.

Q4: What are your duties and responsibilities as Vice President and Head of MERALCO's Sub-transmission Services Office?

A4: The following, among other things, are my principal duties and responsibilities:

My major responsibilities as Sub-transmission Services Head include the Sub-transmission Lines, Substation, Power System Protection, SCADA and Testing. As Substation Services Asset Management Head, I manage Sub-transmission Process Management, Maintenance Planning and Performance Management and Development of Sub-transmission Standards. Basically as Head of Sub-transmission Office, my responsibilities include the construction, commissioning, operation, testing and maintenance of all MERALCO sub-transmission lines, substations, protective relays and SCADA.

Q5: Are you familiar with the Application of MERALCO entitled, **"IN THE MATTER OF THE APPLICATION FOR APPROVAL OF THE EMERGENCY INSTALLATION OF ONE (1) 83 MVA POWER TRANSFORMER AT NORTH PORT SUBSTATION"**?

A5: Yes. I am familiar with said Application as I have participated in the preparation of the said Application as well as its supporting documents.

Q6: What is the legal basis for filing of the instant Application?

A6: The Application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled, "Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.

Further, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

Q7: What is the Application all about?

A7: In brief, the Application seeks the Honorable Commission's approval of the emergency installation of one (1) 83 MVA, 115 kV–34.5 kV, three-phase power transformer with On-Load Tap Changer (OLTC) as a replacement for the North Port Substation's defective Power Transformer Bank No. 2. A copy of the Emergency CAPEX Project Information Summary is hereto attached as Annex "A".

(The witness showed and identified the original copy of the above-mentioned document to the counsel.)

Q8: What is the emergency Capital Expenditure project that is subject of the instant Application?

A8: The emergency CAPEX pertains to the installation of one (1) 83 MVA, 115 kV – 34.5 kV, three-phase power transformer with On-Load Tap Changer (OLTC) as a replacement for the North Port Substation's defective Power Transformer Bank No. 2.

As a background, the North Port Substation is located at Lot 1, Tayuman, Tondo, Manila. The said substation has six (6) Power Transformer Banks. Power Transformer Bank Nos. 1, 2 and 6 have a rating of 115kV-34.5kV, while the remaining banks (3, 4 and 5) have a 34.5kV-6.24kV rating. However, Power Transformer Bank Nos. 3, 4 and 5 are drawing power from Bank Nos. 1, 2 and 6.

On 15 December 2015, North Port Power Transformer Bank No. 2 was tripped out by transformer differential relay with targets of phases B & C due to exploded high side bushings (H1 & H2).

Thus, the power transformer was immediately subjected to initial test on 16 December 2015 that showed relatively low insulation resistance measured on primary to ground (H-G) and carbonized insulating oil on the OLTC and main tank. The test also indicated that there was a need to replace the damaged bushings.

On 20 December 2015, Winding Resistance and Turn Ratio test was performed on the power transformer without primary and secondary bushings. The results showed relatively low winding resistance on H1H0 windings and low % turn ratio on H0H1-X0X1 windings, and confirmed that there was a need to replace the bushings and recondition the insulating oil.

Attached as Annexes "B" and "B– 1" are the results of the said tests on Power Transformer Bank No.2.

(The witness showed and identified the original copies of the above-mentioned documents to the counsel.)

Considering the failure of the North Port Power Transformer Bank No. 2, its load had to be transferred to adjacent power transformers with 115 kV-34.5 kV rating namely, North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2.

With such a setup, the North Port Bank No. 6 had to be operated above critical level at 80.1%. This may adversely affect the quality of electric service to the various major and vital customers in the area such as University of Santo Tomas, Chinese General Hospital, Department of Public Works and Highways, Asian Terminals, Inc., Asia Brewery, Inc., Philippine Ports Authority, Philippine National Railways and the City Government of Manila.

As stop-gap measures to the possible adverse effects of load shifting to customers in the area and distribution system, Applicant temporarily installed and used an available 83 MVA Power Transformer to replace the North Port Power Transformer Bank No. 2 so that the latter power transformer can be pulled out for further testing and in order to normalize the level of quality of electric service of the affected customers in the City of Manila.

The new Power Transformer was energized on 26 January 2016.

Several preparatory activities had to be undertaken before the final testing of the replaced power transformer such as, fabrication of adapter for bushings, draining of carbonized insulating oil, and installation of adapters and replacement of test bushings and sealing.

On 24 February 2016, a final test was conducted on the power transformer with replaced bushings. The result of the final test was released on 03 March 2016 where the Power Transformer Bank No. 2 was declared defective since the measured turns ratio of 90.01% on H0H1-X0X1 windings exceeded the limits due turn-to-turn short on H0H1 winding.¹ The Dissolved Gas Analysis (DGA) also showed high generation of combustible gases at the time of fault as verified in the field and laboratory equipment. At this point, the new 83 MVA Power Transformer that was earlier temporarily installed was considered a permanent replacement.

¹ As per IEEE Standard C57.12.00-2006, acceptable tolerance values for winding ratios should be within $\pm 0.5\%$ of the nameplate voltages.

Attached as Annex “B-2” is the result of the final test on Power Transformer Bank No.2.

(The witness showed and identified the original copy of the above-mentioned document to the counsel.)

Q9: Why was there a need to implement the emergency project?

A9: The immediate implementation of the project was necessary for the following reasons:

- a. Power Transformer Bank No.2 failed the above-mentioned tests. It was found defective and needed to be replaced;
- b. The tripping out of North Port Power Transformer Bank No. 2 necessitated the transfer of its loads to adjacent power transformers with 115kV-34.5 kV rating such as North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2. Load shifting caused the North Port Bank No. 6 to be loaded above the critical level of 80.1% that can adversely affect the quality of electric service to the customers in Manila. Shown below are the projected loadings of the affected power transformers with and without the replacement of North Port Power Transformer Bank No. 2.

Table 1: Without Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	80.1%
Loading of Tutuban 83-MVA Bank No. 2	55.0%
System Loss	8,479,172 kWh

Table 2: With Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	37.1%
Loading of Tutuban 83-MVA Bank No. 2	45.3%
Loading of North Port 83-MVA Bank No. 2	52.6%
System Loss	8,229,062 kWh

- c. As shown in the tables, the implementation of the project resulted to a lower system loss in the affected area at 8,229,062 kWh

as compared to when the same is not implemented at 8,479,172 kWh; and

d. The implementation of the project restored the normal distribution line flexibility and ultimately ensure the reliability of the distribution system.

Q10: What was the cost of the emergency project?

A10: The cost of the emergency replacement including the cost of the 83 MVA, 115 kV – 34.5 kV, three-phase power transformer with OLTC installed at North Port Substation is **FIFTY FOUR MILLION SEVEN HUNDRED SIXTY TWO THOUSAND THREE HUNDRED EIGHT EIGHT & 98/100 (Php54,762,388.98)**. This amount also includes costs of transformer oil, taxes, duties, brokerage, trucking services and installation. The immediate implementation of the project is necessary for the following reasons.

Q11: Can you tell us why you are executing this Judicial Affidavit?

A11: I am executing this Judicial Affidavit to attest to the truthfulness and veracity of the foregoing statements and in support of MERALCO's Application.

IN WITNESS WHEREOF, I have hereunto affixed my signature this 4th day of April 2016 at Pasig City, Philippines.



JOSE MARI P. MELENDRES
Affiant

Republic of the Philippines)
City of Pasig)S.S.

ATTESTATION

I, **ADRIAN REX C. DIMALANTA**, of legal age, Filipino, with business address 7th floor, Lopez Building Ortigas Avenue, Barangay Ugong, Pasig City after being duly sworn depose and say:


1. I conducted the direct examination of **ENGR. JOSE MARI P. MELENDRES**, the witness to testify on matters in support of the Application entitled **"IN THE MATTER OF THE APPLICATION FOR APPROVAL OF THE EMERGENCY INSTALLATION OF ONE (1) 83 MVA POWER TRANSFORMER AT NORTH PORT SUBSTATION,"** at the afore-mentioned business address;
2. I have faithfully recorded the questions asked and the corresponding answers that were given by the witness; and
3. Neither I nor any other person then present or assisting him coached the witness regarding his answers.

IN WITNESS WHEREOF, I have hereunto set my hand this 4th day of April 2016 at Pasig City.


ADRIAN REX C. DIMALANTA
Affiant

SUBSCRIBED AND SWORN to before me this 7th day of April 2016 by affiant **ENGR. JOSE MARI P. MELENDRES** who showed his SSS ID with No.0368772229 and **ATTY. ADRIAN REX C. DIMALANTA** who exhibited his SSS No. 3421328300.

Doc. No. 283 ;
Page No. 56 ;
Book No. III ;
Series of 2016.


ATTY. MONICA M. MARTIN
NOTARY PUBLIC
Pasig, Pateros, Tiguing & San Juan
Issued on July 12, 2015 at Pasig City
until December 31, 2016
Roll No. 55693; IBP No. 1023726; 01/08/16; RSM Chapter
PTR No. 1473411; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City



ORTIGAS AVENUE, PASIG CITY
0300 PHILIPPINES

ANNEX " D "

SECRETARY'S CERTIFICATE

I, **WILLIAM S. PAMINTUAN**, a duly elected, qualified and incumbent Assistant Corporate Secretary of the Manila Electric Company (MERALCO), a corporation duly organized and existing under and by virtue of the laws of the Philippines, do hereby certify that:

At the regular meeting of the Board of Directors of the Company duly convened and held on February 23, 2015, at which meeting a quorum was present, acted throughout and voted, the following resolution amending the resolution of the Board on January 27, 2014 on the same subject, was approved and that said amendatory resolution is in full force and effect on the date hereof:

"RESOLVED, that the Board of Directors of the Manila Electric Company (MERALCO) authorize, as it hereby authorizes, Messrs. **MANUEL V. PANGILINAN**, Chairman, **OSCAR S. REYES**, President & Chief Executive Officer, **SIMEON KEN R. FERRER**, Corporate Secretary, **ALFREDO S. PANLILIO**, Senior Vice President, Head, Customer Retail Services and Head, Corporate Communication, **RAMON B. SEGISMUNDO**, Senior Vice President & Head, Human Resources & Corporate Services, **ROBERTO R. ALMAZORA**, Senior Vice President, **RAFAEL L. ANDRADA**, First Vice President & Treasurer, **RUBEN B. BENOSA**, First Vice President & Head, Corporate Logistics, **Ms. IVANNA G. DELA PEÑA**, First Vice President & Head, Regulatory Management Office, **WILLIAM S. PAMINTUAN**, First Vice President, Assistant Corporate Secretary, Compliance Officer and Head, Legal and Corporate Governance, **RONNIE L. APEROCHO**, First Vice President & Head, Networks, **MARTHYN S. CUAN**, Vice President & Head, Corporate Information and Technology, **JOSE RONALD V. VALLES**, Vice President and Head, Regulatory Affairs, **MARIA ZARAH R. VILLANUEVA-CASTRO**, Senior Assistant Vice President & Head, Corporate Legal Services, **HORATIO ENRICO M. BONA**, Assistant Vice President & Head, Litigation Team 2, **RAUL G. CORALDE**, Assistant Vice President & Head, Litigation Team 1, **MICHELLE O. DELOS SANTOS-BONA**, Assistant Vice President & Head, Legal Operations Support, **EUGENE JUDE DENIS GERARD E. ALABANZA**, Senior Manager & Head, Litigation Team 3, **CORNELIO MANUEL C. DICCION**, Manager & Legal Counsel, and any lawyer or employee of MERALCO that any of them may designate, name or appoint:

- (1) to represent the Company, in the institution, prosecution, and defense of any claim, complaint, action, proceeding, petition, application, protest, suit, or case, for or against the Company, before any court, prosecutor's office, regulatory, quasi-judicial, or administrative body, agency, or office of the national or any local government;
- (2) to sign, execute, and deliver in connection therewith the necessary or appropriate complaint, petition, application, position paper, memorandum, all types of pleadings and motions, verifications, affidavit-complaint, counter-affidavit, affidavit of merit, affidavit of desistance, affidavit of witness, and all other affidavits of whatever nature, certificate of non-forum shopping,

powers of attorney, certifications, and all other instruments as may be necessary or proper;


- (3) to represent the Company or to designate, name, and appoint a representative or an attorney-in-fact in behalf of the company during the investigation, inquest, preliminary investigation, preliminary conference, pre-trial, mediation, conciliation, arbitration, trial, execution, and all other stages of or incidents related to the case, proceeding or action; to negotiate, enter into, and agree to an amicable settlement, compromise agreement, plea bargaining, admissions or stipulations of fact or documents, simplification of issues, limitation on the number of witnesses, alternative modes of dispute resolution, withdrawal, dismissal or waiver of claim or action; and to perform and execute any and all actions or deeds as may aid in the prompt disposition of such cases, proceedings, or actions filed in behalf of or against the Company;

"RESOLVED, FURTHER, that any previous resolution of the Board of Directors on the same subject matter that is inconsistent herewith shall be deemed terminated, superseded and revoked."

Pursuant to the above resolutions, it is hereby certified that MERALCO is authorized to file the Application, entitled "IN THE MATTER OF THE APPLICATION FOR APPROVAL OF THE EMERGENCY INSTALLATION OF ONE (1) 83 MVA POWER TRANSFORMER AT NORTH PORT SUBSTATION," with the Energy Regulatory Commission (ERC), and that Mr. Ronnie L. Aperoch, Senior Executive Vice President and Head, Networks, is an authorized representative and signatory of the Company with respect to the aforesaid Application.


WITNESS THE SIGNATURE of the undersigned as such officer of the Company and its corporate seal hereunto affixed on this 30 day of March 2015.

MAR 30 2016


WILLIAM S. PAMINTUAN
Assistant Corporate Secretary

SUBSCRIBED AND SWORN to before me this 30 day of March 2015, affiant exhibited to me his Taxpayer Identification Number (TIN) 146-473-562, issued by the Bureau of Internal Revenue (BIR) as his competent evidence of identity.

Doc. No. 299;
Page No. 62;
Book No. I;
Series of 2016.


ATTY. RAYMOND B. YAP
NOTARY PUBLIC
Pasig, Pateros, Taguig & San Juan
Issued on April 6, 2015 at Pasig City
until December 31, 2016
Rol No. 55889; LSP No. 1023728; 01/08/16; Capiz
PTR No. 1A73414; 01/21/16; Pasig City
7th Floor, Lopez Bldg., Ortigas Ave., Pasig City



Republic of the Philippines
SANGGUNIANG PANLUNGSOD
City Government of Pasig

ACKNOWLEDGEMENT

This is to acknowledge the receipt of a copy of Manila Electric Company's (MERALCO) verified Application entitled "IN THE MATTER OF THE APPLICATION FOR APPROVAL OF THE EMERGENCY INSTALLATION OF ONE (1) 83 MVA POWER TRANSFORMER AT NORTH PORT SUBSTATION", with **attached Annexes**, being served by MERALCO, prior to its filing with the Energy Regulatory Commission (ERC).

This acknowledgement is being issued upon the request of MERALCO for whatever legal intents and purposes it may served.

Issued this **7th** day of **April 2016** at Pasig City.


LOIDA U. VILLANUEVA
Acting City Council Secretary

ROCKWELL
PRIMARIES

DISCOVER MORE
(02) 828 9888


VISIT OUR 2-BEDROOM POP-UP MODEL UNIT
AT THE POWER PLANT MALL
ON MARCH 28 TO APRIL 14

HLURB TLS NO. ENCRFO-015-17-021 | AA-2016/03-1196
30 West Capital Drive Corner United St., Kapitolyo, Pasig City | rockwellprimaries.com.ph
Completion Date: September 2020 | Owner: Developer: Rockwell Properties Development Corporation



THE
Vantage
AT KAPITOLYO

ISSN 1908-1189
9 770190 811892



BusinessMirror

Now the
No. 1 Daily
Business
Newspaper in
the Philippines



A broader look at today's business

■ Wednesday, April 6, 2016 Vol. 11 No. 179

P25.00 NATIONWIDE | 5 SECTIONS 32 PAGES | 7 DAYS A WEEK

GO!!!
www.businessmirror.com.ph

GOV'T IDLE LOTS SHOULD BE USED AS SOCIALIZED-HOUSING SITES

'In-city relocation best way to address housing backlog'

Business Mirror @ 10



By JOVEE MARIE N. DELA CRUZ

LAWMAKERS and multisector stakeholders are one in saying that the way forward to addressing the rising housing backlog

5.5M

The estimated housing backlog in the country today

BM Reports
Extra

THE MARCOS CHRONICLES



Offshore dealings thrust into Panama Papers spotlight

HSBC Holdings banks hardest-hit amid on customers' illicit e now starring in a nts detailing how they thousands of offshore

through reputable financial institutions, which are bound by so-called Know Your Customer laws, the group quoted her as saying. Asked about details of the ICIJ story, UBS Spokesman Marsha Askins said the bank decided to end the relationship with the law firm years ago.

"Your question refers to services concerning the setup and administration of offshore companies using third-party providers, which UBS proactively decided to discontinue in 2010," she said in a written statement. "This process happened in stages and has been completed."

HSBC, in a statement, said it works closely with authorities to fight financial crime and implement sanctions.

"Our policy is clear that offshore accounts can only remain open either where clients have been thoroughly vetted [including due diligence, Know Your Customer, source of wealth, and tax transparency checks], where authorities ask us to maintain an account for the purposes of monitoring activity, or where an account has been frozen based on sanctions obligations," the bank said.

Journalists working with the consortium pored through millions of pages of documents leaked from the law firm to piece together what they alleged was a global web of shell companies that helped hide wealth of world leaders and criminals, among others. The records outlined the creation of more than 200,000 offshore companies in all, according to the ICIJ. Almost 15,600 shells were registered by more than 500 banks in recent decades, according to its analysis.

While companies that shield owners' identities can be used legally, they can also be tools for hiding assets, laundering funds or evading taxes. The US, among other countries, require banks doing business in the country to perform certain levels of due diligence on their clients to understand who the beneficial owners of such structures may be. Still, the revelations may complicate relations between banks in developed nations and those in still developing countries, said Peter Hahn, a professor at London's Institute of Financial Services.

"Leading bank chairman and CEOs will have a tough night's sleep worrying and wondering about whether their organization have touched these deals regardless of whether their activities were legal or how long ago they happened," Hahn said. Bloomberg News

Probe banks scandal spreads

ate with any legal probe resulting from the data leak, Agence France-Presse reported. The reports allege that politicians, criminals and celebrities worldwide have used banks and shell companies to hide their finances. "This leak is proof that, despite explicit bank-

Republic of the Philippines
ENERGY REGULATORY COMMISSION
San Miguel Avenue, Pasig City

IN THE MATTER OF THE
APPLICATION FOR APPROVAL
OF THE EMERGENCY
INSTALLATION OF ONE (1) 83
MVA POWER TRANSFORMER
AT NORTH PORT SUBSTATION,

ERC CASE NO. _____

MANILA ELECTRIC COMPANY
(MERALCO),

Applicant.

x-----x

APPLICATION

Applicant MANILA ELECTRIC COMPANY (MERALCO), through the undersigned counsel, and to this Honorable Commission, most respectfully avers that:

1. Applicant is a private corporation duly organized and existing under the laws of the Republic of the Philippines, with principal office located at Lopez Building, Ortigas Avenue, Barangay Ugong, Pasig City. It may be served with notices and other processes of this Honorable Commission through its undersigned counsel at the address indicated herein.

2. Applicant has a legislative franchise to construct, operate and maintain an electric power distribution system for the conveyance of electric power to the end-users in the cities and municipalities of Metro Manila, Bulacan, Cavite and Rizal, and certain cities/municipalities/barangays in Batangas, Laguna, Quezon and Pampanga, pursuant to Republic Act No. 9209.

3. Applicant seeks the Honorable Commission's approval of its emergency installation of one (1) 83 MVA, 115 kV-34.5 kV, three (3)-phase power transformer with On-Load Tap Changer (OLTC) for the replacement of the North Port Substation's defective Power Transformer Bank No. 2.

4. The Application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled: "Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.

5. However, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

BACKGROUND

6. The North Port Substation is located at Lot 1, Tayuman, Tondo, Manila. The said substation has six (6) Power Transformer Banks. Power Transformer Bank Nos. 1, 2 and 6 have a rating of 115kV-34.5kV, while the remaining banks (3, 4 and 5) have a 34.5kV-6.24kV rating. However, the Power Transformer Bank Nos. 3, 4 and 5 are only drawing power from Bank Nos. 1, 2 and 6.

7. On 15 December 2015, North Port Power Transformer Bank No. 2 was tripped out by transformer differential relay with targets of phases B & C due to exploded high side bushings (H1 & H2).

8. Thus, the power transformer was immediately subjected to initial test on 16 December 2015 that showed relatively low insulation resistance measured on primary to ground (H-G) and carbonized insulating oil on the OLTC and main tank. The test also indicated that there was a need to replace the damaged bushings.

9. On 20 December 2015, Winding Resistance and Turn Ratio test was performed on the power transformer without primary and secondary bushings. The results showed relatively low winding resistance on H1-H0 windings and low % turn ratio on H0H1-X0X1 windings, and confirmed that there was a need to replace the bushings and recondition the insulating oil.

10. Accordingly, the tripping out of North Port Power Transformer Bank No. 2 necessitated the transfer of its load to adjacent power transformers with 115 kV-34.5 kV rating namely, North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2.

11. With such a setup, the North Port Bank No. 6 was operating above critical level at 80.1% that can adversely affect the quality of electric service to the various major and vital customers in the area such as University of Sto. Tomas, Chinese General Hospital, Department of Public Works and Highways, Asian Terminals, Inc., Asia Brewery, Inc., Philippine Ports Authority, Philippine National Railways and the City Government of Manila.

12. Considering the critical effect of shifting the load of the power transformer to the adjacent North Port Bank No. 6, a stop gap measure had to be undertaken. Applicant had to use an available 83 MVA Power Transformer and temporarily install the same to replace the North Port Power Transformer Bank No. 2 so that the latter power transformer can be pulled out for further testing. The new Power Transformer was energized on 26 January 2016. Shown below are the loadings of the affected power transformers with and without the replacement of North Port Power Transformer Bank No. 2.

Table 1: Without Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	80.1%

customers will not be burdened with higher line losses resulting from emergency load shifting.

17. The cost of the emergency replacement including the cost of the 83 MVA, 115 kV-34.5 kV, three-phase power transformer with OLTC installed at North Port Substation is FIFTY FOUR MILLION SEVEN HUNDRED SIXTY TWO THOUSAND THREE HUNDRED EIGHTY EIGHT & 98/100 PESOS (Php54,762,388.98). This amount also includes costs of transformer oil, taxes, duties, brokerage, trucking services and installation.

18. In further support of the Application, attached hereto are the following documents:

- Annex "A" - Emergency CAPEX Project Information Summary with supporting documents: (i) Technical and Economic Analysis; (ii) Cost Estimates; (c) Expenditure Summary; (iii) Cost Benefit Analysis Calculation; and (iv) Gantt Chart;
- Annex "B" - Documents showing the results of tests conducted on Power Transformer Bank No.2; and
- Annex "C" - Judicial Affidavit of Engr. Jose Mari P. Melendres, Vice President and Head of Applicant's Sub-transmission Services Office.

PRAYER

WHEREFORE, it is respectfully prayed to this Honorable Commission that the emergency installation of one (1) 83 MVA, 115 kV - 34.5 kV, three-phase power transformer with OLTC at the North Port Substation be APPROVED.

Other relief just and equitable under the premises are likewise prayed for.

Pasig City, 04 April 2016.

MANILA ELECTRIC COMPANY

Applicant

Lopez Building,
Ortigas Avenue,
Barangay Ugong, Pasig City

By:

JOSE RONALDO V. VALLES
Roll of Attorneys No. 42281

PTR No. 1473408; 01/21/16; Pasig City

IBP No. 1023722; 01/08/16; RSM

MCLE Compliance No. V-0002590; 9 June 2014

FRANCIS DINO S. ANTONIO

Counsel for Applicant

Roll of Attorneys No. 48145

PTR No. 1473407; 01/21/16; Pasig City

IBP No. 1023724; 01/08/16; RSM

MCLE Compliance No. V-0004608; 6 November 2014

HAZEL ROSE B. SEE

Counsel for Applicant

Roll of Attorneys No. 48265

PTR No. 1473408; 01/21/16; Pasig City

IBP LRN No. 06460; 1/16/07; QC

MCLE Compliance No. V-0002589; 9 June 2014

MONICA M. MARTIN

Counsel for Applicant

Roll of Attorneys No. 55693

PTR No. 1473411; 01/21/16; Pasig City

IBP No. 1023728; 01/08/16; RSM

MCLE Compliance No. V-0002591; 9 June 2014

7th Floor, Lopez Building
Ortigas Avenue, Barangay Ugong, Pasig City
Tel no. 1622-2260; Fax No: 1622-3550
Email: regulatory.legal.admin@meralco.com.ph

Republic of the Philippines)
City of Pasig) S.S.

VERIFICATION
and CERTIFICATION ON NON-FORUM SHOPPING

I, RONNIE L. APEROCHO, of legal age, married, with office address at Manila Electric Company, Technical Services Building, Meralco Center, Ortigas Avenue, Pasig City, hereby state under oath that:

1. I am the First Vice President and Head of Networks, Manila Electric Company, who is authorized to represent it in this

through reputable financial institutions, which are bound by so-called Know Your Customer laws, the group quoted her as saying.

Asked about details of the ICIJ story, UBS Spokesman Marsha Askins said the bank decided to end the relationship with the law firm years ago.

"Your question refers to services concerning the setup and administration of offshore companies using third-party providers, which UBS proactively decided to discontinue in 2010," she said in a written statement. "This process happened in stages and has been completed."

HSBC, in a statement, said it works closely with authorities to fight financial crime and implement sanctions.

"Our policy is clear that offshore accounts can only remain open either where clients have been thoroughly vetted [including due diligence, Know Your Customer, source of wealth, and tax transparency checks], where authorities ask us to maintain an account for the purposes of monitoring activity, or where an account has been frozen based on sanctions obligations," the bank said.

Journalists working with the consortium pored through millions of pages of documents leaked from the law firm to piece together what they alleged was a global web of shell companies that helped hide wealth of world leaders and criminals, among others. The records outlined the creation of more than 200,000 offshore companies in all, according to the ICIJ. Almost 15,600 shells were registered by more than 500 banks in recent decades, according to its analysis.

While companies that shield owners' identities can be used legally, they can also be tools for hiding assets, laundering funds or evading taxes. The US, among other countries, requires banks doing business in the country to perform certain levels of due diligence on their clients to understand who the beneficial owners of such structures may be. Still, the revelations may complicate relations between banks in developed nations and those in still developing countries, said Peter Hahn, a professor at London's Institute of Financial Services.

"Leading bank chairman and CEOs will have a tough night's sleep worrying and wondering about whether their organization have upheld these deals regardless of whether their activities were legal or how long ago they happened," Hahn said. *Bloomberg News*

probe banks and spreads

with any legal probe resulting from the leak, Agence France-Presse reported. Reports allege that politicians, criminals and celebrities worldwide have used banks and shell companies to hide their finances.

"This leak is proof that, despite explicit bank laws against tax evasion, criminal uses and money laundering, the global offshore shell business remains open for the wealthy well connected," Mark Williams, a lecturer at Aston University and author of *Uncontrolled*, a book on the rise and fall of Lehman Brothers Holdings Inc., said in an email. "More aggressive enforcement needs to be exercised against those firms that aid and abet."

Finma, the Swiss regulator, said in an email it intends to "clarify" the extent to which Swiss banks may have used the services of Mossack Fonseca and whether banks offered Swiss provisions or banking supervisory rules. Shell companies and offshore investments can be legal.

More than 500 banks in all requested that Mossack Fonseca and a predecessor firm create companies for their clients from 1977 to the end of 2015, according to the report. These included HSBC Group Plc, Credit Suisse and UBS AG, according to a summary filed by the group. The banks, in comments, denied any wrongdoing.

The Dutch central bank, which is looking for trust companies and the potential for money laundering in professional soccer, also made the Panama files into account in the report, the Finance Ministry said. *Bloomberg News*

Applicant.

APPLICATION

Applicant **MANILA ELECTRIC COMPANY (MERALCO)**, through the undersigned counsel, and to this Honorable Commission, most respectfully avers that:

1. Applicant is a private corporation duly organized and existing under the laws of the Republic of the Philippines, with principal office located at Lopez Building, Ortigas Avenue, Barangay Ugong, Pasig City. It may be served with notices and other processes of this Honorable Commission through its undersigned counsel at the address indicated herein.

2. Applicant has a legislative franchise to construct, operate and maintain an electric power distribution system for the conveyance of electric power to the end-users in the cities and municipalities of Metro Manila; Bulacan, Cavite and Rizal, and certain cities/municipalities/barangays in Batangas, Laguna, Quezon and Pampanga, pursuant to Republic Act No. 9209.

3. Applicant seeks the Honorable Commission's approval of its emergency installation of one (1) 83 MVA, 115 kV-34.5 kV, three (3)-phase power transformer with On-Load Tap Changer (OLTC) for the replacement of the North Port Substation's defective Power Transformer Bank No. 2.

4. The Application is being filed pursuant to the Honorable Commission's Resolution No. 26, Series of 2009, entitled: "Resolution Amending the Rules for Approval of Regulated Entities' Capital Expenditure Projects". Emergency Capital Expenditure projects are those that require immediate implementation during an event that is not a force majeure or fortuitous event in order to maintain safe, reliable, secure and efficient operation of the power system.

5. However, for purposes of recovering the capital cost of the emergency project through the DU's rates, the same will go through the process of evaluation by the Honorable Commission during the regulatory reset of the DU, unless there is basis for a rate-reopening in the current regulatory period, in accordance with the Rules for the Setting of Distribution Wheeling Rates (RDWR) for DUs.

BACKGROUND

6. The North Port Substation is located at Lot 1, Tayuman, Tondo, Manila. The said substation has six (6) Power Transformer Banks. Power Transformer Bank Nos. 1, 2 and 6 have a rating of 115kV-34.5kV, while the remaining banks (3, 4 and 5) have a 34.5kV-6.24kV rating. However, the Power Transformer Bank Nos. 3, 4 and 5 are only drawing power from Bank Nos. 1, 2 and 6.

7. On 15 December 2015, North Port Power Transformer Bank No. 2 was tripped out by transformer differential relay with targets of phases B & C due to exploded high side bushings (H1 & H2).

8. Thus, the power transformer was immediately subjected to initial test on 16 December 2015 that showed relatively low insulation resistance measured on primary to ground (H-G) and carbonized insulating oil on the OLTC and main tank. The test also indicated that there was a need to replace the damaged bushings.

9. On 20 December 2015, Winding Resistance and Turn Ratio test was performed on the power transformer without primary and secondary bushings. The results showed relatively low winding resistance on H1-H0 windings and low % turn ratio on H0H1-X0X1 windings, and confirmed that there was a need to replace the bushings and recondition the insulating oil.

10. Accordingly, the tripping out of North Port Power Transformer Bank No. 2 necessitated the transfer of its load to adjacent power transformers with 115 kV-34.5 kV rating namely, North Port 133 MVA Bank No. 6 and Tutuban 83 MVA Bank No. 2.

11. With such a setup, the North Port Bank No. 6 was operating above critical level at 80.1% that can adversely affect the quality of electric service to the various major and vital customers in the area such as University of Sto. Tomas, Chinese General Hospital, Department of Public Works and Highways, Asian Terminals, Inc., Asia Brewery, Inc., Philippine Ports Authority, Philippine National Railways and the City Government of Manila.

12. Considering the critical effect of shifting the load of the power transformer to the adjacent North Port Bank No. 6, a stop gap measure had to be undertaken. Applicant had to use an available 83 MVA Power Transformer and temporarily install the same to replace the North Port Power Transformer Bank No. 2 so that the latter power transformer can be pulled out for further testing. The new Power Transformer was energized on 26 January 2016. Shown below are the loadings of the affected power transformers with and without the replacement of North Port Power Transformer Bank No. 2.

Table 1: Without Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	80.1%
Loading of Tutuban 83-MVA Bank No. 2	55.0%
System Loss	8,479,172 kWh

Table 2: With Project

Parameter Under Consideration	
Loading of North Port 133-MVA Bank No. 6	37.1%
Loading of Tutuban 83-MVA Bank No. 2	45.3%
Loading of North Port 83-MVA Bank No. 2	52.6%
System Loss	8,229,062 kWh

13. The new 83 MVA Power Transformer had to be temporarily installed in order to normalize the level of quality of electric service of the affected customers in the City of Manila.

14. Several preparatory activities had to be undertaken before the final testing of the replaced power transformer such as, fabrication of adapter for bushings, draining of carbonized insulating oil, and installation of adapters and replacement of test bushings and sealing.

15. On 24 February 2016, a final test was conducted on the power transformer with replaced bushings. The results of the final test were released on 03 March 2016 where the Power Transformer Bank No. 2 was declared defective since the measured turns ratio of 90.01% on H0, H1-X0X1 windings exceeded the limits due to turn short on H0H1 winding. The Dissolved Gas Analysis (DGA) also showed high generation of combustible gases at the time of fault as verified in the field and laboratory equipment. At this point, the new 83 MVA Power Transformer that was earlier temporarily installed was considered a permanent replacement.

16. It was extremely important for the Applicant to immediately implement the replacement of the defective transformer at North Port Substation in order to serve and promote public interest and welfare in a more suitable and adequate manner, as power interruptions in the affected areas will be avoided and affected

Annex "A" - Emergency CAPEX Project Information Summary with supporting documents: (i) Technical and Economic Analysis; (ii) Cost Estimates; (c) Expenditure Summary; (iii) Cost Benefit Analysis Calculation; and (iv) Gantt Chart;

Annex "B" - Documents showing the results of tests conducted on Power Transformer Bank No.2; and

Annex "C" - Judicial Affidavit of Engr. Jose Mari P. Melendres, Vice President and Head of Applicant's Sub-transmission Services Office.

PRAYER

WHEREFORE, it is respectfully prayed to this Honorable Commission that the emergency installation of one (1) 83 MVA, 115 kV - 34.5 kV, three-phase power transformer with OLTC at the North Port Substation be APPROVED.

Other relief just and equitable under the premises are likewise prayed for.

Pasig City, 04 April 2016.

MANILA ELECTRIC COMPANY

Applicant
Lopez Building,
Ortigas Avenue,
Barangay Ugong, Pasig City

By:

JOSE RONALDO V. VALLES
Roll of Attorneys No. 42281

PTR No. 1473406; 01/21/16; Pasig City

IBP No. 1023722; 01/08/16; RSM

MCLE Compliance No. V-0002590; 9 June 2014

FRANCIS DINO S. ANTONIO

Counsel for Applicant

Roll of Attorneys No. 48145

PTR No. 1473407; 01/21/16; Pasig City

IBP No. 1023724; 01/08/16; RSM

MCLE Compliance No. V-0004608; 6 November 2014

HAZEL ROSE B. SEE

Counsel for Applicant

Roll of Attorneys No. 48265

PTR No. 1473408; 01/21/16; Pasig City

IBP LRN No. 06460; 1/16/07; QC

MCLE Compliance No. V-0002589; 9 June 2014

MONIKA M. MARTIN

Counsel for Applicant

Roll of Attorneys No. 55693

PTR No. 1473411; 01/21/16; Pasig City

IBP No. 1023726; 01/08/16; RSM

MCLE Compliance No. V-0002591; 9 June 2014

7th Floor, Lopez Building

Ortigas Avenue, Barangay Ugong, Pasig City

Tel no. 1622-2260; Fax No: 1622-3550

Email: regulatory.legal.admin@meralco.com.ph

Republic of the Philippines)

City of Pasig

) S.S.

VERIFICATION

and CERTIFICATION ON NON-FORUM SHOPPING

I, **RONNIE L. APEROCHO**, of legal age, married, with office address at Manila Electric Company, Technical Services Building, Meralco Center, Ortigas Avenue, Pasig City, hereby state under oath that:

1. I am the First Vice President and Head of Networks, Manila Electric Company, who is authorized to represent it in this Application as per the attached Secretary's Certificate (Annex "D");

2. I have caused the preparation of the instant Application and read the contents thereof, and I attest that the allegations herein contained are true and correct based on my personal knowledge and on authentic records;

3. I have not commenced any other action or proceeding involving the same issues in the Supreme Court, the Court of Appeals or any court, tribunal, or quasi-judicial agency and, to the best of my knowledge, no such other action or claim is pending therein; and,

4. Should I hereinafter learn that the same or a similar action or claim has been filed or is pending in the Supreme Court, the Court of Appeals or any court, tribunal, or quasi-judicial agency, I shall report the said fact within five (5) days from discovery thereof to this Honorable Commission.

RONNIE L. APEROCHO
Affiant

SUBSCRIBED and SWORN to before me this ____ day of APR 05 2016, 2016, affiant exhibited to me his SSS ID No. 03-15624854 issued in the Philippines.

Doc. No. 260

Page No. 17

Book No. 11

Series of 2016.

As per IEEE Standard C57.12.00-2008, acceptable tolerance values for winding ratios should be within $\pm 0.5\%$ of the nameplate voltages.

ACCOUNTABLE FORM No. 51
Revised January, 1992

(ORIGINAL)

 ERC ENERGY REGULATORY COMMISSION - PHILIPPINES	Official Receipt of the Republic of the Philippines		
	0006496 No. 0006496		
	Date 4/8/2016		
Agency ENERGY REGULATORY COMMISSION		Fund 101	
Payor Manila Electric Company (MERALCO)			
Nature of Collection	Account Code	Amount	
Filing Fee	4-02-01-130	₱ 700.00	
UFLRF	2-00-00-000	10.00	
2016 SCMD 0042 TOTAL		₱ 710.00	
Amount in Words seven hundred ten pesos only			
☒ Cash	Drawee Bank	Number	Date
☐ Check			
☐ Money Order			
Received the amount stated above. MILA A. MIRANDA Cashier II Collecting Officer			
NOTE: Write the number and date of this receipt on the back of check or money order received.			



STATEMENT OF ACCOUNT

ENERGY REGULATORY COMMISSION

<http://www.erc.gov.ph>

Pacific Center Building

San Miguel Ave, Pasig City

Phone 689-5372 loc.5378 Fax 638-4519

STATEMENT NO : 2016-SCMD-0913

BILL TO : MANILA ELECTRIC COMPANY (MERALCO)
Ortigas Avenue, Pasig City

DATE ISSUED : April 07, 2016

DUE DATE : April 12, 2016

PARTICULARS	AMOUNT
In the matter of the application for Approval of the Emergency Installation of one (1) 83 MVA Power Transformer at North Port S/S(Revenue Code: 4-02-01-010)	700.00
UPLRF(Revenue Code: 4-02-01-010)	10.00
TOTAL AMOUNT (Php)	710.00

SEVEN HUNDRED TEN PESOS

Approved by :

ATTY. ALFREDO P. VERGARA JR.

OIC, LEGAL SERVICE

Approved by :

ATTY. FLORESINDA B. DIGAL

DIRECTOR III, ROS

Attested by :

ZYWEEN A. SEVILLEN

BILLING SECTION